

Marine engine indicating

Charles Sutterley Linch

Digitized by Google





Digitized by Google

Library
of the
University of Wisconsin

Digitized by Google

Digitized by Google



Digitized by Google



Digitized by Google

MARINE

Engine Indicating

A Complete Treatise on the
Indicator and Indicator Diagrams,
as applied to Marine Engines

By

C. S. LINCH

Consulting and Constructing Naval Architect
and Marine Engineer

BOSTON:
AMERICAN STEAM GAUGE AND VALVE MFG. CO.
CAMDEN STREET
1910

Digitized by Google

Copyright, 1910, by
AMERICAN STEAM GAUGE & VALVE MFG. CO.

Digitized by Google

207688
DEC 26 1916
THT
.L63

69 5 7 1 75

CONTENTS

Chapter I

THE INDICATOR: Its Construction and Application.

Chapter II

DIAGRAMS: Their Computation and Combination.

Chapter III

DIAGRAMS: Modern Marine Engine Practice, from Single Cylinder to Four Cylinder Triple Expansion.

Chapter IV

VALVE DIAGRAMS: Their Construction and Use.

ADDENDA

PLATES showing Construction of Valve Diagrams: Combined Indicator Diagrams; Sectional Diagram of Modern Marine Engine and General Arrangement of Triple Expansion Engine — showing Reducing Motion, etc.

TABLES of $\frac{1+\text{Hyp. log. R}}{\text{R}}$, and Common Logarithms from 1 to 10,000.

Digitized by Google



HIS work is respectfully dedicated to my friend, R. B. Phillips, Treasurer and Manager of the American Steam Gauge & Valve Manufacturing Company, through whose Indicator, the American-Thompson, I have been able in all my professional work to accomplish most perfect results, and because it is my unqualified opinion that the facility and accuracy of this instrument is unequaled.

The importance of a perfect instrument in the expert work which I am constantly called upon to perform has compelled me to make this selection by thorough tests and the absence of all prejudice.

It is, therefore, in this same spirit that I give credit where credit is due.

CHARLES S. LINCH.

Digitized by Google

FOREWORD

It has been the writer's observation—and doubtless the reader's as well—that text books written on the subject of indicators are invariably based on experiences with stationary engines.

That a thorough treatise on this all-important device, with special reference to its application to marine engines is greatly needed, is obvious to every marine engineer, and this work is undertaken expressly to meet that need, particular care being exercised, especially in all the analyses of diagrams, to be lucid and concise, rather than elaborately technical.

The history of the indicator has been purposely avoided, as being superfluous, the writer deeming it of far greater importance to confine himself especially to a complete description of the most accurate of the modern type.

In the analysis of diagrams it is important, when adjustment of valves must be made, to be able to construct and discuss the valve diagrams, and the object here has been to explain the methods in a clear manner, eliminating all geometrical proof.

All diagrams shown were taken, in actual practice, from modern marine engines.

If by writing this work I have been of help to those who are seeking this knowledge I shall feel amply repaid.

I am greatly indebted to Mr. Harry Vansciver, Division Superintendent, Merchants and Miners Transportation Company, for the analysis of the steamship "Tuscan."

THE AUTHOR.

Digitized by Google

MARINE INDICATING

CHAPTER I

THE steam engine indicator is an instrument which, through the proper functioning of its various parts, depicts upon paper a diagram which should accurately represent the various changes of pressure on one side of the piston of the steam engine during both the forward and return strokes.

Not only does the diagram show these variations, but it shows defects of design and adjustment, enabling the engineer to rectify faulty adjustment, and to determine any changes which would be conducive to increased economy and efficiency.



Fig. 1



Fig. 2

Fig. 1 shows an outside view and Fig. 2 a section through the incased spring instrument manufactured by the American Steam Gauge and Valve Manufacturing Company of Boston, Mass., known to the engineering profession as the American Thompson Improved Indicator. This instrument consists of an outer cylinder or casing into which is secured the liner in which the piston travels. This liner is made of a special hard bronze composition, which differs slightly from the composition of which the piston is made. The object of having the liner and piston made of different compositions is to obtain a uniform expansion. The space between the outer casing and liner forms a suitable steam jacket. The bracket which carries the paper drum

Digitized by Google

spindle and the casing are one casting. This bracket is of sufficient dimensions to form a very rigid and strong appendage, the distance between the center of cylinder and center of drum spindle being only sufficient to insure the pencil striking the proper position on the paper drum in a vertical plane. The pencil motion being three to one, this distance is therefore such that danger of bending with the light construction is eliminated.

The spindle is of steel and, as will be observed, is screwed into the bracket and shouldered; the end extending through the bracket carries the guide pulley bracket and wing nut.

The bearing surface for the paper drum pulley is large, insuring ample bearing surface.



Fig. 2a

Piston

The piston Fig. 2*a* is of a special composition permitting a light construction yet possessing the requisite strength to prevent expansion from pressure, and is grooved for water packing.

The stem of the piston is constructed throughout of steel; the upper part consists of the sleeve "A" which acts as a guide passing through the cylinder cap. The piston "B" is connected with the pencil lever by a connecting rod "C" having a cross-head "D" at the upper end, which acts as a yoke, making connection with pencil lever by knurled-headed screw "G" connecting yoke with lever.

The cross-head is held in place by a small hexagonal lock nut "E." The top of the connecting rod is threaded, permitting the raising or lowering of the cross-head, thus securing adjustment of the atmospheric line on the diagram.

Digitized by Google

The lower end of the connecting rod forms a socket which rests on a ball stud "F," which, in turn, is adjustable in the piston stem. The result is a perfect ball and socket joint, and provides means for taking up any lost motion.

The parallel motion is made of drop-forged, compressed steel, and is carried on a sleeve, which is fitted to the upper end of the steam cylinder, being held in place by the milled cylinder cap. The pencil lever has a vertical motion in the ratio of three to one, and is guided by a short connecting link, which vibrates about a pin carried by the post. The post is carried by an arm cast with the sleeve. A link connecting the pencil lever and vibrating about a center carried also on the sleeve, acts as a fulcrum. The yoke as mentioned connects the piston with the pencil lever.

This construction insures an absolute straight line for pressure line; any inclination of this line in any diagram can therefore be attributed to other causes.

The end of the pencil lever is split, thus forming a spring sleeve to take the lead or German silver points.

Through the arm of the sleeve there is drilled and tapped a hole for the adjusting screw, as shown.

On the bracket carrying the paper drum there is fitted a stop to prevent injury to pencil lever, by introducing excessive friction on card, from too great pressure of lead against paper. The sleeve being free to turn, the adjustment of adjusting screw determines the pressure put on pencil.

The connection of the indicator to the straight or three-way cocks is through the medium of a swivel coupling, having a tailpiece which is secured into the lower end of the cylinder. This tailpiece is provided with a shoulder against which the inner flange of the coupling proper rests; this forms a perfect swivel coupling and is a decided improvement over those having right and left hand thread.

Springs

The springs are made of the finest quality steel wire, and are wound on a mandrel and tempered in the most scientific manner. This mandrel on which all springs are wound is from four to four and one-half threads per inch. In the springs furnished with these instruments there is therefore more wire to each spring, and hence less strain than if wound on mandrels of two and three threads per inch. The heads of the springs are of brass, drilled and tapped to receive the piston and cylinder cap.

In securing the heads to the spring, no solder is used. The cut (Fig. 2*a*) shows clearly the construction.

Digitized by Google

Paper Drum

The paper drum is of brass tubing, turned true, faced, capped and bored for pulley, and is light, yet possessing requisite strength.

The tension spring is carried by the drum pulley, the spring case forming an integral part of same. The tension of the spring is adjusted by turning the knurled cap, the cap is prevented from slipping by friction of the knurled lock nut. The construction is clearly shown in Fig. 3.



Fig. 3

Fig. 6 shows a section through the paper drum of an instrument fitted with detent motion.

Digitized by Google

Leading Pulley

The leading pulley shown in Fig. 4 consists of a wheel which is carried on an adjustable bearing. This bearing as shown is carried by a stand which is cast with a palm, the palm is drilled so that it can pass over the extension of the paper drum spindle. This palm is clamped by the wing nut as shown in Figs. 1 and 2.

The cord from the grooved wheel of paper drum is passed through the hole in the pulley sleeve, thence passing over the pulley to the driving cord from reducing motion. After the leading pulley is adjusted it is clamped by the knurled head screw as shown. It will be noted that the cord from paper cylinder is always tangent to the groove in leading pulley.



Fig. 4

Detent Motion

Fig. 5 shows the instrument fitted with detent motion, and Fig. 6 shows a section through the paper drum of this instrument. It will be noticed that in order to stop the paper cylinder it is only necessary to move lever "A" in the direction traveled by the paper cylinder until the cylinder releases itself. The cylinder will then remain stationary, at which time the completed diagram can be removed and a new card substituted. The lever must be returned to its original position.

Looking now at Fig. 3 we see that the pin which is carried by spring when in position as shown, drives the paper cylinder. This spring is drawn down when lever is pushed over, hence withdrawing pin, thus disengaging the paper drum from pulley. When lever is again thrown back, the spring is free to push pin into position as soon as the hole in drum and drum pulley coincide. Therefore, when new card has been put on drum, turn the milled rim "B" on top of drum forward until it catches. The drum will then be in gear, and hence will revolve in usual manner.

Digitized by Google

Outside Spring Instrument

The outside spring instrument shown in Fig. 6*a* is precisely the same as the incased spring instrument as far as construction and materials are concerned, except that the spring is not subject to variations of temperature, and is visible at all times. The pencil lever is yoked to straddle the spring, and two links are used from pencil lever to post, and to collar on piston rod, otherwise the details are the same.

It will be noted that the bracket which carries the paper drum is drilled and tapped for one of the standards of which there are two, and that there is a lug cast on the cylinder casing which carries the other standard. The standards are fitted at the top with a separator which is drilled and tapped for a long screw to which one end of the spring connects. The piston rod passes through the cylinder cap, and is flanged



Fig. 5

Digitized by Google

at the upper end. This flange forms a shoulder on which the collar carrying the two links connecting the pencil lever rests. On top of this collar is carried the spring base which is provided with four holes in which is inserted a pin for holding piston-rod from turning when spring is to be inserted or removed.



Fig. 6

Reducing Wheel

It frequently happens that engines are not fitted with reducing motions, and when such cases occur we must resort to the use of reducing wheels.

The reducing wheel shown in Fig. 7 is made of aluminum, brass, and steel, combining lightness and strength, two very essential features. The wheel drum from which the cord passes to the cross-head arm or any other arrangement for driving, is $2\frac{3}{4}$ inches in diameter, and is made of aluminum. The coil spring for the take-up is in a separate case and connected by a three to one gear with the cord-wheel spindle, so that while the aluminum cord-wheel makes three revolutions, the spring makes but one. The spring can be adjusted to any desired tension to keep the cord taut on return stroke. The cord-wheel revolves on a steel screw, the thread of which has the same pitch as the cord, so that when the cord is drawn out the wheel travels as it revolves. Thus the cord is wound smoothly on the drum and passes straight through the guide pulley.

Digitized by Google

In using the reducing wheel on the indicator, remove the leading pulley (see Fig. 8) from the indicator and put the wheel on in place of it. Pass the drum cord around the small disk through the hole and under the holder. Observe that the cord is always wound round bushing or



Fig. 6*a*

disk from the left. Before hooking in, see that cord on wheel and indicator is taut at shortest part of stroke and that it will pull out a little further than longest part of stroke.

The cord from reducing wheel to cross-head must run in a straight line.

Digitized by Google

In unhooking the cord do not permit it to run unchecked but allow it to run slowly until the stop reaches the guide pulley.



Fig. 7



Fig. 8

Bushings are furnished of various sizes for small disks so that diagrams can be taken for any stroke up to 72″.

Having described the construction of the instrument we will now take up the subject of its care and adjustment.

Care

Before using an indicator take it apart and thoroughly clean and oil it. Starting at the steam cylinder, remove the small knurled-head screw connecting the pencil lever with the connecting rod. Unscrew the cylinder cap and withdraw the piston and parallel motion by holding the

Digitized by Google

instrument with one hand, and with thumb and finger lift up the sleeve. After the piston has been withdrawn, with one hand grasp the piston and with thumb and finger turn cylinder cap, unscrewing same from spring. Now unscrew spring from piston. Wipe out cylinder with clean waste, and see that all dirt, if any, is removed. Whilst the piston is out of instrument it is as well to look after the paper drum and its appendages.

Remove the knurled-nut "F" (see Fig. 6); take off the paper drum, then with the wire clip (which is furnished with each instrument fitted with detent motion) remove the auxiliary spring case "H" by catching the end of the clip in the notches; then remove the spring and inner sleeve "I." After cleaning and oiling, replace the inner sleeve "I" by inserting it into the drum so that the pin on the outside of the sleeve will enter the slot inside of drum bearing and turn it until it comes to a stop; then with the wire clip catch hold of the auxiliary spring holder "H" and give the auxiliary spring "E" a tension of about ¼ turn, catching the points on the spring case "H" into the slots provided for them.

Whilst we have the auxiliary spring case and sleeve out it is necessary to be sure that the spindle is oiled, therefore, remove the lock nut, thus releasing the spring tension, then with screw driver (furnished with each instrument) remove the small screw on spindle, then remove lock nut, and lift off the paper drum pulley. Oil thoroughly and replace the pulley, and turn knurled cap, giving the spring the required tension and lock with lock nut; replace screw in spindle, thence replace paper drum, and finally the knurled nut "F."

Having selected the spring we wish to use, screw same to cylinder cap; next screw on the piston. Oil the piston with good cylinder oil and replace piston in cylinder; screw on the cylinder cap, and last, connect the pencil lever with connecting rod by inserting and gently screwing up the screw through yoke. Care must be exercised, and it is important to remember that the pencil lever must be disconnected first, and connected last. With the porpoise or watch oil (furnished with each instrument) oil the joints in the parallel motion. It is to be remembered that all parts of the instrument except the piston must not be oiled with any other oil except the kind furnished, and only a good cylinder oil is to be used on piston.

Adjustment

Great care must be exercised in adjusting the instrument. For the adjustment of the paper drum spring, the tension on this must not be greater than is absolutely required. To determine just what this should be in any case, we must, with the engine turning very slow, take a diagram; then with engine turning maximum number of revolutions,

Digitized by Google

take another diagram; with a pair of dividers measure the length of the diagrams; should the diagram taken with maximum turns show a difference in length the spring must be adjusted to give the same length. The tension on the spring will of course be greater for fast and less for slow turning engines, hence the necessity of adjusting to suit conditions.

The adjustment of the outside instrument is precisely the same as for incased spring.

The adjustment of the pencil is controlled by the adjusting screw, and should be such as to give as light a line consistent with clearness.

A diagram can very readily be distorted by excessive friction, and the data from same absolutely useless; beside the injury to the pencil lever.

After the instrument is removed from engine it should again be taken apart and all parts thoroughly cleaned and oiled; the cylinder thoroughly dried out and all water of condensation removed from jacket. The springs should be thoroughly cleaned, dried, and oiled with porpoise oil. The piston should be oiled with porpoise oil when instrument is to be put away. All parts which are concealed, such as the ball and socket joint, should be wiped out by forcing a thin piece of linen down the sleeve with a toothpick, and after same has been dried it should be oiled. The indicator is a very delicate instrument, and upon its proper care depends its accuracy, hence its value, and too much attention cannot be bestowed upon its care and adjustment.

Testing the Instrument

Examine the instrument and try each part separately and see that it works smoothly. Put the instrument together without the spring. Hold the instrument by the steam cylinder in the right hand, and with thumb and finger raise the pencil lever very carefully to full extent of travel.

Place the thumb of right hand under the steam connection, release the pencil lever. Now slightly release the thumb over steam connection and note the fall of the piston. Repeat this until piston has traveled full stroke. The piston should fall freely every time the thumb is withdrawn. If however the piston moves in a sluggish manner, there is then excessive friction. If on the contrary it falls freely we know that the friction is a minimum. Now withdraw the piston in the manner above described and put in the desired spring. Oil piston and connect up the instrument. Before placing instrument on cylinder or indicator cocks, blow out thoroughly the pipes and connections; too much care cannot be exercised in making sure that the connections are thoroughly cleansed, as any grit or dirt is not only liable to cut the cylinder but it will affect the diagram as well.

Digitized by Google

Changing Indicator Springs

The remarks made under the head of care and adjustment explain the method sufficiently, and in this connection it is only necessary to add: Care must be taken to see that the spring is shouldered in cap, and full down on piston. In removing the spring on the outside spring instrument unscrew the knurled nut at the top until the end of the spring is released. Then, turn the spring until it is free from the base. The piston is prevented from turning whilst removing the spring by inserting the pin (furnished with the instrument) in holes in the spring base.

The adjustment for atmospheric line when taking diagrams from condensing engine or low pressure cylinder of multiple expansion engines is made by the knurled nut at top.

Having described the instrument, its care and adjustment, we will now take up the connections to cylinders and reducing motions.

Cylinder Connections

Cylinders of marine engines are as a rule fitted with pipes and 3-way cocks.

The cylinders have bosses cast on them both top and bottom. The bosses are drilled through into the counter bore of the cylinder. The outer end is tapped for 1″ pipe; short nipples are screwed into the bosses, and ells used to connect with the side pipes. There is a great mistake in using ordinary ells, and wherever possible long-turn ells should be used, as the friction of steam is greatly reduced, and short bends should in all cases be eliminated.

The side pipes connect with a 3-way cock. Frequently angle valves are used in place of ells. This is very bad practice, and should not under any circumstance be countenanced.

When the pipes are to remain permanent fixtures, the 3-way cock is fitted with a screw cap, and when the instrument is not in commission, this cap should be screwed on to prevent any dirt, etc., getting into pipes.

The following should be remembered: Angle valves should never be used. The steam should be led to the instrument without any abrupt change of flow having to be encountered. In case the cylinder is not fitted with bosses, and holes have to be drilled in cylinder, the location of same must be such that the flow will not be disturbed, such as would occur by having holes opposite steam ports, as the inertia effect of the steam would affect diagram. Care must be exercised to see that cylinder head does not block the openings.

Where the stroke is very long, or pipes require a bend, short nipples with long turn ells looking up should be used; the straight-way cocks

Digitized by Google

can then be screwed into these ells, and the instrument will then be in a vertical plane. Never use the instrument in a horizontal plane, that is to say, do not screw straight-way cock into the boss.

Never if possible use ordinary ells, use only long turn ells, and close nipple, and use two instruments to each cylinder. If the engine is to be indicated then the data should be accurate, and if it is not worth assuring oneself that every precaution has been taken to make it so, then do not attempt to reason about the diagrams taken.

Never use any lead or litharge in connecting the pipes, as it is liable to get into the steam cylinder of the instrument and ruin it. In making up the connections, use oil on pipe threads. If after assembling there is a leak, same can be eliminated by winding strands of waste around the exposed thread. The distortion of diagrams caused by long pipes is clearly shown in diagrams taken from George W. Clyde and the pipe arrangement before and after alteration is shown in figs. 1 and 2 of insert.

Reducing Motions

The reducing motion is as a rule, especially on the larger engines, a permanent fixture, and designed to give a length of diagram to suit the ideas of the designer. It should be designed to give a diagram not less than 4 inches long, except in high speed engines where the drum is a smaller diameter and hence a shorter diagram is a necessity.

The design of the motion is not a standard. Plate 1 shows the usual type of reducing motion. This is simply an arm or lever driven from the cross-head pin of the main engine through the medium of a short link. The lever is pivoted to the housings and pin for leading cord is located to give a certain length of diagram.

Another method of reducing the piston travel consists of a steel rod, pivoted to the cross-head pin; on the housing is bolted a bracket, to which is pivoted a brass sleeve; this sleeve carries an adjustable pin, to which the leading cord is attached by moving this pin in or out; the length of diagram can be varied. Still another method, and one which is in every way superior, is to drive a lever which is pivoted to either the housing or column, from the cross-head pin through the medium of a link. At the other end of the lever is connected a light vertical rod guided at its upper end by a guide bolted to the cylinder foot. This rod has on its upper end an eye into which the hook on the drum cord can be engaged or disengaged. This eliminates a long leading or driving cord, and the connection is therefore very short. This is an ideal motion, and as it can be made very light, and yet possess the requisite rigidity, the effect of inertia is too small to take account of.

Digitized by Google

Taking Diagrams

Before putting instrument on straight or 3-way cocks, blow out the pipes thoroughly, make sure there is no dirt or grit left in them. Remove the piston and parallel motion and connect the instrument to cock. See that leads are correct, and after adjusting same, screw the instrument down tight.

Adjust now the length of leading or driving cord, exercising care to see that drum does not hit the stops in either up or down stroke. After this adjustment has been made, see that the hook on the drum cord is secured without any danger of slipping. See further that the loop or ring on driving cord is secured against slipping. Open now the steam connection and blow steam through the cylinder. After having done this make sure no dirt is in the cylinder. Oil the piston with good cylinder oil as directed, and insert it in cylinder, screw down the cylinder cap. Turn steam on the instrument and let it work until all condensation is eliminated, and instrument is thoroughly warmed. When dry steam blows through the reliefs we are prepared to take diagrams; see that the joints in parallel motion are oiled with porpoise oil, as explained in previous pages.

Placing Cards on Drum

Take a blank card and turn over one end about ¼ inch. Insert this under one of the clips on drum, then with thumb and finger draw card around drum and place the other end of card in the second clip. With thumb and finger pull card down on drum until it touches the shoulder at base of drum, flatten both edges out by passing the finger down the turned edges, exercise care and see that card is tight and smooth.

After the adjustment of the pencil has been made and the drum put in motion, press the adjusting screw against stop, and describe the atmospheric line first. Pull pencil away from paper and then open cock to steam, press screw against stop, and do not permit pencil to travel more than once around the card. In other words, hold only for one revolution as near as can be judged. If 3-way cock is used, mark on card whether taken from top or bottom. If top, then repeat the process for bottom. After diagrams have been taken the data should be inserted in their respective places on back of diagram as shown in fig. 9. Pressing adjusting screw against stop is the same as saying pressing pencil against card, as it is supposed that the adjustment has been made as directed.

Before taking diagrams it is well to try the instrument to determine whether drum spindle is true. This can be done, as follows:

Place card on paper drum, press adjusting screw against stop and pull drum cord slowly by hand, describing the atmospheric line, return

Digitized by Google

drum to first position, open cock to steam, and with drum stationary describe the pressure line, with cock still open, again pull the paper drum, describing a line parallel with atmospheric line, with drum held in this position shut off steam, leaving the pencil to descend, open cock to atmosphere and we shall have described a rectangle. Now the admission line should be at right angles to the atmospheric line, and the steam line shall be parallel with atmospheric line. If the admission line is not at right angles with the atmospheric line, the drum spindle is not true. It is very important that this condition shall obtain. This test can be made before placing instrument on engine by removing the spring and raising the pencil lever by hand. The former


AMERICAN STEAM GAUGE AND VALVE MFG. CO. BOSTON. CHICAGO. NEW YORK. EXCLUSIVE MANUFACTURERS OF American Thompson Improved Indicator. (Original "Thompson Indicator.")

DIAGRAM from M S. S. Admiral December 1st 1908
Diameter of Cylinder 18"
Length of stroke 30"
Revolutions per Minute 125
Pressure of Steam in lbs. in Boiler 160
Position of Throttle Valve wide Open
Vacuum per Gauge in inches 26
Temperature of Hot Well 120°
Scale of Spring 80
Inside Diameter of Feed Pipe 6"
" " Exhaust Pipe 8"
Piston Valves on H.P. Cyl
Engine 18"-28"-45"
Built by Wm Jones
Boiler Pressure designed 160
Barometer Reads 14.7 inches
Throttle
Regulator
REMARKS: Drop between Boiler and H.P. Piston 15 lbs. Wire drawing Excessive H.P. Piston Valve Leaks.

Fig. 9

method is to be preferred as the instrument has been warmed and everything in condition. If a test gauge can be attached at a point close to instrument, we can then determine whether our springs are correct. It is a good method to make this test before taking diagrams, and keeping the test card with other records.

Before proceeding to take up the subject of indicator diagrams, it will be well to give a description of the planimeter and its use.

Planimeter

The planimeter as its name implies is an instrument for the measuring the areas of irregular figures. There are several different types of instruments manufactured. We will, however, confine ourselves to the Amsler instrument as manufactured by the American Steam Gauge and Valve Manufacturing Company (see Fig. 10). This instrument consists of three essential parts, namely: A guide arm pivoted at "A" to the paper; a tracing arm which is hinged to the guiding-arm, and which carries the tracing point "B"; a measuring wheel "G," which carries a graduated cylindrical scale. There is also a vernier "E" for reading the scale on the wheel.

Digitized by Google

When in use the planimeter rests on the paper at three points. The pivot "A" which is a needle point pressed slightly into the paper; the edge of the measuring wheel "G," and the tracing point "B." A weight over the pivot "A" holds the needle point down, and gives the instrument stability.



Fig. 10

To measure the area of any irregular figure like an indicator diagram the instrument is placed as in Fig. 10, so that the arm shall not take inconvenient positions when the outline of the diagram is traced. Take any point on the diagram as at "B" and set the measuring wheel to read zero, trace the diagram in a clockwise or right-hand direction.

Before proceeding to explain the method of reading, it will be as well to describe the vernier and measuring wheel.

Let Fig. 11 represent a scale of units numbered 1, 2, 3, 4, etc., which

Digitized by Google

are sub-divided into tenths. The vernier U. V. is as long as nine of the sub-divisions, and is divided into ten parts. Thus the intervals of the vernier are 9/10ths as long as the interval of the scale, or we can say they are 1/10th of an interval shorter. As shown the index of the vernier reads 4.5 on the scale. It will be noted that the 4th division of the vernier coincides with a division of the scale, the 3d division of the vernier is 1/10th of an interval from the next mark on the scale, the 2nd division is 2/10ths, etc. Therefore, the reading of the vernier is 4.54 square inches, for if the measuring wheel is divided into ten equal parts, each to equal one square inch, then the sub-divisions enable us to read to hundredths of a square inch.

Therefore, starting at any desired point run tracing point "B" in clockwise direction, and trace around diagram until starting point



Fig. 11

is reached, find highest figure on measuring wheel which has passed the zero on vernier moving to the left, in this case 4. Find next the number of completed divisions between 4 on measuring wheel and zero on vernier, which is in this case 5. Find division on vernier which corresponds with some division on measuring wheel, and in this case it is 4. Therefore, the exact reading is 4.54 square inches.

After the operator becomes familiar with the instrument it is not necessary to set the wheel to zero, but take the reading before starting to trace outline of diagram, and subtract this from the final reading. Thus, suppose when instrument is in position we find the reading to be 1.64, the final reading is 6.18. Therefore, $6.18 - 1.64 = 4.54$ square inches, area of card.

The instrument can be used for finding areas of any irregular figures. If the area is large, divide it by lines into areas of less than 20 square

Digitized by Google

inches and take separate measurements. If drawing be to scale multiply the reading of instrument by the square of the ratio number of the scale. Should it be required to find the area of an irregular figure containing 6 square inches drawn to a scale of 3 inches = 1 foot 3 inches = 1 foot is $\frac{1}{4}$ size. Therefore, $\frac{1}{4} \times \frac{1}{4} = \frac{1}{16}$ and $6 \times 16 = 96$ square inches.

Definitions

Relating to indicator diagrams. (See Fig. 12.) Four phases of valve-motion occur during a complete revolution of the engine, and are as follows:



Fig. 12

Admission ABC. When valve is open, and steam passing into the cylinder.

Expansion CD. When valve has cut off the steam supply to cylinder, and hence steam is neither admitted or released, therefore, the piston is moved through this distance by the expansive force of the steam.

Exhaust DEF. When the valve closes the admission port, and the port to exhaust opened, and hence steam is escaping from cylinder into receiver, or condenser if condensing, or atmosphere if non-condensing.

Compression FA. When all ports are closed, and the remaining steam in the cylinder acts as a cushion to bring the piston gently to rest.

The atmospheric line XX′ is a line drawn by the pencil of the indicator when both sides of the piston are open to the atmosphere. The steam is of course shut off from instrument. The atmospheric line on the diagram represents the pressure of the atmosphere, the gauge reading being zero.

The vacuum line OX″ is a reference line drawn at a distance corre-

Digitized by Google

sponding to barometer-pressure by scale below the atmospheric line. The barometric pressure which is usually 14.7 lbs. This line represents a perfect vacuum, or absence of pressure when drawn to scale to 15 lbs.

The clearance line OY is a reference line drawn at a distance from the end of the diagram equal to the same per cent. of its length as the clearance or volume not swept through by the piston is of the piston displacement. In other words, the distance between the clearance line and the end of diagram represents the volume of the clearance between piston and cylinder head, plus the volume of ports and passages at that end of cylinder.

Line of boiler pressure YY′ is a line drawn parallel to the atmospheric line, at a distance from it by scale equal to the boiler pressure shown by gauge.

Admission line AB is the line showing the rise of pressure due to admission of steam to the cylinder by the opening of steam valve.

Point of admission A indicates the pressure when the admission of steam begins at the opening of the valve.

Steam line BC is drawn when the steam-valve is open and steam is being admitted to the cylinder.

Point of cut-off C is the point where the admission of steam is stopped by the closing of the valve.

Expansion curve CD shows the fall in pressure as the steam in the cylinder expands.

Point of release D shows where the exhaust valve opens.

Exhaust line DE shows the change in pressure which takes place when the exhaust-valve opens.

Back pressure line EF shows the pressure acting against piston during its return stroke.

Point of exhaust closure F is the point where the exhaust valve closes. Point of compression F is where the exhaust valve closes, and compression begins. Compression curve FA shows the rise in pressure due to compression of the steam remaining in the cylinder after the exhaust valve has closed.

Initial pressure is the pressure acting on the piston at the beginning of the stroke.

Terminal pressure is the pressure above the line of perfect vacuum which would exist at the end of the stroke if the steam had not previously been released.

Admission pressure is the pressure acting on the piston at end of compression, and is as a rule less than the initial pressure.

Compression pressure is the pressure acting on the piston at beginning of compression; it is the least back pressure.

Cut-off pressure is the pressure acting on the piston at beginning of expansion.

Digitized by Google

Release pressure is the pressure acting on the piston at end of expansion.

Mean forward pressure is the average height of that part of the diagram traced on forward stroke.

Mean back pressure is the average height of that part of the diagram traced on the return stroke.

Mean effective pressure is the difference between the mean forward pressure and the mean back pressure during a forward and return stroke.

It is the height or length of the mean ordinate intercepted between the top and bottom lines of the diagram multiplied by the scale of spring used in instrument when diagram was taken. It is obtained without regard to atmospheric or vacuum lines.

Equivalent or referred mean effective pressure, often written as aggregate equivalent pressure referred to low pressure cylinder, is the mean effective pressure which would be required to produce the same indicated horse-power from a cylinder of the same dimensions as the low pressure cylinder of a multiple expansion engine.

Ratio of expansion is the ratio of the volume of steam in the cylinder at the end of stroke to that at cut-off.

Initial expansion is the fall of pressure during admission due to imperfect steam supply.

Wire drawing is the fall of pressure between admission and cut-off.

Horse-power. The unit employed to measure the rate at which work is done in a steam engine is the "horse-power," the power exerted in the performance of 33,000 foot pounds of work per minute.

A distinction must be made between the indicated horse-power, and the actual or brake horse-power. When we speak of indicated horse-power, the work done per minute by the steam on the piston of the engine, as computed from indicator diagrams, is understood. The friction of the shafting and pumps, as well as the reciprocating parts, friction of piston rods through stuffing boxes, glands, etc., valve gear and all working parts, absorb power and cause a loss which is termed frictional losses.

If, therefore, the sum of all these frictional losses is deducted from the indicated power we get the actual power available, which is delivered to the screw propeller, or in other words it is the rate at which useful work is done in turning the propeller.

The brake horse-power in very large engines is less, and in small engines considerably less than the indicated horse-power.

Now, brake horse-power $\div$ indicated horse-power = efficiency of engine. Therefore, efficiency of engine multiplied by indicated horse-power = brake horse-power. Stated in form of an equation we have: B. H. P. $= N \times$ I. H. P. when N = efficiency.

Digitized by Google

The following table (calculated from Middendorf, Scheffswiderstand und Maschinenleistung) gives values of efficiency N:

I. H. P.	N	I. H. P.	N
5 to 10	0.58	600 to 700	0.71
10 to 50	0.59	700 to 800	0.72
50 to 100	0.60	800 to 900	0.73
100 to 150	0.61	900 to 1,000	0.74
150 to 200	0.62	1,000 to 2,000	0.79
200 to 300	0.64	2,000 to 3,000	0.85
300 to 400	0.66	3,000 to 4,000	0.88
400 to 500	0.68	4,000 to 5,000	0.90
500 to 600	0.69	6,000 and over	0.91

The determining of the brake horse-power has been, until recently, a difficult and in fact almost impossible procedure due to the fact that large powers had to be absorbed, and the difficulties of fitting a brake to absorb it very great. The values of the efficiency as shown above have been taken as approximate values, and until recently approximate values were the only ones available.

The torsion meter enables us to determine accurately the power delivered to the shaft. The latest trials made with the torsion meter have given the following values:

I.H.P.	N	I.H.P.	H.
1,630	0.885	2,370	0.920
1,640	0.091	2,690	0.911
1,940	0.911	4,500	0.935

Before entering upon the subject of the indicator diagram, it will be as well if we explain the rules of mean ordinates.

The simplest way of determining the M. E. P. is by the planimeter. It frequently happens that we are compelled to compute the pressure without the assistance of this instrument, hence we have to resort to some practical method of computation.

"Rule of Mean Ordinates"

Divide the diagram into ten equal parts by lines at right angles to the atmospheric line, and measure the center of each division between the top and bottom lines forming the diagram. The mean height of the ten divisions, measured in inches and multiplied by scale of spring, is equal to the mean effective pressure in pounds per square inch. Greater accuracy is obtained by dividing diagram into 20 equal parts and measuring each ordinate, dividing the sum by 20 to obtain mean ordinate, then multiply by scale of spring. In the use of the planimeter we get the area of the diagram, and dividing it by the length of card we get the height of the mean ordinate, and multiplying this mean

Digitized by Google

ordinate by scale of spring as explained gives us the M. E. P. in pounds per square inch.

Fig. 13 shows the method of obtaining the M. E. P. and dividing the card.



Fig. 13

Numb. of Ord.	Length of Ord.
L_1	1.09375″
L_2	1.3125 ″
L_3	1.3125 ″
L_4	1.3125 ″
L_5	1.1875 ″
L_6	1.0625 ″
L_7	.90625″
L_8	.40625″
L_9	.65625″
L_{10}	.4375 ″
	Sum = 9.68750

Lgt. of Mean Ord. = $10\rfloor 9.68750\lfloor = 0.96875$

Scale of Spring = 60 lbs. per inch.

Mean Effective Pressure = $0.96875 \times 60 = 58.125$ lbs.

Mean Effective Pressure by Planimeter = 58.37 lbs.

Simpson's Rule

Another method is by what is known as Simpson's Rule, and is as follows:

Divide the diagram into ten equal parts as before, and lettering the ordinate as shown, and take,

$Y_0 + Y_{10} = L_1$

$Y_1 + Y_3 + Y_5 + Y_7 + Y_9 = L_2$

$Y_2 + Y_4 + Y_6 + Y_8 = L_3$.

Digitized by Google

The mean effective pressure in pounds per square inch will therefore be,

$$\frac{L_1 + 4L_2 + 2L_3}{30} \times S$$



Fig. 14

Simpson's first rule is: To the sum of the first and last ordinate, add four times the even ordinates, plus twice the odd ordinates and multiply the sum by one-third the common interval gives area of figure. Now our interval is one-tenth, and one-third multiplied by one-tenth is equal to one-thirtieth, and this one-thirtieth multiplied by the scale of spring gives the divisor of our fraction. Therefore, the sum of $L_1 + 4L_2 + 2L_3$ divided by one-thirtieth multiplied by spring gives the mean effective pressure in pounds per square inch. Computation in full of Fig. 14.

Numb. of Ord.	Length of Ord.	Multiplier	Function of Ord's.
y_0	0.25 "	1	0.25
y_1	1.125 "	4	4.5
y_2	1.218 "	2	2.436
y_3	1.1875 "	4	4.75
y_4	1.0625 "	2	2.125
y_5	.875 "	4	3.5
y_6	.71875"	2	1.4365
y_7	.625 "	4	2.5
y_8	.5 "	2	1.
y_9	.375 "	4	1.5
y_{10}	0.0	1	0.0

Sum of function, 23.9975

Common interval $= \frac{1}{10}$.

$\frac{1}{3}$ " " $= \frac{1}{3} \times \frac{1}{10} = \frac{1}{30}$.

$23.9975 \times \frac{1}{30} = 30 \overline{)23.9975} = 0.7999$.

Scale of Spring = 60 lbs. per inch.

Mean Effective Pressure $= 0.7999 \times 60 = 47.994$ lbs.

Mean Effective Pressure by Planimeter = 48.7 lbs.

Digitized by Google

Engine Types

Single-cylinder engines are those in which the whole work of the steam is performed in one cylinder. Twin cylinder engines are those in which each cylinder works in precisely the same way as a single-cylinder engine; the steam passing into both cylinders direct from the boilers, and exhausting from both cylinders into the atmosphere or condenser.

Compound engines are those in which the steam works successively in two or more cylinders placed close to each other.

In a two-cylinder compound engine the steam passes from the boiler into the high-pressure cylinder, exhausting from the high-pressure cylinder into the receiver and thence into the low-pressure cylinder. From the low-pressure cylinder it exhausts into the condenser.

In a triple expansion engine, the steam passes from the boiler into the high-pressure cylinder, exhausts from the high-pressure into the first receiver, from thence into the intermediate cylinder, exhausting from the intermediate cylinder into the second receiver, from thence into the low-pressure cylinder, and from low-pressure cylinder into the condenser.

In a quadruple expansion engine, the steam passes from the boiler into the high-pressure cylinder, exhausts from high-pressure into the first receiver, from thence into the first intermediate cylinder, exhausts from first intermediate cylinder into the receiver and from there into a second larger intermediate cylinder, exhausting from the second intermediate cylinder into the receiver, thence into the low-pressure cylinder, and from the low-pressure cylinder into the condenser.

As the steam decreases in pressure in passing through the various cylinders, its volume correspondingly increases; therefore the cylinder, from high-pressure onward, must increase in size, this increase depending upon the degree of expansion.

It frequently happens that the same degree of expansion may be divided between two cylinders, either two high-pressure or two low-pressure cylinders. This is resorted to for constructive reasons.

A triple expansion engine may have four cylinders high-pressure, intermediate-pressure, and two low-pressure cylinders of the same size.

A triple expansion engine having 5 cylinders, namely, two high-pressure, one intermediate, and two low-pressure cylinders, has been installed in large Atlantic liners.

Multiple expansion engines are computed in precisely the same manner as a single cylinder engine. The reasoning is the same as if all work of the steam were done in the low-pressure cylinder. This will be more readily understood when we take up the computations of Equivalent M. E. P. and Cylinder Dimensions.

Digitized by Google

CHAPTER II

Work of Steam

It is necessary that the work of the steam in the cylinder is comprehended thoroughly, and it will therefore be necessary to consider a hypothetical case. Let us assume that we have a vertical cylinder, open at the upper end to the atmosphere, and closed at the bottom. We will further assume that the cylinder is fitted with a piston without weight and frictionless.

If a certain quantity of water is introduced at the bottom of the cylinder and a fire is built under it to convert the water into steam, we will have the boiler and engine represented by one vessel; the piston and water being brought into direct contact.

Let us make the diameter of piston about 13½ inches; this will give us a sectional area of 1 square foot, equal to 144 square inches.

Let a quantity of water weighing 1 pound be poured into the cylinder, and let this stratum of water support the piston.

As the upper end of the cylinder is open to the atmosphere, the pressure of the atmosphere (here taken as 14.7 lbs.) acts upon the piston, amounting to 14.7 lbs. × 144 square inches = 2,116.8 lbs. on the square foot of surface of the piston. The temperature of the water under atmospheric pressure will be raised to 212° F, before any steam is generated. If now the heat of the fire be maintained, the temperature will remain stationary at 212° F, but steam will be formed, and disengaged under the piston. The piston supposed to be frictionless and without weight will be raised with its load of 2,116.8 pounds through consecutive stages, each, say, one foot, until it reaches an elevation of 26.6 feet above the bottom of the cylinder. When this point is reached we shall have found the whole one pound of water evaporated, the constant elasticity of the fluid having been measured by 14.7 pounds per square inch, and a temperature of 212° F.

What are we to understand by this? We see that the pound of water has been entirely evaporated into steam of atmospheric pressure, and occupies a volume of 26.6 cubic feet, for 1 square foot area × 26.6 feet = 26.6 cubic feet. The initial work consists in having lifted a weight of 2,116.8 pounds through a height of 26.6 feet, or, expressed in foot pounds, 2,116.8 pounds × 26.6 feet = 56,306.88 foot pounds.

The above demonstration affords a vivid conception of the expansive force of steam, or to be more exact, the force of water when converted into steam. Here we had a lamina of water not quite one-fifth of an inch in depth, lying at the bottom of a cylinder 13½ inches

Digitized by Google

diameter. This water is converted into steam of atmospheric pressure of 1,602.4 times its original volume, for $\frac{1}{5}$ inch = 0.0166 feet, and 26.6 feet ÷ 0.0166 feet = 1,602.4.

As one heat unit is equivalent to 778 foot pounds, the value of the external work expressed in heat units is 56,306.88 foot pounds ÷ 778 heat units = 72.37 H. U. There is a small expenditure of energy in raising the mass of steam against the force of gravity. Thus, the average height to which the steam is raised is 26.6 ÷ 2 = 13.3 feet, and 1 pound × 13.3 feet = 13.3 foot pounds, or, 13.3 foot pounds ÷ 778 H. U = 0.017 H. U.

British Thermal Unit

A British thermal unit or B. T. U. is the heat required to raise one pound of water from 62° F to 63° F. Heat is always measured in B. T. U.'s in the English system.



Fig. 15

Expansion of Steam

The steam in the cylinder of a steam engine during expansion is supposed to follow substantially a law known as the law of Boyle and Mariotte. This law states that the pressure varies as the volume in an

Digitized by Google

inverse ratio. That is to say: As the volume increases the pressure suffers a decrease.

Symbolically, if P = pressure, and V = volume, then P. V. = C.

We say substantially, because the actual changes of pressure do not follow the law exactly. The pressure may, and in the majority of cases it does fall more rapidly in the early stages of the expansion, and less rapidly in the latter portion than indicated by the law of inverse ratio. Therefore, the finial pressure is as a rule greater than that which would be deduced from the ratio of expansion.

Now the fullness of the expansion curve depicted on the indicator diagram, near the end, compensates for the hollowness near the beginning, and hence we find that the area bounded by the curve is practically equal to that bounded by a hyperbolic curve according to the law.

We, therefore, assume that for all practical purposes, and for general investigation, the steam expands according to the law, P. V. = C.

The curve which represents diminishing pressures due to increasing volume is a portion of a hyperbola.

The rectangular hyperbola used as a curve of expansion is constructed as follows: (See Fig. 15.)

Let $OY' = P$, the initial pressure.

Let $Y'U = V$, the volume up to cut-off.

Let $OX_7 = Vo$, the volume at end of stroke.

Produce the line Y'U to U_7; divide UU_7 into any number of parts, say 7. Draw a series of radiating lines from O to U_1, U_2, U_3 . . . . . U_7.

Now where the radiating lines OU_1, OU_2 . . . . . OU_7 intersect the ordinate UX, such as points 1, 2, 3, etc., these points of intersection give points through which are drawn lines parallel to OX_7, as 1, 1, −2, 2, −3, 3, etc.

Drawing a fair curve through the corresponding points of intersection with the ordinates U_1 X_1, U_2 X_2, U_3 X_3 . . . . . U_7 X_7, we have the curve known as the rectangular hyperbola, or curve of P. V. = C.

To determine the pressure at any point of the expansion curve, say for volume $Y'U_3 = OX_3$. Draw the diagonal line OU_3, then through point 3 the intersection of U, X and OU_3 draw the horizontal line 3,3 parallel to OX_7. Point 3 is a point on the expansion curve and the vertical line 3, X_3 gives the absolute pressure corresponding to the volume OX_3.

Should we desire to obtain the finial pressure after expansion: Draw the diagonal line OU_7; then through the point 7, the intersection of UX and OU_7, draw the horizontal line 7, 7, parallel to OX_7. The vertical line 7, X_7 gives the required finial absolute pressure. We can conversely find the volume which a quantity of steam V. would

Digitized by Google

occupy at the pressure P. if it were compressed to the pressure P_a. To obtain the volume, draw the diagonal line OU′ (see Fig. 16) now where OU′ intersects Y′U, draw A, A parallel to Y″O. The line Y″A gives the required volume.

It should be borne in mind that Y′U is volume without clearance, and OX_7 is vacuum line.



Fig. 16

To illustrate the application of the hyperbolic law of expansion, showing that the product of pressure and volume at any point of the expansion-curve is constant. Let the line XX1 (Fig. 17) represent the stroke of the piston and the corresponding volume described by it without clearance.

Digitized by Google

Assume steam of 160 pounds absolute pressure be admitted for a space 1 foot in length XA. The area of the rectangle is the product of the pressure and volume of the steam admitted. If the steam expands to double its volume XD the pressure will be one half, represented



Fig. 17

by DC. The area of the rectangle XE×XD, is the product of pressure × volume, and this area will be equal to the area of the rectangle XY×XA.

Expanding further to any number of volumes we find the pressure multiplied by volume is equal to the initial pressure multiplied by initial volume. The area of each rectangle is therefore equal to the original rectangle. The hyperbolic curve containing these rectangles may be indefinitely extended at either end, embracing toward the left hand, high pressures and small volumes, and to the right hand, low pressures and large volume.

The area of the rectangle XYBA, being the product of pressure and volume, expresses the work done upon the piston by the steam on

Digitized by Google

entering the cylinder and occupying a given volume. The area bounded by the hyberbolic curve BM, the ordinates MX_1, AB, and the base AX_1 expresses the work done by expansion of the steam after the communication with the steam supply has been cut off.

Let P = absolute initial pressure of steam.

Let V = volume up to cut-off.

The work done by the steam during admission is P.V. (See Fig. 18.)

Let S = whole stroke.



Fig. 18

The mean pressure during this period, in relation to the whole stroke S, is $p = P\frac{V}{S}$ where p = mean pressure.

The work of expansion is equal to the area Y′Y″XUY′. The area Y′Y″XUY′ = P V hyp log $\frac{S}{V}$. The mean pressure during the work of expansion in relation to whole stroke S is P $\frac{V}{S}$ hyp log $\frac{S}{V}$. Now $\frac{V}{S}$ = cut-off = C.

C is expressed either as a fraction or as a percentage of the volume of the cylinder. Thus, cut-off $\frac{1}{4}$ stroke = 4⌋1.00⌊ = 0.25 or 25 per cent.

Digitized by Google

of stroke. $\frac{S}{V}$ is termed the ratio or degree of expansion. The ratio or degree of expansion is also equal to $\frac{1}{C}$ or 1 divided by the cut-off.

It should be clearly understood that in multiple expansion engines, that is, compound, triple and quadruple expansion engines, the term total cut-off is frequently used, and is understood to mean the ratio that the volume of steam admitted to the high-pressure cylinder bears to the volume of the low-pressure cylinder.

Total expansion means the ratio that the volume of the low-pressure cylinder bears to the volume of steam admitted to the high-pressure cylinder.*

As an example, suppose we have a triple expansion engine, the volume of the low-pressure cylinder is 7 times the volume of the high-pressure cylinder. The ratio of cylinder capacities are therefore 1:7.

Assume a cut-off in high-pressure cylinder of 75 per cent. of stroke. The ratio or degree of expansion is $\frac{7^{\prime\prime}}{0.75} = 75 \rfloor 700 \lfloor 9.33$.

And the total cut-off will be $\frac{1}{9.33} = \frac{.75}{7} = 0.107$.

The cut-off in the high-pressure cylinder is equal to the ratio of cylinder capacities ÷ total expansion.

Thus $\frac{7}{9.33} = 0.75$.

Let C = total cut-off.

Let C_h = cut-off in the high-pressure cylinder.

Let R = ratio of the volume of low-pressure cylinder to that of the high pressure cylinder.

Then total cut-off $C = \frac{C_h}{R}$.

And total expansion $= \frac{1}{C} = R\frac{1}{C_h}$.

Clearance

All engines have clearance, the space between the piston and cylinder-head when piston is at either end of its stroke. The steam passages between valve face and cylinder bore. This clearance space must be filled with steam of the initial pressure at the beginning of each stroke. The clearance is measured as a certain percentage of the cylinder volume. When so expressed it is termed volumetric clearance. For example, if we have a cylinder 12 inches in diameter by 12 inches stroke: The volume of the cylinder = area of cylinder in square inches × stroke in inches. Now the area of a 12″ circle = 113.10 square inches. 113.1 □″ × 12″ = 1357.2 cubic inches volume of cylinder.

Suppose the clearance between cylinder head and piston plus the clearance in port is equal to 95 cubic inches. The percentage is, therefore, 95 ÷ 1357.2 = 0.07 or 7 per cent. It is rather a tedious and sometimes impossible task to determine accurately the correct clearance, and

* The volume of a cylinder is equal to the area of the cylinder in square inches multiplied by the stroke of piston in inches.

Digitized by Google

where the data must be very accurate, the only way to determine it is from the cylinder drawings. The clearance may be measured in parts of the stroke and the clearance length added to the period of admission. It is evident that this sum represents or expresses the initial volume of steam for expansion.

Thus suppose that the clearance is 7 per cent. of the volume of the cylinder or piston displacement, which is one and the same thing, and let us further assume cut-off at half stroke = 50 per cent.

We readily see that the effective cut-off is not 50 per cent., but it is more than this by the amount of clearance, and hence we have the



Fig. 19

expansion of a volume of steam equal to 50 per cent. plus 7 per cent. = 57 per cent. instead of only 50 per cent. This practially amounts to making the cylinder 7 per cent. longer and cutting off at 50 per cent. of the stroke without clearance.

The mean pressures in practice are greatly effected by clearance. Before the incoming steam can force the piston out, it has to fill the clearance space. Now this space being filled alternately with admission steam of a high temperature, and the cooler exhaust steam

Digitized by Google

having a lower temperature causes considerable loss by condensation during admission. It matters not how accurately the engine is designed, the clearance spaces are large, and the superficial areas, exposed to extreme variations of temperature, are likewise large. It will therefore readily be seen that clearance affects expansion prejudicially due to the fact that it raises the terminal pressure, and affects compression, because it reduces the finial pressure of compression.

Diagram (Fig. 19) shows first the work of expansion is increased by clearance. Thus area XUU^7X_7X is greater than $XUU,^7\ X_7X$, area $XUU,^7\ X_7X$ representing work done during expansion without clearance. "Second," showing that compression must be increased to obtain a given terminal pressure if there is clearance.

The rate of expansion taken without clearance is termed nominal rate of expansion.

The rate of expansion taken with clearance is termed the actual rate of expansion.

When the clearance can be accurately determined it is better to use it, and obtain the actual instead of the nominal rate of expansion.

Then if V_n = nominal rate of expansion.

V_a = actual rate of expansion.

C = clearance as a fraction of the cylinder capacity.

We have $\frac{1}{V_a}=\frac{\frac{1}{V_n}+C}{1+C}$. $V_a=V_n\frac{1+C}{1+CV_n}$.

$\frac{1}{V_n}+C$ is the volume of steam at cut-off between the piston and valve.

This steam expands to the volume $1+C$ at the end of the stroke. If there is no compression of the steam before admission the whole space $\frac{1}{V_n}+C$ must be filled with fresh steam at each stroke.

In some cases there is sufficient compression to fill the clearance space with steam of initial pressure. The volume of steam used during each stroke will then be that swept by the piston up to cut-off only. This will then be equal to $\frac{1}{V_n}$.

Whilst clearance serves to increase the mean pressure beyond that due to the nominal rate of expansion, it cannot be considered as a source of loss, unless the equivalent cut-off is taken to obtain the rate of expansion. With the use of higher steam-pressures and higher rates of expansion the disadvantageous influence of clearance is diminished.

With good steam distribution and proper compression, the drawbacks due to clearance may be lessened. As the actual total cut-off deviates less from the theoretical; the limit of total expansion due to clearance can be arranged to fall in more favorable position. The clearance should however in any case be made as small as possible.

Digitized by Google

Losses in Cylinders

The principal causes of loss of pressure in the cylinders of a marine engine are the following:

Friction in boiler stop valve.
Friction in throttle valve on cylinder.
Losses by friction in main steam pipe.
Friction or wire drawing of the steam during admission.
Liquification during expansion.
Compression and back-pressure.
Friction in the ports and pipes.

The loss by friction in the stop-valves, throttle-valve, and main steam pipe does not show on the indicator diagram, but the loss is manifest in the fall of pressure or drop between boiler and piston.

The loss by friction or wire drawing is as a rule due to defective design and adjustment. Defective design embracing small steam ports. Valve chest too small, causing thereby expansion of steam into cylinder when valve opens without being replaced with sufficient rapidity by steam from boiler.

Adjustment embracing valves, not permitting a sufficiently large opening for the quantity of steam required. Valves not cutting-off with quickness. This latter is a defect inherent in a link motion.

Liquification during expansion, due in part to the cooling action of the cylinder walls.

In multiple expansion engines, liquification losses are less than in single-cylinder engines. Exhausting before the piston reaches end of its stroke, whilst conducive to good working of fast running engines, nevertheless shows a loss in the indicator diagram.

The Steam Jacket

The steam jacket is seldom used except for warming the engine cylinders. The value of the steam jacket decreases with the diameter of the cylinder and high piston speeds. The wet steam supplied by the average water tube boiler neutralizes the good effects.

Again it is only the innermost layers of the cylinder walls that are affected by the fluctuation of temperature taking place in the cylinder. The variations will be less in the outer layers of metal; each concentric layer has a mean temperature, diminishing toward the exterior surface of the walls. It is readily seen that the outer layers approximate to the surrounding temperature of the atmosphere. The higher the temperature the less far will the variations of temperature extend outward through the walls and hence the exchange of heat during one revolution will be smaller.

Digitized by Google

Effective Mean Pressure With Clearness

Assume steam pressure = 100 pounds gauge or 100 + 15 = 115 pounds absolute.

Let clearance space equal one-ninth of the cylinder volume.

Back-pressure assumed at 16 pounds absolute.

Nominal cut-off = $\frac{1}{4}$ the stroke.

Assume no compression.

The actual cut-off $V_a = V_n \frac{1+C}{1+CV_n}$.

$V_n = 4$. Hence $4 \frac{1+\frac{1}{9}}{1+\frac{4}{9}} = \frac{\frac{10}{9}}{\frac{13}{9}} = \frac{10}{13} \times 4 = 3$.

The mean pressure will be $115 \times \frac{1+\text{hyp log } V_a}{V_a} =$

$115 \times 0.6993 = 80.42$ pounds.

Effective mean pressure = 80.42 − 16 = 64.42 pounds.

Let us assume that we now compress the steam to full pressure = 115 pounds.

Then $\frac{115}{16} = 7$ = rate of compression.

Then the mean pressure = 80.42 pounds as obtained before.

The effective mean pressure = $(80.42 - 16)(1 + \frac{1}{9}) + \frac{115}{9}(1 - 2.95) = \frac{10}{9} \times 64.42 - \frac{224.25}{9} = 46.66$ pounds.

If there was no clearance the mean effective pressure would have been 68.59 − 16 = 52.59 pounds.

We see that the steam used in the case with full compression is the same as if there had been no clearance. The effective pressure was only 46.66 pounds. There is consequently a loss due to clearance of 52.59 pounds − 46.66 pounds, or say 5.93 pounds, or about 11 per cent.

In the first case the quantity of steam used is $\frac{13}{16}$ the volume of cylinder per stroke or one-ninth of the volume in excess of the quantity with no clearance. If with this increase of steam there was no clearance and the rate of expansion of 4 there should be an increase in the work done, and the increased work will be to the work done by the smaller quantity of steam as 13 is to 9.

We, therefore, see that the equivalent mean effective pressure is then $\frac{13}{9}$ of 52.59 or 75.96 pounds. Against 64.42 pounds, which shows a loss of 11.54 pounds or 15 per cent. This case will show the loss due to clearance, and whilst it may be considered one rarely met with in practice, yet it is sufficient to demonstrate what has been said before on this subject.

Before leaving this subject, another case will be quoted. From data of a compound engine in the author's possession we have the following:

Steam pressure, 120 pounds gauge or 135 absolute.

Digitized by Google

Receiver pressure, 25 pounds absolute.

Cut-off high-pressure cylinder, 60 per cent.

Nominal rate of expansion, 1.66.

Clearance, $\frac{1}{9}$ the cylinder volume.

We will take the first case with no compression.

Now actual rate of expansion $= 1.66 \frac{1+\frac{1}{9}}{1+\frac{1.66}{9}} = 1.66 \frac{\frac{10}{9}}{\frac{10.66}{9}} = \frac{1.66 \times 10}{10.66} =$ 1.55.

The mean pressure will be $135 \frac{1+\text{hyp log } 1.55}{1.55} =$ $0.9292 \times 135 = 125.44$ pounds.

The effective mean pressure $= 125.44 - 25 = 100.44$ pounds.

When $\frac{3}{5}+\frac{1}{9}$ or $\frac{32}{45}$ of the volume of the cylinder of steam is used, the equivalent effective mean pressure will be $\frac{10.66}{9}$ of $97.39 = 115.35$ pounds.

The loss by clearance is, therefore, $115.35 - 100.44 = 14.91$ pounds or 13 per cent.

Now assume we compress the steam to initial pressure.

The effective mean pressure is 103.06 pounds.

The loss is, therefore, $115.35 - 103.06 = 12.29$ pounds or 10.64 per cent.

In conclusion, it is unnecessary to say the loss from clearance in a compound engine is not so serious as in a simple engine. If the clearance in the low-pressure cylinder of multiple expansion engines is large, considerable loss will occur. Otherwise, if the clearance in low-pressure cylinder is small, the losses from clearance are of no consequence. This is due to the fact, that whereas in the simple engine the cut-off is earlier, the clearance is from constructive reasons much the same. Again the ratio of clearance to volume at cut-off will be much higher. In the multiple expansion engine, the steam passing from high-pressure cylinder to the other cylinders will do more work. The exhaust steam passing to the condenser in a single cylinder condensing engine is at a higher pressure when there is clearance than when there is no clearance.

Mean Pressure in Multiple Expansion Engines

In the compound engine, if the effective mean pressure in the high pressure cylinder be divided by the ratio of the volume of low-pressure cylinder to that of the high-pressure cylinder, plus the effective mean pressure in the low-pressure cylinder the sum is termed the equivalent or referred effective mean pressure.

This referred effective mean pressure is the pressure necessary to obtain from the low-pressure cylinder alone the whole work of both cylinders.

If the effective mean pressure in the high-pressure cylinder be divided by the ratio of the volume of low-pressure cylinder to the

Digitized by Google

volume of high-pressure cylinder; the quotient is the pressure required to do the same work in the low-pressure cylinder as is effected in the high-pressure cylinder.

Thus if the ratio of $\frac{\text{L. P. Cyl.}}{\text{H. P. Cyl.}} = 4$ say.

If the effective mean pressure in high-pressure cylinder = 90 pounds.

Then the effective mean pressure in the low-pressure cylinder to do the same work as effected in high-pressure cylinder $= \frac{90}{4} = 22.5$ pounds.*

If the effective mean pressure in the high-pressure cylinder is as before 90 pounds, and the effective mean pressure in the low-pressure cylinder is 15 pounds, then the equivalent or referred effective mean pressure is equal to $\frac{90}{4} + 15 = 37.5$ pounds.

The referred effective pressure in multiple expansion engines should be the same as the effective mean pressure in a single cylinder engine having the same total rate of expansion. This, however, is never realized owing to drop in receivers, and other causes which will be taken up later.

The equivalent or referred effective mean pressure in a triple expansion engine is obtained in the same way. That is to say, the referred effective mean pressure is equal to the sum of the effective mean pressure in high-pressure cylinder divided by the ratio of the volume of low-pressure cylinder to the volume of high-pressure cylinder, plus the effective mean pressure in mean-pressure cylinder divided by the ratio of the volume of low-pressure cylinder to the volume of mean-pressure cylinder plus the effective mean pressure in low-pressure cylinder, or, placed in the form of an equation we have

If P'_m = Effective mean pressure in H. P. Cyl.
P''_m = Effective mean pressure in M. P. Cyl.
P'''_m = Effective mean pressure in 2nd M. P. Cyl.
P''''_m = Effective mean pressure in L. P. Cyl.
R = The ratio of the volume of L. P. to H. P. Cyl.
R′ = The ratio of the volume of L. P. to M. P. Cyl.
R″ = The ratio of the volume of L. P. to 2nd M. P. Cyl.

Then referred effective mean pressure is $\frac{P'_m}{R} + P'''_m$ for compound.

$\frac{P'_m}{R} \pm \frac{P''_m}{R'} + P''''_m$ for triple expansion.

$\frac{P_m'}{R} + \frac{P''_m}{R'} + \frac{P'''_m}{R''} + P_m''''$ for quadruple expansion.

* The same reasoning applies to triple and quadruple engines.

Digitized by Google

Actual Effective Mean Pressures

The actual mean pressures in practice are less than those computed for a given initial pressure and rate of expansion.

Now the effective mean pressure is equal to the absolute initial pressure multiplied by the quotient obtained by dividing 1 plus the hyperbolic logarithm of the rate of expansion by the rate of expansion minus the absolute back pressure.

Thus if P_i = initial absolute pressure per□″ in any cylinder.
P_b = absolute back pressure per□″ in any cylinder.
R = total rate of expansion.
R_h = rate of expansion in H. P. Cyl.
R_m = rate of expansion in M. P. Cyl.
R_{m1} = rate of expansion in 2d M. P. Cyl.
R_l = rate of expansion in L. P. Cyl.

Then $P_i \times \frac{1+\text{hyp log } R}{R} - P_b$ = effective mean pressure due to the initial pressure P_i and a total rate of expansion R.*

As stated above, this pressure is, however, that which would obtain in a perfect engine, and hence is only a theoretical effective mean pressure.

In an actual engine, however, carefully designed, there will be causes of loss, and hence the actual indicator diagram will show an effective mean pressure much less than computed. The causes of loss have been treated in this chapter.

Now the ratio of the actual effective mean pressure to the theoretical effective mean pressure expresses the efficiency of the system and is termed the design or card factor.

Card Factor

The card factors vary not only for the various types of engines, but for engines of the same type, and different powers.

The following table gives a fair average:

For single engines not allowing for clearance	0.75 to 0.85
For single engines allowing for clearance	0.6 to 0.68
For compound engines not allowing for clearance	0.7 to 0.85
For compound engines allowing for clearance	0.55 to 0.7
Triple expansion engines not allowing for clearance	0.67 to 0.75
Triple expansion engines allowing for clearance	0.5 to 0.54
Quadruple expansion engines not allowing for clearance	0.65 to 0.7
Quadruple expansion engines allowing for clearance	0.55 to 0.7

In determining the card factors, it is best whenever possible to make a note of engine's performance, deducting the card factor and tabulating

*The E M. P. for any cylinder can be found by substituting the literal quantities in the equation.

Digitized by Google

same. As an example, suppose we have a triple expansion engine the ratio of the volume of L. P. cylinder to H. P. cylinder is 1:7.

Assume cut-off in H. P. cylinder=75 per cent.

The total rate of expansion or R=7÷0.75=0.75⌋7.00⌊=
075⌋700.00⌊9.33
675
250
225
250

Assume steam pressure 160 lbs absolute.

Assume back pressure 5 lbs. absolute.

Now $160\times\frac{1+\text{hyp log } 9.33}{9.33}=160\times0.3473=55.57$ lbs.

The mean pressure=55.57 lbs.

The effective mean pressure=55.57−5=50.57 lbs.

Now suppose from the indicator diagrams we have a referred effective mean pressure of 34 lbs.

The card factor would be the ratio of 34 lbs to 50.57 lbs.=0.672.

Now, conversely, suppose we were designing a triple expansion engine, the ratio of the volume of L.P. cylinder to H.P. cylinder=1:7.

Cut-off in H. P. cylinder 0.75.

All conditions the same as before.

The theoretical referred effective mean pressure we found to be 50.57 lbs.

Now suppose we select a card factor of say 0.67.

Then the actual pressure would be 50.57×0.67=33.88, say 34 pounds.

In designing a multiple expansion engine the referred effective mean pressure is used, and after that has been determined the diam. of the low-pressure cylinder is determined.

From the remarks made before on the definition of equivalent or referred pressure, we reason about it as though the power was to be developed in the L. P. cylinder only.

With a single cylinder engine, condensing or non-condensing, the cut-off would be total cut-off, thus with a total rate of expansion of 6 and a cut-off of 75 per cent in the H. P. cylinder of a multiple expansion engine, the total cut-off would be $\frac{0.75}{6}=0.125$.

The total rate of expansion, being the reciprocal of the total cut-off would therefore be $\frac{1}{0.125}=8$. We therefore see that with a multiple expansion engine cutting-off at 75 per cent in the H. P. Cyl. the total

Digitized by Google

rate of expansion with a ratio of L. P. to H. P. Cyl. of 6 would be 8, while to effect this rate of expansion in a single cylinder we would cut-off at one-eighth the stroke. It is at once apparent that the great temperature range would prohibit the use of a single cylinder aside from other losses.

An example of the application of the principles enunciated in this chapter will perhaps be of benefit in aiding to comprehend fully those principles.

From data in the author's possession we will select a triple expansion engine which was designed to develop 1530 I. H. P.

The following data will be used:

Designed I. H. P. = 1530.

Steam pressure at H. P. cylinder = 150 pounds gauge.

Steam pressure at H. P. cylinder 165 pounds absolute.

Back pressure 5 pounds absolute.

Cut-off in H. P. cylinder = 0.75 = 75 per cent. of stroke.

Total rate of expansion decided upon = 8.

The theoretical referred effective mean pressure is

$$[165\# \times \frac{1 + \text{hyp log } 8}{8} - 5\#].$$

But $\frac{1 + \text{hyp log } 8}{8} = 0.3849.$

Theoretical mean pressure = $165\# \times 0.3849 = 63.5$ pounds.

Theoretical effective mean pressure = $63.5\# - 5\# = 58.5$ pounds.

From diagrams of a similar engine the design factor of 0.583 was obtained.

Using this factor for our present computation we obtain:

The expected effective mean pressure = $58.5\# \times 0.583 = 34.1$ pounds.

As the designed horse power is to be 1530, the foot pounds of work per minute is therefore $1530 \times 33000 = 50{,}490{,}000$.

The stroke of piston is to be 2.75 feet = 33".

Designed piston speed = 580.8 feet.

Revolutions = 105.6.

Computing the diameter of the L. P. cylinder we have

$$\text{Area L. P. Cyl.} = \frac{1530 \times 33000}{34.1 \times 580.8} = 2550 \text{ square inches.}$$

The nearest practical diameter is 57 inches, and the corresponding area is 2551.8 square inches.

The ratio of the volume of L. P. cylinder to H. P. cylinder must be equal to cut-off in H. P. cylinder multiplied by total rate of expansion or $0.75 = \frac{R}{8}$. $\therefore R = 6$.

Digitized by Google

The diameter of the H. P. cylinder will be obtained, thus:

$$\text{Area H. P. cylinder} = \frac{\text{Area L. P. cylinder}}{\text{Cut-off H. P. Cyl.} \times \text{total rate of expansion}}$$

$$= \frac{2551.8\square''}{0.75 \times 8} = \frac{2551.8\square''}{6} = 425.3 \text{ square inches.}$$

The nearest practical diameter is 23.27 inches.

The area and therefore diameter of the M. P. cylinder is a subject upon which no two designers agree. It should be in the ratio of the square root of the ratio of L. P. to H. P. cylinder; this, however, gives a cylinder too large, as the temperature range is too great, and the power unequal, hence putting up excessive strains on crank shaft.

From a list of engines showing a fair distribution of power, it is found that the square root of the ratio of L. P. to H. P. cylinder is multiplied by a constant factor ranging from 1.05 to 1.1.

The diameter of the M. P. cylinder will be obtained, thus:

$$\text{Area M. P. cylinder} = \frac{\text{Area L. P. cylinder}}{\text{F} \sqrt{\text{Ratio of L. P. to H. P. Cyl.}}}$$

This engine as built had cylinders of the following dimensions:

H. P. cylinder diameter = 23½ inches.
M. P. cylinder diameter = 35 inches.
L. P. cylinder diameter = 57 inches.
Stroke common to all cylinders = 33 inches.

The ratio of $\frac{\text{L. P.}}{\text{H. P.}} = \frac{2551.8}{433.73} = 5.88.$

The ratio of $\frac{\text{M. P.}}{\text{H. P.}} = \frac{962.11}{433.73} = 2.21.$

The ratio of $\frac{\text{L. P.}}{\text{M. P.}} = \frac{2551.8}{962.11} = 2.65.$

The effective mean pressure H. P. Cyl. = 56.7 pounds.
The effective mean pressure M. P. Cyl. = 31.1 pounds.
The effective mean pressure L. P. Cyl. = 12.8 pounds.

The actual referred effective mean pressure is

$$\frac{56.7\#}{5.88} + \frac{31.1\#}{2.65} + 12.8\# = 34.17 \text{ pounds.}$$

The I. H. P. developed in H. P. cylinder = 432.82
The I. H. P. developed in M. P. cylinder = 526.92
The I. H. P. developed in L. P. cylinder = 574.86
The total I. H. P. = 1534.70

Note.—It is usual in designing the cylinders to be guided by temperature range, and distribution of power, etc., and as this involves a treatment which has no place in a book of this kind, as it is too abstruse, and is fully treated in the author's book on marine engine design.

Digitized by Google

Horse Power

The unit of horse power is 33,000 foot pounds per minute. This is equivalent to 33,000 pounds raised 1 foot or 1 pound raised 33,000 feet per minute.

The power to be exerted is, therefore, expressed in foot pounds. We had 1530 horse power as the desired number; we multiplied this by 33,000 foot pounds because 1 horse power is equal to 33,000 foot pounds of work per minute. Now this is the numerator of our fraction. As the horse power varies directly as the piston speed in feet per minute and as the effective mean pressure, we see that this is the denominator of our fraction.

Now the formula for horse power is $\frac{PLA2N}{33000}$.

Where P = effective mean pressure.
L = length of stroke in feet.
A = area piston in square inches.
N = number of revolutions per minute.

Now as I. H. P. = $\frac{PLA2N}{33000}$.

The area of cylinder will be given by $\frac{\text{I. H. P} \times 33000}{PL2N}$.

It must be clearly borne in mind that the effective mean pressure is the mean of the effective pressures. If the power is to be determined for each end of the cylinder separately, then the formula is $\frac{PLAN}{33000}$ and top and bottom must be added to obtain the total horse power.

Again it is readily seen that the mean pressure for each cylinder is evidently equal to the initial pressure in that cylinder, multiplied by $\frac{\text{I} + \text{hyp log of rate,}}{\text{rate}}$ where rate is the rate of expansion in that cylinder. The back pressure has to be deducted to obtain the effective mean pressure. As this is the theoretical pressure it must be multiplied by a factor. This factor like other factors must be determined from the ratio of the actual effective mean pressure to the theoretical effective mean pressure. What has been said before about the reasoning on multiple expansion engines, namely, that the low pressure is treated as though all the work was to be done in that cylinder is now sufficiently clear.

In computing the horse power developed in the cylinder or cylinders of an engine, the net area of piston is understood. That is to say, the area of piston-rod, and tail-rod, if any, must be deducted

Digitized by Google

from area of piston. As an example, suppose we have an engine of the following dimensions:

Diameter of cylinder, - - - 10 inches
Stroke of piston, - - - - - 24 inches
Revolutions, - - - - - - - 100 per minute
Diameter of piston-rod, - - 2 inches
M. E. P. top from diagram, - 40 pounds
M. E. P. bottom from diagram, 36 pounds
Area of piston $=10^2 \times .7854 = 78.54$ square inches

Therefore, I. H. P. top $= \frac{PLAN}{33000} = \frac{40 \times 2 \times 78.54 \times 100}{33000} = 19.04.$

Now I. H. P. bottom $= \frac{36 \times 2 \times (10^2 - 2^2) \times 0.7854 \times 100}{33000} = 16.45.$

Total I. H. P. $= 19.04 + 16.45 = 35.49.$

We can if desirable proceed thus:

The M. E. P. top was 40 pounds.
The M. E. P. bottom was 36 pounds.
The average M. E. P. is therefore 38 pounds.
Area of piston top $= 78.54$ square inches.
Area of piston bottom $= 78.54$ square inches $- 3.14$ square inches $= 75.4$ square inches.
Mean area $= (78.54\square'' + 75.4\square'') \div 2 = 76.97\square''.$

The I. H. P. $= \frac{PLA2N}{33000} = \frac{38 \times 2 \times 76.97 \times 2 \times 100}{33000} = 35.49.$

If a tail rod is fitted to the piston of any cylinder, its area must be deducted from area of piston.

Digitized by Google

CHAPTER III

Combining Indicator Diagrams

Before taking up the subject of indicator diagrams in general, we will describe the method of combining same.

The object of combining the diagrams is to present in a graphical manner the losses suffered in multiple expansion engines, and to study their effects, and by proper analysis to determine the best methods for their reduction. In multiple expansion engines certain large losses appertaining to the expansive engine and not shown by the indicator diagrams are avoided. Other losses are, however, introduced which consists of those between the cylinders due to sudden expansion, wire drawing, friction, etc. It is very important to reduce all losses to the smallest possible extent; hence the value of combining and analyzing the diagrams.

The indicator diagrams which we will combine were taken from a triple expansion engine, having cylinders of the following dimensions:

Diameter of H. P. cylinder = 19″
Diameter of M. P. cylinder = 30″
Diameter of L. P. cylinder = 50″
Stroke common to all cylinders = 30″.

Fig. 20 shows the indicator diagrams from the 3 cylinders. The top and bottom diagrams are on one card.

The top diagrams only will be treated.

Taking now the diagram from high-pressure cylinder top, we divide the diagram into twenty equal spaces.* Erect ordinates perpendicular to the line of perfect vacuum. Measure the pressure at each ordinate. The pressure up to steam line and expansion line, we will call plus or positive. Measure likewise the pressure between back-pressure line and vacuum line; call this pressure minus, or negative. If a scale for pressures corresponding with spring used in instrument when diagrams were taken is not at hand, we can measure each ordinate in inches and convert same into pounds, per square inch. Thus, if the ordinate is $1\frac{3}{4}$″ long and the scale used was, say, 80 pounds, the pressure would be $1.75 \times 80 = 140$ pounds per square inch.

In using 20 ordinates the work is more tedious, but the result amply repays for any extra work, as the enlarged diagram is more accurate. After having divided the high-pressure diagram as described, we pro-

* Some prefer to divide diagram into 10 equal spaces; 20, however, are more accurate.

Digitized by Google



Fig. 20

Digitized by Google



Fig. 21

Digitized by Google

ceed to treat the diagram from M. P. cylinder and L. P. cylinder, in precisely the same manner. Fig. 21 shows the diagrams of Fig. 20 divided, and the corresponding pressure inserted.

The combined diagram is shown on plate 2.

The method of construction is as follows: Draw a horizontal line OX, and a vertical line OY, intersecting OX in O. The horizontal line OX is a line of volume; the vertical line OY is a line of pressure, or perhaps more correctly the line on which pressures are set off.

The line OX is also the line of perfect vacuum. In combining diagrams the volumes of the different cylinders are set off in their proper volumetric ratios; whilst the pressures are all set off to the same scale.

For pressures we will use a scale of 10 pounds to the inch; thus every inch in height on line OY represents 10 pounds pressure per square inch on piston.

Set off from O on OY pressures up to the absolute boiler pressure, thus 0, 10, 20,.....187 as shown.

The boiler pressure at the time these diagrams were taken was 172 pounds gauge or 187 pounds absolute. Line OY is not only a line of pressure, but it is also the line from which the clearance in each cylinder is measured. We must know the volumetric clearance in each cylinder before we can combine the diagrams. As mentioned in chapter II, this is a very difficult undertaking after engines are erected and in the ship. It is then necessary to obtain this information from the builders. The clearances for this engine was determined from the drawings of the cylinders and was found to be as follows:

Volumetric clearance H. P. cylinder = 14 per cent.
Volumetric clearance M. P. cylinder = 14 per cent.
Volumetric clearance L. P. cylinder = 9 per cent.

From the line OY set off parallel with OX, and to the right a distance equal to the clearance in H. P. cylinder. Before doing this, however, we must decide upon what length to make the H. P. cylinder diagram. The length of diagram is entirely optional and depends upon the whim of the engineer. 2 inches makes a good length of diagram, as then each ordinate is $\frac{1}{10}''$ apart, that is to say, the interval is 0.1 inch.

We will adopt a length of 2 inches. Now 14 per cent. of 2 inches is equal to $0.14 \times 2 = 0.28$ inch. Set off, therefore, from OY a distance of 0.28 inch and draw a vertical line parallel with OY. Draw a horizontal line parallel with OX, at a height corresponding to the initial absolute pressure in H. P. cylinder, which is in this case 176.2 pounds absolute. Set off a distance from OY on the horizontal line mentioned, a distance of 2.28 inches, or 2 inches from the clearance line. Now divide the

Digitized by Google

2 inches into 20 equal parts, drawing ordinates parallel with OY. Set off on these ordinates the pressures corresponding to the similar ordinates on the indicator diagram (Fig. 21).

After these pressures are all set off on their respective ordinates for both the forward and return stroke, we trace a curve through the points and obtain the contour of diagram. It is best in all cases when dealing with pressures to deal with absolute pressures, because pressures are set off from vacuum. In taking pressures from the diagram it it better to take from vacuum line also. This line can be drawn on each card, by setting off below the atmospheric line a distance corresponding to 15 pounds to the scale with which diagram was taken.

Intermediate Cylinder Diagram

The diameter of the M. P. cylinder is 30 inches.

The area of a 30-inch cylinder is 706.86 square inches.

The diameter of the H. P. cylinder is 19 inches.

The area of a 19-inch cylinder is 283.53 square inches. The ratio of the volume of M. P. to H. P. is, therefore, $706.86 \div 283.53 = 2.49$.

The high pressure diagram having been made 2 inches in length, the length of the M.. P. diagram will, therefore, be $2.49 \times 2 = 4.98$ inches.

The clearance in M. P. cylinder was found to be 14 per cent.; therefore, 14 per cent. of $4.98 = 4.98'' \times 0.14 = 0.697$ inch. Set off from OY a distance equal to 0.697 inch, draw a line parallel with OY. Draw a horizontal line parallel with OX, at a height corresponding to the initial absolute pressure, in this cylinder, which in this case is 64.875 pounds absolute. Set off from OY on the horizontal line just described, a distance of 5.677 inches or 4.98 inches from the clearance line. Now divide the 4.98 inches into 20 equal parts, drawing ordinates parallel with OY. Set off on these ordinates the pressures corresponding to the similar ordinates on the indicator diagram (Fig. 21). After these pressures are all set off on their respective ordinates, as explained for the H. P. diagram. and the curves drawn in, we have the contour of the M. P. cylinder diagram.

Low-pressure Diagram

The diameter of the L. P. cylinder is 50 inches.

The area of a 50-inch cylinder is 1963.5 square inches.

The diameter of the H. P. cylinder is 19 inches.

The area of a 19″ cylinder is 283.53 square inches.

The ratio of the volume of L. P. to H. P. is therefore, $1963.5 \div 283.53 = 6.92$.

The high-pressure diagram having been made 2 inches in length, the length of the L. P. diagram will therefore be $6.92 \times 2 = 13.84$ inches.

Digitized by Google

The clearance in L. P. cylinder was found to be 9 per cent.; therefore, 9 per cent. of $13.84 = 13.84 \times 0.09 = 1.24$ inches. Set off from OY a distance equal to 1.24 inches; draw a line parallel with OY. Draw a horizontal line parallel with OX, at a height corresponding to the initial absolute pressure in this cylinder, which is in this case 20.2 pounds absolute. Set off from OY on the horizontal line just described, a distance of 15.08 inches, or 13.84 inches from the clearance line. Now divide the 13.84 inches into 20 equal parts, drawing ordinates parallel with OY. Set off on these ordinates the pressures corresponding to the similar ordinates on the indicator diagram, Fig. 21. After these pressures are all set off on their respective ordinates as explained for the H. P. and M. P. diagrams, and the curves drawn in, we have the contour of the L. P. cylinder diagram.*

We now have the three diagrams drawn to the same scale of pressures, and each diagram set out in its proper volumetric ratio, and with their proper clearances.

The next step is to draw the $PV = C$ curve.

The method of doing this has been described in a previous chapter, and need not be treated here. Any of the curves can be drawn, and they are of interest, and should be practiced by the student.

Drawing the curve $PV = C$ through the point of cut-off as shown, we note that, producing this curve to the maximum initial pressure, the cut-off is slightly reduced. This is known as the reduced cut-off, for we see that the cut-off on the indicator diagram of H. P. cylinder is 59 per cent. This is the nominal cut-off. The actual cut-off is nominal cut-off + clearance $= 0.59 + 0.14 = 73$ per cent. The reduced cut-off should be $\frac{(0.59+0.14) \times 161.52}{176.2} = 0.67$ or 67 per cent.

Measuring the combined diagram we see that it measures just 67 per cent. for $1\frac{1}{16}'' \div 2 = 53$ per cent.

$0.53 + 0.14 = 0.67$ or 67 per cent.

161.52 pounds is the cut-off pressure.

176.2 pounds is the initial pressure on H. P. piston.

Back Pressure Line

The assumed back pressure is 4 pounds absolute. From O on OY, set off a distance equal to 4 pounds, draw a horizontal line parallel with the perfect vacuum line OX.

Atmospheric Line

The atmospheric line should be drawn after pressure and vacuum lines are established. Therefore, from O on OY, set off a distance

* It may be found by some to be more desirable to work from the atmospheric line for H. P. and M. P. diagrams and above and below atmospheric line for L. P. diagram. This is optional.

Digitized by Google

equal to 15 pounds, draw a horizontal line parallel with the perfect vacuum line OX.

Looking at the combined diagrams, plate 2, we note that there is a drop of 10.8 pounds between boiler and piston of H. P. cylinder.

The boiler pressure was 187 pounds absolute.

The initial pressure by indicator diagram is 176.2 pounds absolute. Therefore, 187 − 176.2 = 10.8 pounds.

There is also a drop between the initial pressure and cut-off pressure. The cut-off pressure is 161.52 pounds, and the difference between 176.2 pounds and 161.52 pounds = 14.68 pounds.

The pressure in first receiver was 67 pounds. The initial pressure in M. P. cylinder was 64.875 pounds.

There is a drop in this receiver of 67 pounds − 64.875 pounds = 2.125 pounds.

The pressure in second receiver was 21 pounds.

The initial pressure in L. P. cylinder was 20.2 pounds.

There is a drop in this receiver of 21 pounds − 20.2 pounds = 0.8 pounds.

The theoretical diagram is that represented by OY, OX, and the curve PV = C.

The effective mean pressure of the ideal diagram is obtained as follows:

The initial steam pressure is 176.2 pounds absolute.

The reduced cut-off was 67 per cent. This is an actual and not a nominal cut-off.

The ratio of the volume of the L. P. cylinder to the H. P. cylinder is 6.92.

Now $0.67 = \frac{6.92}{X}$. Therefore, the total rate of expansion

$X = 6.92 \div 0.67 = 10.32$.

Now $\frac{1 + \text{hyp log } 10.32}{10.32} = 0.3224$.

The theoretical mean pressure = 176.2 × 0.3224 = 56.8 pounds.

The theoretical effective mean pressure = 56.8 pounds − 4 pounds = 52.8 pounds.

The effective mean pressure shown by H. P. diagram = 80.6 pounds.

The effective mean pressure shown by M. P. diagram = 29.687 pounds.

The effective mean pressure shown by L. P. diagram = 10.4 pounds.

Then the effective mean pressure referred is as before equal to $\frac{80.6}{6.92} + \frac{29.687}{2.77} + 10.4 = 11.64$ pounds + 10.71 pounds + 10.4 pounds = 32.75 pounds.

Digitized by Google

Now, as explained before, the card factor is a ratio, and represents the percentage of returns for investment. The card factor in this case is, therefore, $32.75 \div 52.8 = 0.62$. That is to say, the actual pressure is 62 per cent. of the theoretical. If the theoretical diagram is to be considered from initial pressure H. P. cylinder to perfect vacuum, then the card factor would be $32.75\# \div 56.8\# = 0.576$.

In all engineering investigations, accuracy should be the prime factor. Not only in the analysis and computations, but the instruments with which the data is obtained should be accurate, and should the instrument be in error, this error must be determined and allowed for. It will be found profitable, after all measurements of the diagrams have been made and recorded, to determine the effective mean pressures, from the measurements made, before combining, as the measurements are many, and having previously found the effective mean pressure of the diagrams by planimeter, it is a good check.

An example will make these remarks clear.

The effective mean pressure of the top indicator diagram of H. P. cylinder was found to be 80.6 pounds; from the ordinates we have 80.18 pounds. It is shown by Fig. 21 that measuring between the limits of the diagram the following pressures are obtained.

1st	Ordinate	31.3	pounds.
2d	"	54.125	"
3rd	"	75.8	"
4th	"	96.25	"
5th	"	101.06	"
6th	"	101.06	"
7th	"	101.06	"
8th	"	101.06	"
9th	"	101.07	"
10th	"	103.47	"
11th	"	103.475	"
12th	"	101.055	"
13th	"	97.455	"
14th	"	89.04	"
15th	"	80.59	"
16th	"	72.19	"
17th	"	64.97	"
18th	"	57.69	"
19th	"	45.69	"
20th	"	25.26	"
21st	"	0.	"
	Sum =	1603.67	

Digitized by Google

Digitized by Google

58

tl
is
is
b
tl

fa
n
tl
fe
h
fi
a
t

c
g
c

Digitized by Google

And $1603.67 \div 20 = 80.18$ pounds effective mean pressure. Showing a difference $= 80.6 - 80.18 = 0.42$ pounds, or .5 per cent. That is $\frac{1}{2}$ of 1 per cent. less.

Treating the M. P. and L. P. diagrams in a similar manner we obtain for the top diagram of M. P. cylinder 29.25 pounds. The effective mean pressure of the same diagram by planimeter is 29.687 pounds. Showing a difference of $29.687 - 29.25 = 0.437$ pounds, or 1.4 per cent. less.

For the top diagram of L. P. cylinder 10.81 pounds. The effective mean pressure of the same diagram by planimeter is 10.4. Showing a difference of $10.81 - 10.4 = 0.41$ pounds or nearly 4 per cent. greater.

This is sufficient to prove the accuracy of the different pressures. It will be noticed that in each diagram of the combined diagram, the effective mean pressure is inserted. Each diagram was carefully traced over with the planimeter and the pressures inserted obtained.

It may have been noted that the remarks upon the combined diagram took no account of the clearance in the L. P. cylinder. The diagrams and the combined diagrams, fig. 21a, are from the same engine as those shown on plate 2, but at a different time. Now taking into consideration the clearance in L. P. cylinder, our computations would be as follows: The nominal cut-off in H. P. cylinder is 75 per cent. The clearance in H. P. cylinder is equal to 14 per cent. of the cylinder volume.

The initial pressure as shown by H. P. cylinder diagram is 165.38 pounds absolute.

The pressure at cut-off H. P. cylinder as shown by diagram is 157.88 pounds absolute.

The equivalent cut-off from measurement is 84.5 per cent.

Thus nominal equivalent cut-off from measurement $= 70.5$ per cent. $70.5 + 14 = 84.5$ per cent.

The actual equivalent cut-off by computation is

$$\frac{(75+14) \times 157.88}{165.38} = 0.849 = 84.9 \text{ per cent.}$$

Initial volume for expansion is therefore 84.9 per cent.

The finial volume will therefore be $(100+9) \times 6.92$ where $6.92 =$ the ratio of $\frac{\text{L. P.}}{\text{H. P.}}$

Clearance in L. P. cylinder $= 9$ per cent. of the cylinder volume. Now $109 \times 6.92 = 754.28$

$$\text{The cut-off is therefore} = \frac{\text{initial volume}}{\text{finial volume}} = \frac{84.9}{754.28} = 0.112.$$

$$\text{The total rate of expansion} = \frac{1}{R} = \frac{1}{0.112} = 8.92.$$

Digitized by Google

If we take and divide the distance OX into volumes equal to OU, we see that it contains OU just 8.92 times. By the shorter method, as previously described, we have

Equivalent cut-off = 0.845.

Ratio $\frac{\text{L. P.}}{\text{H. P.}} = 6.92.$

Total ratio of expansion $= \frac{6.92}{0.845} = 8.18.$

The mean pressure per pound for 8.920 = .358.

The mean pressure per pound for 8.180 = .3759.

Taking initial pressure 165.38 pounds in both cases, we have

$165.38 \times 0.358 = 59.2$ pounds.

$165.38 \times 0.3759 = 62.16$ pounds.

Deducting 4 pounds back pressure in both cases, we have for effective mean pressure:

$59.2 - 4 = 55.2$ pounds.

$62.16 - 4 = 58.16$ pounds.

The difference = 2.96 pounds, or 5 per cent.

The effective referred mean pressure from diagrams = 33.7 pounds.

The card factor in the former case is $\frac{35.91}{55.2} = 0.65.$

The card factor in the latter case is $\frac{35.91}{58.16} = 0.617.$

Some designers do not deduct an assumed back pressure, treating the area between initial pressure and a vacuum.

The card factor then becomes in the first case: $\frac{35.91}{59.2} = 0.6.$

In the latter case the card factor is: $\frac{35.91}{62.16} = 0.577.$

It is thus seen that when the first value is taken or the first method, the cylinders would be slightly smaller than with the second method. That is to say, in designing with a referred, effective mean pressure the cylinders would be slightly smaller with the clearance in L. P. cylinder taken into consideration. It is, therefore, better to deal with the actual values from similar engines, and in computing the effective theoretical mean pressure, from the combined diagram the clearance in L. P. cylinder must be considered. Computing from actual data the card factor for several types of engines, the following gives a fair mean when determining the mean referred pressure without taking a theoretical back-pressure into consideration.

Digitized by Google

COMPOUND ENGINES

Large engines up to 100 revolutions per minute	0.6 to 0.68
Small engines	0.5 to 0.6
Triple expansion 3-cylinder engines	
Mercantile ships	0.55 to 0.58
Triple expansion 4-cylinder engines	0.5 to 0.54
Quadruple expansion	0.52



Fig. 22

It is absolutely necessary to exercise the greatest care in not only taking diagrams, but in computing the data, for unless the data is reliable it is simply a waste of time to analyze results. The value to the designer as well as to the practical engineer of the information to be derived from the indicator diagram cannot be over-estimated.

Before closing this subject we will consider some other curves, and describe the method of constructing them. It was at one time customary to plot what was termed the saturation curve when cards were combined. Others treated the PV = C curve as the curve of saturation.

Digitized by Google

The PV=C curve is and has been repeatedly referred to as the theoretical curve of expansion. In previous remarks, we see how absurd such reference is. The equation to the saturation curve is $PV^k=C$.

Now the exponent k for this curve is 1.0646, whilst the exponent for the hyperbola is 1.

The adiabatic curve is $PV^k=C$. The exponent k for this curve is 1.13.

It is interesting to plot these curves on a combined indicator diagram, to see their variations and peculiar features, and the exercise is highly instructive.



Volume	Decimal
1¼	0.789
1½	0.649
2	0.478
2½	0.377
3	0.311
3½	0.263
4	0.229
5	0.180
6	0.148

Saturation Curve.

Fig. 23

Curves of Expansion

With each figure there is given a table of the constants used in constructing the respective curves.

Fig. 22 shows a practical method of plotting the PV=C curve, and its construction is as follows: Let OY represent the absolute initial pressure; from O set off on OY a distance of 1 inch represented by OZ. Now set off on the line OX a distance equal to the volume up to cut-off. Complete the rectangle OYBA.

Digitized by Google

Draw a diagonal line from B passing through Z, and produce same to pass through O′ on the line of perfect vacuum produced. Set off on OX, a distance OB = 1¼ OA, OC = 1½ OA, OD = 2 OA, OE, = 2½ OA, OF = 3 OA, OG = 3½ OA, etc.

Now from O set off on OY a distance = 0.8 inch for 1¼ vols. 0.667 for 1½ vols., 0.5 for 2 vols., 0.4 for 2½ vols., 0.333 for 3 vols., 0.286 for 3½ vols. and 0.25 for 4 vols. Now pass diagonals through the corresponding points from O′ intersecting AB. From these points of intersection pass horizontal lines parallel with OX. The horizontals intersecting the ordinates erected on OX, as shown, locate points of the



Volume	Decimal
1¼	0.777
1½	0.632
2	0.457
2½	0.355
3	0.289
3½	0.243
4	0.209
5	0.162
6	0.132

Adiabatic Curve

Fig. 24

curve; passing a fair curve through these points gives us a curve known as the equilateral hyperbola, or PV = C curve. Taking the combined indicator diagrams, the volume is 73 per cent. and proceeding as just described we obtain the curve as there plotted.

Fig. 23 shows the saturation curve. This curve is constructed in precisely the same manner as the PV = C curve. The decimal corresponding to the volume is given in figure.

Fig. 24 shows the adiabatic curve of expansion. Constructed the same as explained for the two preceding curves. The decimal corresponding to the volume is given in the figure.

Digitized by Google

Indicator Diagrams

The following four diagrams are taken from the steam tug "Baltic." Diameter cylinder 16 inches; stroke of piston 16 inches.



Average M. E. P., 69.84 lbs.

6″ Cut-off. Steam, 120 lbs. 118 Revo.
133.561 I. H. P.
Scale of Spring, 60



Average M. E. P., 77.34 lbs.

7″ Cut-off Steam, 120 lbs. 120 Revo.
150.325 I. H. P.
Scale of Spring, 60

Digitized by Google



Average M. E. P., 83.44 lbs.

8″ Cut-off Steam, 120 lbs. 126 Revo.
170.317 I. H. P.
Scale of Spring, 60



Average M. E. P., 101.245 lbs.

Full Stroke of Valve Steam, 120 lbs. 132 Revo.
216.502 I. H. P.
Scale of Spring, 60

Digitized by Google

The following diagrams are from the first compound engine built in America.

This engine has cylinders of the following dimensions

High pressure cylinder 24 inches.

Low pressure cylinder 38 inches.

Stroke common to both 36 inches.

In the first chapter I stated that the defects incident to long indicator pipes would be discussed later.

Diagrams "a" and "b" are from the H. P. and L. P. cylinders respectively. The indicator pipe was arranged as shown in inset facing page 66 in fig. 1.

Looking at card "a,"



Card "a"

AMERICAN STEAM GAUGE AND VALVE MFG. CO. BOSTON. NEW YORK. CHICAGO.
EXCLUSIVE MANUFACTURERS OF
American Thompson Improved Indicator.
(Original Thompson Indicator.)

DIAGRAM from M. S.S. Geo. W. Clyde July 27th 1903
Engine 24"-38"x36"
Diameter of Cylinder 24"
Length of stroke 36"
Revolutions per Minute 77.7
Pressure of Steam in lbs. in Boiler 60
Position of Throttle Valve Full open
Vacuum per Gauge in inches 24
Temperature of Hot Well 126°
Scale of Spring 40
Inside Diameter of Feed Pipe
" " Exhaust Pipe
Valves

Built by Wm. Cramp
Pressure
Barometer Reads
Throttle
Regulator
REMARKS: Atmos 96°
injection 74°
Air Pump Disch 112°
Feed - 184°
Data for Card "a"

Digitized by Google



Fig .1



Fig. 2

Digitized by Google

Digitized by Google

we see the drop between boiler and H. P. piston is 5 lbs. for top, 2.5 lbs. for bottom. The initial steam pressure top is 55 lbs. gauge or 70 lbs. absolute. For the bottom the initial pressure is 57.5 lbs. gauge or 72.5 lbs absolute. The absolute steam pressure is 75 lbs. The M. E. P. top is 41.25 lbs. M. E. P. bottom is 35.625 lbs. Giving a difference between top and bottom of 5.625 lbs. The average M. E. P. is $41.25\#+35.625\#=76.875$ lbs. $76.875\div 2=38.4375$ lbs.

For card "b,"



Card "b"

AMERICAN STEAM GAUGE AND VALVE MFG. CO. BOSTON. CHICAGO. NEW YORK. EXCLUSIVE MANUFACTURERS OF
American Thompson Improved Indicator. (Original Thompson Indicator.)

DIAGRAM from M. S. S. Geo W. Clyde July 27th 1903
Engine 24"-38"x36"
Diameter of Cylinder 38"
Length of stroke 36"
Revolutions per Minute 77.7
Pressure of Steam in lbs. in Boiler 60
Position of Throttle Valve Full Open
Vacuum per Gauge in Inches 24
Temperature of Hot Well 126°
Scale of Spring 12
Inside Diameter of Feed Pipe
" " Exhaust Pipe
Valves
Built by Wm Cramp
Pressure
Barometer Reads
Throttle
Regulator
REMARKS: Atmos 96°
injection 74°
Air Pump Disch 112°
Feed 184°
Data for Card "b"

we have a receiver pressure of 5 lbs. gauge or 20 lbs. absolute. The drop in receiver is for top 2.25 lbs. and 1.5 lbs. for bottom. The initial steam pressure top is 2.75 lbs. gauge of 17.75 lbs. absolute. For the bottom the initial pressure is 3.5 lbs. gauge or 18.5 lbs. absolute.

Digitized by Google

The M. E. P. top is 12.93 lbs. M. E. P. bottom is 11.0625 lbs., giving a difference of 1.8675 lbs. The average M. E. P. is $12.93\# + 11.062\# = 23.992$ lbs. $23.992 \div 2 = 11.996$ lbs.

The constant for the H. P. cylinder $= \frac{PLA2N}{33000}$.

Let the M. E. P. pressure = 1 pound.

Piston speed in feet = 1 foot per minute.

Then the constant for 1 lb. M. E. P and one foot of piston speed $= \frac{1 \times 1 \times 452.39 \times 2 \times N}{33000} = \frac{904.78}{33000} = 0.02741.$

The constant for L. P. cylinder $= \frac{1134.1 \times 2}{33000} = \frac{22682}{33000} = 0.06873.$

The average M. E. P. H. P. cylinder = 38.4375

The average revolutions = 77.7

The stroke of piston = 3 feet.

The indicated horse power developed in H. P. cylinder is, therefore, $C \times M.E.P. \times N \times L = 0.02741 \times 38.4375 \times 77.7 \times 3 = 245.571$ horse power.

The indicated horse power developed by L. P. cylinder is, therefore, $C \times M.E.P. \times N \times L = 0.06873 \times 11.996 \times 77.7 \times 3 = 192.189$ horse power.

The collective I. H. P. $= 245.571 + 192.189 = 437.76$.

The ratio of cylinder capacities = area L. P. cylinder $\div$ area H. P. cylinder $= 1134.1 \div 452.59 = 2.56$.

The aggregate equivalent M. P. referred to L. P. piston is, therefore, $\frac{\text{M. E. P. H. P. Cyl.}}{\text{Ratio } \frac{\text{L. P.}}{\text{H. P.}}} + \text{M. E. P. L. P. Cyl.} = \frac{38.4375}{2.56} + 11.996 =$ $15.01\# + 11.996\# = 27$ lbs.



Card "c"

Digitized by Google

Diagrams "c," "d" and "e" are from the same engine but with short connections (see fig. 2 of inset facing page 66).

AMERICAN STEAM GAUGE AND VALVE MFG. CO. BOSTON. CHICAGO. NEW YORK. EXCLUSIVE MANUFACTURERS OF **American Thompson Improved Indicator.** (Original Thompson Indicator.)

August 10th 1903

DIAGRAM from M S.S. Geo W. Clyde Engine

Diameter of Cylinder	24"	Built by	
Length of stroke	36"	Pressure	
Revolutions per Minute	75	Barometer Reads	
Pressure of Steam in lbs. in Boiler	58	Throttle	
Position of Throttle Valve	Full Open	Regulator	
Vacuum per Gauge in Inches	22.75	REMARKS:	Conditions same as July 27th 1903
Temperature of Hot Well	126°		
Scale of Spring	40		
Inside Diameter of Feed Pipe			
" " Exhaust Pipe			
Valves			



Card "d"



Card "e"

Taking diagram "c" we see that the drop between boiler and H. P. piston is 7.5 lbs. for top, 6.75 for bottom. The initial steam pressure

Digitized by Google

top is 50.5 lbs. or 65.5 lbs. absolute. For the bottom the initial pressure is 51.25 lbs. gauge or 66.25 lbs. absolute. The absolute steam pressure is 73 lbs. The M. E. P. top is 36.25 lbs., M. E. P. bottom is 35 lbs., giving a difference between top and bottom of 1.25 lbs.



The average M. E. P. is 36.25# + 35# = 71.25 lbs. 71.25 ÷ 2 = 35.625 lbs.

For diagrams "d" and "e" we have no drop in receiver. The receiver pressure is 6.75 lbs. gauge or 21.75 lbs. absolute. The M. E. P. of L. P. top is 15 lbs. The M. E. P. of L. P. bottom is 13.875 lbs.

The average M. E. P. is 15# + 13.875# = 28.875 lbs. 28.875 ÷ 2 = 14.875 lbs.

The constant for H. P. cylinder we found to be 0.02741.

Now for H. P. cylinder the I. H. P. is thus found to be $0.02741 \times 35.625 \times 75 \times 3 = 219.712$ I. H. P.

The constant for L. P. cylinder was 0.06873.

The I. H. P. L. P. cylinder is thus found to be $0.06873 \times 14.875 \times 75 \times 3 = 229.95$ I. H. P., say 230.

The collective I. H. P. = 219.712 + 230 = 449.712.

The aggregate equivalent M. P. referred to L. P. piston is, therefore,

$$\frac{35.625}{2.56} + 14.875 = 13.91\# + 14.875\# = 28.785 \text{ lbs.}*$$

Following are two series of indicator diagrams. Taken from a double screw ferryboat, whose cylinders measure

$$\frac{18'' \times 38''}{28''} \text{ and } \frac{18'' \times 38''}{28''}$$

RUN	REV.	RUN	REV.
1 and 2	128¼	5 and 6	128½
3 and 4	130	Average of all Runs	128.9

* A close perusal of the diagrams from the G. W. Clyde will prove the uncertainty and, in fact, unreliability of ordinary indicator pipes as fitted. If on trial trip the ordinary method of one instrument to each cylinder is insisted upon, then before any data is taken, diagrams with short connections should be made, and hence a correction factor is determined. After this has been done, we have a check for the diagrams, and no error need be introduced.

Digitized by Google

SERIES 1



RUN NO. 1A

Steam 150 For'd Rec. 24 Aft. Rec. 24 Vac. 24″ Rev. 127

I. H. P., F. H. P. 354.3 I. H. P., F. L. P. 299.8

I. H. P., A. H. P. 409.0 I. H. P., A. L. P. 334.6 Total, I. H. P. 1397.7

Throttle wide open. Gear: { F. H. P. linked in $3\frac{3}{16}$″. A. H. P. linked in $2\frac{11}{16}$″. F. L. P. linked full out. A. L. P. linked full out.

Digitized by Google

SERIES 2









RUN NO. 2B

Steam 132½ L. P. Rec. 23 Vac. 24½" Rev. 139

I. H. P., F. H. P. 420.0 I. H. P., F. L. P. 371.75

I. H. P., A. H. P. 422.0 I. H. P., A. L. P. 388.79 Total, I. H. P. 1602.54

Throttle wide open. Full Gear.

Digitized by Google

SERIES 2









RUN NO. 3A

Steam 112 L. P. Rec. 18 Vac. 25″ Rev. 128

I. H. P., F. H. P. 313.16 I. H. P., F. L. P. 305.04

I. H. P., A. H. P. 326.78 I. H. P., A. L. P. 291.92 Total, I. H. P. 1236.90

Throttle wide open. Full Gear.

Digitized by Google

SERIES 2









RUN NO. 4A

Steam 122 L. P. Rec. 19½ Vac. 25¾" Rev. 137½

I. H. P., F. H. P. 391.24 I. H. P., F. L. P. 371.26

I. H. P., A. H. P. 399.15 I. H. P., A. L. P. 350.12 Total, I. H. P. 1511.77

Throttle wide open. Full Gear.

Digitized by Google

SERIES 2



RUN No. 5B

Steam 150 L. P. Rec. 28 Vac. 24″ Rev. 140

I. H. P., F. H. P. 439.82 I. H. P., F. L. P. 448.4

I. H. P., A. H. P. 454.71 I. H. P., A. L. P. 394.14 Total, I. H. P. 1737.07.

Throttle wide open. All linked up $\frac{3}{4}$.

Digitized by Google

SERIES 2









RUN NO. 6B

Steam 125 L. P. Rec. 23 Vac. 27″ Rev. 138½

I. H. P., F. H. P. 390.06 I. H. P., F. L. P. 391.17

I. H. P., A. H. P. 399.96 I. H. P., A. L. P. 372.61 Total, I. H. P. 1553.80

Throttle wide open. All linked up ¾.

Digitized by Google

SERIES 3

ENGINE $\frac{25'' \times 41\frac{1}{2}'' \times 68''}{42''}$

Steam Pressure, 170 lbs. per square inch designed. Boiler Pressure, 150 lbs. on trial. 1st Receiver 44 lbs. 2d Receiver 6½ lbs. Vacuum, 26 inches.

Revolutions 86 lbs.







I. H. P. 710.68 H. P. Cyl. I. H. P. 551.10 L. P. Cyl.
I. H. P. 727.09 I. P. Cyl. Total, 1,988.87

Mean Pressure, Ref. D. to L. P. Cyl. = 28.62 lbs.

Throttle full open. All valves linked up to cut-off 29¾" top, 26½" bot.

Digitized by Google

SERIES 4

ENGINE $\frac{34'' \times 57'' \times 104''}{63''}$

HIGH PRESSURE	INTERMEDIATE PRESSURE	LOW PRESSURE
Diam. Cylinder....34″	Diam. Cylinder....57″	Diam. Cylinder...104″
Diam. Piston Rod...9″	Diam. Piston Rod...9″	Diam. Piston Rod...9″
Stroke.....63″	Stroke .....63″	Stroke.....63″
Scale of Spring ...120	Scale of Spring.....60	Scale of Spring. 10 & 20
I.H. P. Constant .2787	I. H. P. Constant..8019	I.H.P. Constant 2.6928







M. E. P.	I. H. P.	
H = 115.05	H = 2,661.35	Steam ..... 232.
M = 52.95	M = 3,524.23	M. P. Rec. ..... 81.
L = 17.07	L = 3,815.19	L. P. Rec..... ..... 19.
	Total, 10,000.77	Vacuum ..... 25.5″
		R. P. M. ..... 83.
		Piston Speed 871.5
		Cut Off ..... Full

Digitized by Google

SERIES 4







M. E. P.	I. H. P.		
H = 110.4	H = 2,524.	Steam	230.
M = 54.3	M = 3,570.	M. P. Rec.	79.
L = 16.43	L = 3,630.	L. P.Rec.	16.
	Total, 9,724.	Vacuum	24.5″
		R. P. M.	82.
		Piston Speed	861.
		Cut off	Full

Digitized by Google

SERIES 4







M. E. P.	I. H. P.		
H = 130.99	H = 2,885.	Steam	232.
M = 48.15	M = 3,050.	M. P. Rec.	65.
L = 13.71	L = 2,917.	L. P. Rec.	12.5
	Total, 8,852.	Vacuum	25.″
		R. P. M.	79.
		Piston Speed	829.5
		Cut off	Full

Digitized by Google

SERIES 4







M. E. P.	I. H. P.		
H = 126.15	H = 2,707.4	Steam	225.
M = 41.55	M = 2,565.3	M. P. Rec.	62.
L = 13.50	L = 2,799.1	L. P. Rec.	11.25
	Total, 8,071.8	Vacuum	24."
		R. P. M.	77.
		Piston Speed	808.5

Cut off: H. P. = .71, M. P. = .732, L. P. = Full

Digitized by Google

SERIES 4







M. E. P.	I. H. P.		
H = 123.6	H = 2,602.	Steam	220.
M = 41.7	M = 2,525.	M. P. Rec.	59.
L = 12.81	L = 2,605.	L. P. Rec.	10.5
	Total, 7,732.	Vacuum	25.5″
		R. P. M.	75.5
		Piston Speed	79.3

Cut off: H. P. = .71, M. P. & L. P. = Full

Digitized by Google

SERIES 4







M. E. P.	I. H. P.		
H = 122.55	H = 2,561.84	Steam	220.
M = 41.10	M = 2,471.60	M. P. Rec.	61.
L = 11.74	L = 2,360.95	L. P. Rec.	10.5
	Total, 7,394.39	Vacuum	25."
		R. P. M.	75.
		Piston Speed	787.5

Cut off: H. P. = .69, M. P. & L. P. = .75

Digitized by Google

SERIES 4



M. E. P.	I. H. P.		
H = 125.1	H = 2,553.7	Steam	210.
M = 36.9	M = 2,167.5	M. P. Rec.	49.5
L = 10.48	L = 2,067.2	L. P. Rec.	8.0
	Total, 6,788.4	Vacuum	25."
		R. P. M.	73.25
		Piston Speed	769.125

Cut off: H. P. = .66, M. P. — .75, L. P. = .735

Digitized by Google

SERIES 4







M. E. P.	I. H. P.		
H = 114.3	H = 2,301.66	Steam	202.
M = 36.0	M = 2,085.48	M. P. Rec.	50.
L = 10.77	L = 2,095.41	L. P. Rec.	8.
	Total, 6,482.55	Vacuum	25.″
		R. P. M.	72.25
		Piston Speed	758.6

Cut off: H. P. = .69, M. P. = .73, L. P. = .75

Digitized by Google

SERIES 4



M. E. P.	I. H. P.		
H = 110.55	H = 2,141.3	Steam	204.
M = 34.42	M = 1,918.3	M. P. Rec.	45.
L = 9.75	L = 1,828.4	L. P. Rec.	6.5
	Total, 5,888.0	Vacuum	25.5″
		R. P. M.	69.5
		Piston Speed	729.75

Cut off: H. P. = Normal, Throttled, M. P. & L. P. = Full

Digitized by Google

TRIAL TRIP OF PASSENGER STEAMER AT DELAWARE BREAKWATER

NO. OF RUN	STARBOARD ENGINE						PORT ENGINE						TOTAL I. H. P.
	STEAM	1ST REC.	2D REC.	VAC. INS.	REV.	I. H. P.	STEAM	1ST REC.	2D REC.	VAC. INS.	REV.	I. H. P.	
1	145	18	−9	26	99	305.8	145	17	−7½	26½	96	308.4	614.2
2	144	17	−8½	25½	96½	392.5	145	16½	−7½	26½	97½	305.2	697.7
3	133	33½	0	25	118	739.2	133	35	1	26	119	656.5	1,395.7
4	137	34½	0	26	122	711.8	137	33½	0	27	123	740.1	1,451.9
5	147	51	5½	25½	136	No Cards	147	54	3	26½	136	No cards	Taken
6	150	52	6	26	136	No Cards	150	54	3	26	137	No cards	Taken
7	155	55	7	26	142	1,126.1	155	56	5	26	143	1,111.5	2,237.6
8	158	57	10	26	146½	1,192.3	158	57	7	26	146½	1,216.9	2,409.2

Scale of Springs used: H. P. = 80 lbs. M. P. = 30 lbs. L. P. = 16 lbs.

Length of course = 1.261 nautical miles.

Engine $\frac{19\frac{1}{4}'' \times 30'' \times 50''}{30''}$

Digitized by Google

SERIES 5

H.P. = 108.6 I.H.P



I P. = 128.0 I.H.P.
M.E.P. = 12.08 lbs.





L.P = 69.2 I.H.P.
M.E.P. = 2.35 lbs.

No. 1 STARBOARD

Digitized by Google

SERIES 5







L.P. = 87.2 I.H.P.
M.E.P. = 3.04 lbs

No. 2 STARBOARD

Digitized by Google

SERIES 5







NO. 3 STARBOARD

Digitized by Google

SERIES 5







NO. 4 STARBOARD

Digitized by Google

SERIES 5







No. 7 STARBOARD

Digitized by Google

SERIES 5







NO. 8 STARBOARD

Digitized by Google







No. 1 PORT

Digitized by Google

SERIES 5

H.P. = 120.7 I.H.P.



I.P. = 107.7 I.H.P.
M.E.P. = 10.32 lbs.





L.P. = 76.8 I.H.P.
M.E.P. = 2.65 lbs.

No. 2 PORT

Digitized by Google

SERIES 5



No. 3 PORT

Digitized by Google

Digitized by Google

Digitized by Google

SERIES 5







No. 4 PORT

Digitized by Google

SERIES 5







No. 7 PORT

Digitized by Google

SERIES 5







No. 8 PORT

Digitized by Google

SERIES 6

INDICATOR DIAGRAMS TAKEN FROM ENGINE $\frac{23'' \times 37\frac{1}{2}'' \times 43'' \times 43''}{30''}$



No. 1 STARBOARD

Steam 145 lbs. 1st Rec. 38 lbs. 2d Rec. 3 lbs. Vac. 22″ Rev. 160
I. H. P., H. P. 781.5 I. H. P., I. P. 604.0
I. H. P., F. L. P. 243.9 I. H. P., A. L. P. 290.4 Total I. H. P. 1919.8
Scale of springs used: H. P. = 80 lbs., M. P. = 30 lbs., L. P. = 16 lbs.

Digitized by Google

SERIES 6



NO. 2 STAR. ENG.

Rev. 160

I. H. P., H. P. 862.1	I. H. P., I. P. 690.8	
I. H. P., F. L. P. 252.7	I. H. P., A. L. P. 298.8	Total, 2,104.4

Digitized by Google

SERIES 6









No. 3 STAR. ENG.

Rev. 160

I. H. P., H. P. 835.9 I. H. P., I. P. 728.3
I. H. P., F. L. P. 294.2 I. H. P., A. L. P. 337.9 Total, 2,196.3

Digitized by Google

SERIES 6









NO. 4 STAR ENG.

Steam 150 1st Rec. 20 2d Rec. –5 Vac. 21″ Rev. 128

I. H. P., H. P. 457.6	I. H. P., I. P. 317.0	
I. H. P., F. L. P. 113.5	I. H. P., A. L. P. 123.9	Total, 1,012.0

Digitized by Google

SERIES 6









NO. 5 STAR. ENG.

Steam 149 1st Rec. 30 2d Rec. 2 Vac. 21″ Rev. 142
I. H. P., H. P. 622.1 I. H. P., I. P. 422.9
I. H. P., F. L. P. 158.4 I. H. P., A. L. P. 191.2 Total, 1,394.6

Digitized by Google

SERIES 6









NO. 6 PORT ENG.

Steam 125 1st Rec. 20 2d Rec. 6 Vac. 21″ Rev. 125

I. H. P., H. P. 390.2	I. H. P., I. P. 301.2	
I. H. P., F. L. P. 77.3	I. H. P., A. L. P. 99.8	Total, 868.5

Digitized by Google

SERIES 6









NO. 7 PORT ENGINE

Steam 143 1st Rec. 30 2d Rec. 2 Vac. 21″ Rev. 138
I. H. P., H. P. 481.2 I. H. P., I. P. 418.0
I. H. P., F. L. P. 150.0 I. H. P., A. L. P. 179.1 Total, 1228.3

Digitized by Google

SERIES 7



80 lbs. Spring.



30 lbs. Spring.

Ford Low Press. I.H.P 93.0



16 lbs. Spring.

Aft Low Press. I.H.P. 83.8



16 lbs. Spring.

No. of Run	Steam	1st Rec.	2d Rec.	Vac.	Rev.
1	115	33	−1	24½″	110

Digitized by Google

SERIES 7









No of Run	Steam	1st Rec.	2d Rec.	Vac.	Rev.
4	135	46½	3¾	24½"	122

Digitized by Google

SERIES 7









No. of Run	Steam	1st Rec.	2d Rec.	Vac.	Rev.
5	168	57	8	24″	133

Digitized by Google

SERIES 7







16 lbs. Spring.



16 lbs. Spring.

No. of Run	Steam	1st Rec.	2d Rec.	Vac.	Rev.
6	170	59	10	25″	134

Digitized by Google

LOG OF TRIAL TRIP OF JANUARY 24, 1907

Freight Steamer "Tuscan"	Points Down	Time	Elapsed Time Minutes	Nautical Miles	Statute Miles	Speed Knots	Speed Miles	Mean Rev's	Mean Steam	Mean I.H.P	%
Place, Patapsco River and Chesapeake Bay	Passed Sandy Point	11-12-13									
			32′, 2″	7.4	8.5	13.8	15.87	81.6	182.6	2838	21
270 Tons Coal	" Thomas Point	11-44-15									
			14′, 14″	3.25	3.74	13.68	15.73				
F. W. Tanks Full	" Bloody Point	11-58-29									
Draft on Trial — For'd .... 9′, 9″	" Bloody Point	12-07-00									
Aft .....13′, 6″			11′, 45″	3.25	3.74	16.6	19.0				
Mean ...11′, 7½″	" Thomas Point	12-18-45									
			27′, 15″	7.4	8.5	16.26	18.69	86.4	185.3	3079	13
Wetted Surface, 12,800 Square Feet	" Sandy Point	12-46-00									
	" Sandy Point	12-55-00									
			30′, 03″	7.4	8.5	14.76	16.97	83.5	176.5	3059	19
I.H.P. per 100 square inches, W. S. @ 10 knots, 6.6	" Thomas Point	1-25-03									
Displacement, 2,260 Tons	" Thomas Point	1-35-00									
			28′, 15″	7.4	8.5	15.72	18.07	84.6	170.3	2983	14
Admirality Co-eff., 200.9	" Sandy Point	2-03-15									
Fore Peak Tank Full to 1 ft. of Lower Deck	" Sandy Point	2-10-00									
			30′, 15″	7.4	8.5	14.64	16.83	85.5	184	3252	20
Aft. Tank Full	" Thomas Point	2-40-15									
	Thomas Point	2-59-30									
			27′, 30″	7.4	8.5	16.14	18.56	83.3	180.6	2928	15
	Sandy Point	3-27-00									

Digitized by Google

	No. Card	Time	Steam	Vac.	M. P. Rec.	L. P. Rec.	Rev.	M.R.P.	I. H. P. H. P.	I. H. P. M. P.	I. H. P. L. P.	I. H. P. Total
C	1	10–45	180	27	66	14	83.3	33.0	823.27	870.21	1090.91	2784.39
C	2	11–00	186	27	67	16	83.3	34.0	840.66	805.72	1216.79	2863.17
O	3	11–15	184	27	70	19	85	34.2	780.91	855.05	1305.84	2941.80
C	4	11–30	185	27	67	16	82	33.4	821.84	793.15	1156.50	2771.49
C	5	11–45	183	27¼	65	14	84.5	32.8	846.89	749.11	1106.63	2802.63
O	6	12–00	188	27	72	19	85	35.5	798.66	904.38	1348.66	3051.70
O	7	12–15	183	27	72	20	83	34.4	693.22	867.04	1421.44	2981.70
O	8	12–30	188	27	80	22½	85.6	35.2	643.50	894.20	1509.08	3046.78
O	9	12–45	185	27	78	21½	85	37.4	615.26	1118.14	1477.10	3210.50
O	10	1–00	178	27	74	20	82.5	37.0	597.17	1089.50	1412.89	3099.56
O	11	1–15	175	27	72	20	83.3	35.8	602.96	1031.32	1384.62	3018.90
O	12	2–15	178	27	77	23	85	37.4	427.11	1141.03	1541.32	3209.46
O	13	2–30	190	27	77	21	86	37.9	682.36	1098.02	1516.13	3296.51
C	14	2–45	182	27	66	16	82.6	33.6	773.86	894.82	1141.15	2809.83
C	15	3–00	176	27¼	63	14½	82.6	31.9	735.87	846.89	1081.76	2664.52
O	16	3–15	183	27	72	20½	84	35.6	689.88	942.49	1396.26	3028.73
O	17	3–30	183	27	73	21	83.5	36.6	627.67	991.49	1472.06	3091.22

Card marked "C" by pass closed. Cards marked "O" by pass open.

1st Mean					2nd Mean					3rd Mean					4th Mean				
Steam	Rev.	I.H.P.	Speed Knots	Speed Miles	Steam	Rev.	I.H.P.	Speed Knots	Speed Miles	Steam	Rev.	I.H.P.	Speed Knots	Speed Miles	Steam	Rev.	I.H.P.	Speed Knots	Speed Miles
182.6	81.6	2838	13.8	15.87	183.9	84	2958	15.03	17.28										
185.3	86.4	3079	16.26	18.69						178.6	84	2989	15.13	17.40					
176.5	83.5	3059	14.76	16.97	173.4	84	3021	15.24	17.52						178.2	84.1	3022	15.22	17.51
170.3	84.6	2983	15.72	18.07						177.8	84.2	3055	15.31	17.63					
184	85.5	3252	14.64	16.83	182.3	84.4	3090	15.39	17.74										
180.6	83.3	2928	16.14	18.56															

Digitized by Google

LOG OF TRIP OF JANUARY 28 AND 29, 1907—BALTIMORE TO PHILADELPHIA

Freight Steamer "Tuscan"	Points Down	Time	Elapsed Time Minutes	Nautical Miles	Statute Miles	Speed Knots	Speed Miles	Mean Rev's	Mean Steam	Mean I.H.P.	Slip %
Place, Patapsco River and Chesapeake Bay	Passed Sandy Point	3-14-45									
310 Tons Coal	" Thomas Point	3-45-30	30′, 43″	7.4	8.5	14.44	16.60	81.6	170	2480	18
F. W. Tanks Full	" Sharps Island.....	4-52-20	66′, 50″	15.3	17.6	13.72	15.79	79.2	171	2472	20
Draft { For'd.....10′, 4″ Aft.....13′, 8″ Mean ....12′, 0″	" Coye Point	5-52-50	60′, 30″	15.2	17.5	14.76	16.97	80.4	174		14
	" Cedar Point	6-13-30	20′, 40″	5.2	6.0	15.05	17.30	81.6	178.3		15
Wetted Surface, 13,000 Square Inches	" Point Lookout	7-17-00	63′, 30″	15.4	17.7	14.54	16.72	81.	180		17
I.H.P. per 100 square inches, W. S., @ 10 knots, 6.6	" Smith's Point.....	8-00-50	43′, 50″	10.7	12.3	14.62	16.81	77.4	170.6		15
Displacement, 2,340 Tons	" Wind Mill	9-11-00	70′, 10″	17.0	19.5	14.51	16.69	78.6	165		15
Admiralty Co-eff., 202.2	" Wolf Trap	10- 5-45	54′, 45″	12.2	14.0	13.36	15.36	79.2	175		22
Fore Peak Tank Full to 1 ft. of Lower Deck	" York Spit	10-53-20	47′, 35″	10.6	12.2	13.21	15.19	80.4	179		23
Aft. Tank Full											

Digitized by Google

READINGS OF TRIP, JANUARY 28 AND 29, 1907

No. Card	Time	Steam	Vac.	M. P. Rec.	L. P. Rec.	Rev.	M.R.P.	I. H. P. H. P.	I. H. P. M. P.	I. H. P. L. P.	I. H. P. Total
1	3–25	170	26½	62	11	79	30.6	758.78	733.56	955.02	2447.36
2	3–40	170	26½	63	11	79	31.5	775.28	764.13	974.91	2514.32
3	4–35	170	26¼	63	12	79	30.4	742.98	733.56	955.02	2431.56
4	6–00	180	26	65	13½	81.5	32.1	822.50	788.31	1046.81	2657.62
5	7–40	172	26	60	11	79.5	31.5	763.57	768.96	1001.10	2533.63
6	10–00	180	25½	68	14	80.3	31.9	793.52	807.77	990.95	2592.24
7	11–00	178	25¼	70	15½	81	33.3	749.80	877.49	1102.40	2729.69
8	11–45	175	25¾	70	15	81	31.8	738.53	846.15	1019.99	2604.67

NOTE—Cards 1 to 5 inclusive taken January 28, 1907. Cards 6, 7, 8, taken with coal test, January 29, 1907.

Coal used from 9.30 A. M. to 12.00 M., 14763 lbs.

Coal used per hour, 5905 lbs.

Coal used per I. H. P., per hour, 2.29 lbs.

Coal used per sq. foot of grate per hour, 20.9 lbs.

Digitized by Google

TUSCAN







By Pass Closed.

Time-10^{45} A.M. Date, 1-24-1907.
Card No. 1. Vac.-27.5
Steam-180 lbs. M.R.P.-330
M.P. Rec. 66 L.P. Rec. 140
R.P.M.=83.3 I.H.P.=278439

Digitized by Google

TUSCAN







By Pass Closed.

Time-6^{00} P.M	Date, 1-28-1907
Card No. 4	Vac-26.0
Steam-180 lbs.	M.R.P. 32.1
M.P.Rec. 65	L.P Rec. 13.5
R.P.M.-81 5	I.H.P-2657.62

Digitized by Google

TUSCAN



By Pass Open.

Time-2^{30} P.M.	Date-1-24-1907.
Card No. 13	Vac-2.7
Steam-190 lbs.	M.R.P. 37.9
M.P. Rec. 77.	L.P. Rec. 21.
R.P.M. - 86.	I.H.P. 3296.51.

The preceding series of diagrams are representative of modern marine engine practice. The data is sufficiently full to enable a thorough analysis to be made. They are worthy of close and careful study, and, being exact reproductions, can therefore be measured.

Further comment is unnecessary.

Digitized by Google

CHAPTER IV

Valve Diagrams

We will first describe the construction of the Zeuner diagram, and then the construction of the diagram for Marshall valve gear.

On plate 3 is shown valve diagrams for each cylinder of the engine shown on plate 1, the indicator diagrams of which are shown on page 95.

The construction will be made for top only (see plate 4), as the method for bottom is precisely the same.

Draw the horizontal line XX, and produce it to a sufficient length to take in the length of connecting rod between centers to same scale as selected for crank pin circle. Draw the vertical line YY, intersecting XX, in O. With O as center and radius equal to throw of crank, or half stroke, describe the crank pin circle A, B, C, D. This circle is drawn to any convenient scale; as shown it is drawn 3″=1 foot. Divide the diameter C, A, into 10 equal parts, each division representing $\frac{1}{10}$ of the stroke. With O as center, and radius equal to the eccentricity or half travel of the valve, describe the circle E, F, G, H. Now mark the end which is to be taken as top, and which one for bottom, selecting the right hand of diagram for top, as shown, and with G as center describe an arc i equal to the lead. It is better to make the valve diagram twice full size, as then the intersections of the different lines are shown with more distinctness.

Now set off from C a distance equal to the cut-off either in inches or percentage, and with a radius equal to connecting rod length as before, describe an arc, intersecting the crank pin circle in K. From O draw a diagonal line passing through K and cutting the circle of valve-travel in K_1. From K_1 draw a diagonal line tangent to the lead arc i and cutting the circle at L.

Through O draw a line OM perpendicular to K_1 L, cutting it in N. With O as center and ON as radius, describe an arc; ON is then the steam lap, and NM the maximum port opening.

Bisect the line OM, and with P as center describe the valve circles Q, R, S, and Q_1, R_1, S_1.

Through O draw a line parallel with K_1 L, and at the points of intersection with the travel circle T U_1 as centers describe arcs equal to the exhaust lap. If the exhaust lap is negative the circle will lie in the upper valve-cirlce, Q, R, S, and if positive it will lie in the lower valve-

Digitized by Google

circle Q_1, R_1, S_1. The reason for describing the arc at points T and U_1 is due to the fact that the intersection of the arc representing exhaust lap, with the valve-circle as at V, is rather difficult to exactly determine, and may cause variation.

From O draw diagonals tangent to the circles, and at the points where they cut the crank pin circle as at W, W_1, drop arcs with radius equal to radius of connecting rod, upon the diameter C, A. This gives the point of stroke at which release and compression takes place. With O as center and a radius equal to port opening plus exhaust lap describe an arc, cutting the lower valve-circle in Z, Z_1; from O draw diagonal lines through the points of intersection. This gives us the points between which the exhaust valve is full open.

Upon examining the diagram we see that the crank has to pass through the angle G, O, K_1, to arrive at the point where the steam is cut off; this point is shown at 1 where the lap-circle cuts the valve-circle.

Angle M, O, F, is the angle of advance. That is to say, when engine is turning over, the center of the eccentric sheave leads the center line of crank by 90 degrees plus the angle of advance; hence having the required lead, and point of cut-off we can by the construction determine the required angle.*

If the exhaust lap is negative, then the point of intersection of the lap circle with the valve-circle, point 2, shows where the valve opens to release the expanded steam. If, therefore, we desire to determine the point of release, we see that if it is desired to release later in the stroke the lap may have to be positive and if on the other hand we desire it earlier we need negative lap.

The distance between the intersection of the lap-circle with the diameter GE, and where the valve-circle cuts the diameter GE, is equal to the lead.

Again at point 3, where the lap-circle intersects the valve-circle this point of intersection shows where the valve starts to open for lead.

The analysis of the valve diagram enables us to determine the effects of any changes we may desire to make. Thus suppose we desire to cut off longer in the stroke, in other words to permit the steam to follow longer, the lead to remain unchanged. It is evident that to maintain the same lead, the steam lap must be reduced. Suppose, however, the lap is required to remain unchanged. It is evident that the lead must be reduced. The other changes involved will be left for the student to work out, and only by working out these different

* If engine turns under, the angle which the center of eccentric sheave makes with crank is 90 degrees—the angle of advance.

Digitized by Google

problems, in other words, constructing the diagram and discussing it, can he ever expect to be able to properly analyze it as it is impossible by mere reading to perform, and further, the subject is so broad and interesting that it is only by actual performance that one is able to grasp the details. There are several different diagrams used for analyzing the slide-valve operated by eccentrics, but the Zeuner is the most beautiful.

The diagrammatic work to the right of the diagram is only given to make the subject if possible more clear, and as before mentioned the diagrams shown on plate 3 should be very carefully studied.

The Marshall Valve Gear

The Marshall valve gear is one of the types of radial valve gears, which is used more extensively in marine practice than any other radial gear.

The diagram for Marshall valve gear and a valve diagram are shown on plate 5.

We will take a concrete case, and lay down the diagram, from the following data:

Travel of valve, $6\frac{13}{16}''$.
Lap of valve top, $1\frac{5}{16}''$.
Lap of valve bottom, $1\frac{1}{4}''$.
Lead top, $\frac{7}{16}''$.
Lead bottom, $\frac{1}{2}''$.
Maximum port opening, top $1\frac{1}{2}''$.
Maximum port opening, bottom $2\frac{3}{4}''$.
Cut-off top, 75.8 per cent. $=22\frac{3}{4}''$.
Cut-off bottom, 77.9 per cent. $=23\frac{3}{8}''$.
Stroke of piston $=30''$.
Eccentricity $=2\frac{1}{2}''$.
Length of stiff eccentric rod, $23.13''$.
Length of prolongation of eccentric rod, $16.03''$.

Draw the horizontal line XX_1, and the vertical line YY_1, intersecting the horizontal line XX_1 in O.

Lay off a distance OC such that $OC=\sqrt{L^2-R^2}$, where L is the length of the stiff eccentric rod. OC in this case is given, namely, $23''$, therefore, $L=\sqrt{OC^2+R^2}=23.13''$, and R is the eccentricity. From C lay-off a distance CD, and draw the vertical line UU_1.

With O as center and eccentricity as radius $2\frac{1}{2}''$ in this diagram, describe a circle, to any convenient scale. This diagram is drawn half size except where otherwise marked.

Digitized by Google

Now 5″ diameter circle drawn half size corresponds with 30″, the stroke of piston to a scale of 1″=1 foot. Therefore, with a scale of 1″=1 foot, set up on YY1, produced, the stroke of engine as shown, and with a radius equal to the length of connecting rod between centers, in this case 5′−7½″, describe arcs cutting the circle in points 2, 4, 6, 8.....30, etc., as shown. Now with C as center, and radius of length of radius rod, describe the arc A, B, in this case 12½″. With A and B as centers and the radius of 12½″ describe arcs E and F. With O1, 2, 4, 6, 8, etc., as centers, and L as radius describe arcs on arc E, for one complete revolution in a head gear repeating the same process on arc F for astern gear. Now the distance CD is equal to the length of the prolongation of the stiff eccentric rod, "M." Therefore, from the points 0, 2, 4, 6, 8, etc., draw lines passing through the intersection of the arcs, on arc E and F as previously described. Measuring off from the points of intersection along the lines representing M, we get a series of points through which a fair curve is drawn, this elongated figure represents the oscillations of the point D, or the point of attachment of the valve-rod. The writer uses a beam compass with an extra attachment, placing needle point on points 0, 2, 4, 6, 8, etc., and the middle leg of compass on C, the other leg taken equal to the length of M; hence when arc is described on arc E, a corresponding arc is described at its proper distance, hence passing a line through the latter arc, a point is obtained; numbering these points as shown prevents confusion to one not accustomed to laying down the diagram, and until one is thoroughly acquainted with construction, it will pay to mark them; proceeding thus for one complete revolution we obtain points through which a fair curve is passed, giving us the elongated figure as shown.

Only the ahead motion has been considered. The astern motion is treated in precisely the same manner. If the student has not a beam compass handy, then a straight edge can be used, made as follows: Measure off the length L, and scrive marks upon the straight edge corresponding to the length O1 C=L. Scrive a distance corresponding to CD1 =M, therefore, the points of intersection can be accurately located. To the left of the diagram is drawn the stroke of piston to a scale of 1″=1 foot. This is divided into 15 equal parts representing 2 inch intervals of same.

The lap is laid off $1\frac{5}{16}$″ for top, 1¼″ for bottom.

With a pair of dividers the points for 2, 4, 6, 8, etc., of the elongated figure is laid off on the respective piston position. Connecting these points we obtain the figure as shown. Measuring the port opening for top we find 1½″ as required, for bottom we find 2¾″ as required. On

Digitized by Google

the diagram we lay off as shown, the lead, lap, and port opening. Observe that the point D_1 intersects the lead line for both top and bottom; this is as it should be, for when the crank is on top or bottom center the valve has opened for lead.

This engine is worked from the starboard side. If worked from the port side, the ahead position would be reversed, that is to say, ahead would be to the right and astern to the left of center line.

The eccentric coincides in this gear with the crank. The stiff eccentric-rod L is jointed at C to the radius rod AC, which swings on A. The gudgeon is attached to the radius arm, shown on plate 5, which is movable on fixed centers.

The prolongation M of the eccentric-rod L may form a slight angle with L if desirable. Conditions of design, however, control this.

It can be readily observed from diagram that the amount of lead is proportionate to the length M, and hence the term lead arm is frequently applied. The valve rod is joined at D_1 and the distance traversed represents the oscillations of the valve. The angle at which the radius-arm deviates on either side from the vertical through the fixed center is termed the deviation angle.

The crank-shaft revolves in the same direction in which the radius-arm deviates from the vertical.

As the center C travels through an arc described by the radius-rod AC the oscillations are greater above than below the center line, as will be noted. This difference between upper and lower oscillations has the following advantages:

The valve-openings are less for down stroke.
The cut-off is earlier.
The compression is earlier.
For the up stroke, the cut-off is later.
The valve-opening is greater.
The compression is later.
The momentum of the moving parts are, therefore, better balanced.

The difference between oscillations is effected by the length of radius-rod, and radius-arm.

The diagram has been marked to make its construction as clear as possible.

Digitized by Google







The set of diagrams shown above is from a triple expansion engine fitted with Marshall Valve Gear. These diagrams are fair types of those obtained with this gear, and same should be closely studied and compared with the other diagrams shown, as all other diagrams were taken from engines fitted with link-motion.

The publishing of peculiarly formed diagrams, showing variou contours, has been purposely avoided, as it would be impossible to

Digitized by Google

show the very many forms of diagrams, and as it is only by a thorough grasp of the principles fundamental combined with practice that one can ever become proficient in analysis, it has been the author's aim to present these.

Plate 6 shows a section through the cylinders and valve chest of a triple expansion engine, and shows clearly the passages through which the steam travels from throttle valve to condenser. The H. P. and M. P. take steam on inside of valve and the L. P. on outside of valve. The receivers are cast with cylinders and are shown dotted. In this engine the H. P. crank leads.

It may be well to say in conclusion: Let the student take diagrams from either a compound or triple expansion engine with first H. P. crank leading, then if possible, diagrams from same type of engine with L. P. crank leading. Combine the diagrams, and note the difference under the various conditions. This way and this alone can he properly analyze.

If by writing this work I have been of help to those who are seeking this knowledge and who are willing to work hard for a clear understanding of this most interesting and vital subject, I shall feel amply repaid.

Digitized by Google

TABLE OF $\frac{1+\text{Hyp log } r}{r}$

Let r = Rate of expansion.

$\frac{1}{r}$ = Cut-off.

r	$\frac{1}{r}$	$\frac{1+\text{Hyp log } r}{r}$	r	$\frac{1}{r}$	$\frac{1+\text{Hyp log } r}{r}$
1.33	0.752	0.9657	8.0	0.125	0.3849
1.4	0.714	0.9546	8.25	0.121	0.377
1.5	0.667	0.937	8.5	0.118	0.3694
1.6	0.625	0.9188	8.75	0.114	0.3622
1.7	0.588	0.9003	9.00	0.111	0.3552
1.75	0.571	0.8911	9.25	0.108	0.3486
1.8	0.556	0.882	9.5	0.105	0.3422
1.9	0.526	0.8641	9.75	0.103	0.3361
2.0	0.500	0.8465	10.00	0.100	0.3302
2.1	0.476	0.8294	10.25	0.097	0.3246
2.2	0.455	0.8129	10.50	0.095	0.3191
2.25	0.444	0.8048	10.75	0.093	0.315
2.75	0.364	0.7315	11.00	0.091	0.3088
3.00	0.333	0.6995	11.25	0.089	0.304
3.25	0.308	0.6703	11.50	0.087	0.2994
3.75	0.267	0.6191	11.75	0.0851	0.2947
4.0	0.25	0.5965	12.00	0.0833	0.2904
4.25	0.235	0.5757	12.25	0.0816	0.2861
4.5	0.222	0.5564	12.5	0.08	0.2821
5.0	0.200	0.5219	12.75	0.0784	0.2781
5.25	0.190	0.5063	13.	0.0769	0.2741
5.5	0.182	0.4917	13.25	0.0755	0.2705
5.75	0.174	0.4781	13.5	0.0741	0.2668
6.	0.167	0.4652	13.75	0.0727	0.2633
6.25	0.160	0.4532	14.	0.0714	0.2599
6.5	0.154	0.4418	15.	0.0667	0.2472
6.75	0.148	0.431	16.	0.0625	0.2358
7.0	0.143	0.4208	17.	0.0588	0.2255
7.25	0.138	0.4111	18.	0.055	0.2161
7.5	0.133	0.4019	20.	0.050	0.1998
7.75	0.129	0.3932			

Digitized by Google

Digitized by Google

TABLE

CONTAINING THE

COMMON LOGARITHMS OF NUMBERS

FROM 1 TO 10,000

To obtain the hyperbolic logarithm of a number
multiply the common logarithm of
the number by 2.302585

Digitized by Google

Digitized by Google

N.	0	1	2	3	4	5	6	7	8	9	D.
100	00 0000	00 0434	00 0868	00 1301	00 1734	00 2166	00 2598	00 3029	00 3461	00 3891	432
101	4321	4751	5181	5609	6038	6466	6894	7321	7748	8174	428
102	8600	9026	9451	9876	01 0300	01 0724	01 1147	01 1570	01 1993	01 2415	424
103	01 2837	01 3259	01 3680	01 4100	4521	4940	5360	5779	6197	6616	420
104	7033	7451	7868	8284	8700	9116	9532	9947	02 0361	02 0775	416
105	02 1189	02 1603	02 2016	02 2428	02 2841	02 3252	02 3664	02 4075	02 4486	02 4896	412
106	5306	5715	6125	6533	6942	7350	7757	8164	8571	8978	408
107	9384	9789	03 0195	03 0600	03 1004	03 1408	03 1812	03 2216	03 2619	03 3021	404
108	03 3424	03 3826	4227	4628	5029	5430	5830	6230	6629	7028	400
109	7426	7825	8223	8620	9017	9414	9811	04 0207	04 0602	04 0998	397
110	04 1393	04 1787	04 2182	04 2576	04 2969	04 3362	04 3755	04 4148	04 4540	04 4932	393
111	5323	5714	6105	6495	6885	7275	7664	8053	8442	8830	390
112	9218	9606	9993	05 0380	05 0766	05 1153	05 1538	05 1924	05 2309	05 2694	386
113	05 3078	05 3463	05 3846	4230	4613	4996	5378	5760	6142	6524	383
114	6905	7286	7666	8046	8426	8805	9185	9563	9942	06 0320	379
115	06 0698	06 1075	06 1452	06 1829	06 2206	06 2582	06 2958	06 3333	06 3709	06 4083	376
116	4458	4832	5206	5580	5953	6326	6699	7071	7443	7815	373
117	8186	8557	8928	9298	9668	07 0038	07 0407	07 0776	07 1145	07 1514	370
118	07 1882	07 2250	07 2617	07 2985	07 3352	3718	4085	4451	4816	5182	366
119	5547	5912	6276	6640	7004	7368	7731	8094	8457	8819	363
120	07 9181	07 9543	07 9904	08 0266	08 0626	08 0987	08 1347	08 1707	08 2067	08 2426	360
121	08 2785	08 3144	08 3503	3861	4219	4576	4934	5291	5647	6004	357
122	6360	6716	7071	7426	7781	8136	8490	8845	9198	9552	355
123	9905	09 0258	09 0611	09 0963	09 1315	09 1667	09 2018	09 2370	09 2721	09 3071	352
124	09 3422	3772	4122	4471	4820	5169	5518	5866	6215	6562	349
125	09 6910	09 7257	09 7604	09 7951	09 8298	09 8644	09 8990	09 9335	09 9681	10 0026	346
126	10 0371	10 0715	10 1059	10 1403	10 1747	10 2091	10 2434	10 2777	10 3119	3462	343
127	3804	4146	4487	4828	5169	5510	5851	6191	6531	6871	341
128	7210	7549	7888	8227	8565	8903	9241	9579	9916	11 0253	338
129	11 0590	11 0926	11 1263	11 1599	11 1934	11 2270	11 2605	11 2940	11 3275	3609	335
130	11 3943	11 4277	11 4611	11 4944	11 5278	11 5611	11 5943	11 6276	11 6608	11 6940	333
131	7271	7603	7934	8265	8595	8926	9256	9586	9915	12 0245	330
132	12 0574	12 0903	12 1231	12 1560	12 1888	12 2216	12 2544	12 2871	12 3198	3525	328
133	3852	4178	4504	4830	5156	5481	5806	6131	6456	6781	325
134	7105	7429	7753	8076	8399	8722	9045	9368	9690	13 0012	323
135	13 0334	13 0655	13 0977	13 1298	13 1619	13 1939	13 2260	13 2580	13 2900	13 3219	321
136	3539	3858	4177	4496	4814	5133	5451	5769	6086	6403	318
137	6721	7037	7354	7671	7987	8303	8618	8934	9249	9564	316
138	9879	14 0194	14 0508	14 0822	14 1136	14 1450	14 1763	14 2076	14 2389	14 2702	314
139	14 3015	3327	3639	3951	4263	4574	4885	5196	5507	5818	311
140	14 6128	14 6438	14 6748	14 7058	14 7367	14 7676	14 7985	14 8294	14 8603	14 8911	309
141	9219	9527	9835	15 0142	15 0449	15 0756	15 1063	15 1370	15 1676	15 1982	307
142	15 2288	15 2594	15 2900	3205	3510	3815	4120	4424	4728	5032	305
143	5336	5040	5943	6246	6549	6852	7154	7457	7759	8061	303
144	8362	8664	8965	9266	9567	9868	16 0168	16 0469	16 0769	16 1068	301
145	16 1368	16 1667	16 1967	16 2266	16 2564	16 2863	16 3161	16 3460	16 3758	16 4055	299
146	4353	4650	4947	5244	5541	5838	6134	6430	6726	7022	297
147	7317	7613	7908	8203	8497	8792	9086	9380	9674	9968	295
148	17 0262	17 0555	17 0848	17 1141	17 1434	17 1726	17 2019	17 2311	17 2603	17 2895	293
149	3186	3478	3769	4060	4351	4641	4932	5222	5512	5802	291
150	17 6091	17 6381	17 6670	17 6959	17 7248	17 7536	17 7825	17 8113	17 8401	17 8689	289
151	8977	9264	9552	9839	18 0126	18 0413	18 0699	18 0986	18 1272	18 1558	287
152	18 1844	18 2129	18 2415	18 2700	2985	3270	3555	3839	4123	4407	285
153	4691	4975	5259	5542	5825	6108	6391	6674	6956	7239	283
154	7521	7803	8084	8366	8647	8928	9209	9490	9771	19 0051	281
155	19 0332	19 0612	19 0892	19 1171	19 1451	19 1730	19 2010	19 2289	19 2567	19 2846	279
156	3125	3403	3681	3959	4237	4514	4792	5069	5346	5623	278
157	5900	6176	6453	6729	7005	7281	7556	7832	8107	8382	276
158	8657	8932	9206	9481	9755	20 0029	20 0303	20 0577	20 0850	20 1124	274
159	20 1397	20 1670	20 1943	20 2216	20 2488	2761	3033	3305	3577	3848	272
N.	0	1	2	3	4	5	6	7	8	9	D.

Digitized by Google

N.	0	1	2	3	4	5	6	7	8	9	D.
160	20 4120	20 4391	20 4663	20 4934	20 5204	20 5475	20 5746	20 6016	20 6286	20 6556	271
161	6826	7096	7365	7634	7904	8173	8441	8710	8979	9247	269
162	9515	9783	21 0051	21 0319	21 0586	21 0853	21 1121	21 1388	21 1654	21 1921	267
163	21 2188	21 2454	2720	2986	3252	3518	3783	4049	4314	4579	266
164	4844	5109	5373	5638	5902	6166	6430	6694	6957	7221	264
165	21 7484	21 7747	21 8010	21 8273	21 8536	21 8798	21 9060	21 9323	21 9585	21 9846	262
166	22 0108	22 0370	22 0631	22 0892	22 1153	22 1414	22 1675	22 1936	22 2196	22 2456	261
167	2716	2976	3236	3496	3755	4015	4274	4533	4792	5051	259
168	5309	5568	5826	6084	6342	6600	6858	7115	7372	7630	258
169	7887	8144	8400	8657	8913	9170	9426	9682	9938	23 0193	256
170	23 0449	23 0704	23 0960	23 1215	23 1470	23 1724	23 1979	23 2234	23 2488	23 2742	255
171	2996	3250	3504	3757	4011	4264	4517	4770	5023	5276	253
172	5528	5781	6033	6285	6537	6789	7041	7292	7544	7795	252
173	8046	8297	8548	8799	9049	9299	9550	9800	24 0050	24 0300	250
174	24 0549	24 0799	24 1048	24 1297	24 1546	24 1795	24 2044	24 2293	2541	2790	249
175	24 3038	24 3286	24 3534	24 3782	24 4030	24 4277	24 4525	24 4772	24 5019	24 5266	248
176	5513	5759	6006	6252	6499	6745	6991	7237	7482	7728	246
177	7973	8219	8464	8709	8954	9198	9443	9687	9932	25 0176	245
178	25 0420	25 0664	25 0908	25 1151	25 1395	25 1638	25 1881	25 2125	25 2368	2610	243
179	2853	3096	3338	3580	3822	4064	4306	4548	4790	5031	242
180	25 5273	25 5514	25 5755	25 5996	25 6237	25 6477	25 6718	25 6958	25 7198	25 7439	241
181	7679	7918	8158	8398	8637	8877	9116	9355	9594	9833	239
182	26 0071	26 0310	26 0548	26 0787	26 1025	26 1263	26 1501	26 1739	26 1976	26 2214	238
183	2451	2688	2925	3162	3399	3636	3873	4109	4346	4582	237
184	4818	5054	5290	5525	5761	5996	6232	6467	6702	6937	235
185	26 7172	26 7406	26 7641	26 7875	26 8110	26 8344	26 8578	26 8812	26 9046	26 9279	234
186	9513	9746	9980	27 0213	27 0446	27 0679	27 0912	27 1144	27 1377	27 1609	233
187	27 1842	27 2074	27 2306	2538	2770	3001	3233	3464	3696	3927	232
188	4158	4389	4620	4850	5081	5311	5542	5772	6002	6232	230
189	6462	6692	6921	7151	7380	7609	7838	8067	8296	8525	229
190	27 8754	27 8982	27 9211	27 9439	27 9667	27 9895	28 0123	28 0351	28 0578	28 0806	228
191	28 1033	28 1261	28 1488	28 1715	28 1942	28 2169	2396	2622	2849	3075	227
192	3301	3527	3753	3979	4205	4431	4656	4882	5107	5332	226
193	5557	5782	6007	6232	6456	6681	6905	7130	7354	7578	225
194	7802	8026	8249	8473	8696	8920	9143	9366	9589	9812	223
195	29 0035	29 0257	29 0480	29 0702	29 0925	29 1147	29 1369	29 1591	29 1813	29 2034	222
196	2256	2478	2699	2920	3141	3363	3584	3804	4025	4246	221
197	4466	4687	4907	5127	5347	5567	5787	6007	6226	6446	220
198	6665	6884	7104	7323	7542	7761	7979	8198	8416	8635	219
199	8853	9071	9289	9507	9725	9943	30 0161	30 0378	30 0595	30 0813	218
200	30 1030	30 1247	30 1464	30 1681	30 1898	30 2114	30 2331	30 2547	30 2764	30 2980	217
201	3196	3412	3628	3844	4059	4275	4491	4706	4921	5136	216
202	5351	5566	5781	5996	6211	6425	6639	6854	7068	7282	215
203	7496	7710	7924	8137	8351	8564	8778	8991	9204	9417	213
204	9630	9843	31 0056	31 0268	31 0481	31 0693	31 0906	31 1118	31 1330	31 1542	212
205	31 1754	31 1966	31 2177	31 2389	31 2600	31 2812	31 3023	31 3234	31 3445	31 3656	211
206	3867	4078	4289	4499	4710	4920	5130	5340	5551	5760	210
207	5970	6180	6390	6599	6809	7018	7227	7436	7646	7854	209
208	8063	8272	8481	8689	8898	9106	9314	9522	9730	9938	208
209	32 0146	32 0354	32 0562	32 0769	32 0977	32 1184	32 1391	32 1598	32 1805	32 2012	207
210	32 2219	32 2426	32 2633	32 2839	32 3046	32 3252	32 3458	32 3665	32 3871	32 4077	206
211	4282	4488	4694	4899	5105	5310	5516	5721	5926	6131	205
212	6336	6541	6745	6950	7155	7359	7563	7767	7972	8176	204
213	8380	8583	8787	8991	9194	9398	9601	9805	33 0008	33 0211	203
214	33 0414	33 0617	33 0819	33 1022	33 1225	33 1427	33 1630	33 1832	2034	2236	202
215	33 2438	33 2640	33 2842	33 3044	33 3246	33 3447	33 3649	33 3850	33 4051	33 4253	202
216	4454	4655	4856	5057	5257	5458	5658	5859	6059	6260	201
217	6460	6660	6860	7060	7260	7459	7659	7858	8058	8257	200
218	8456	8656	8855	9054	9253	9451	9650	9849	34 0047	34 0246	199
219	34 0444	34 0642	34 0841	34 1039	34 1237	34 1435	34 1632	34 1830	2028	2225	198
N.	0	1	2	3	4	5	6	7	8	9	D.

Digitized by Google

N.	0	1	2	3	4	5	6	7	8	9	D.
220	34 2423	34 2620	34 2817	34 3014	34 3212	34 3409	34 3606	34 3802	34 3999	34 4196	197
221	4392	4589	4785	4981	5178	5374	5570	5766	5962	6157	196
222	6353	6549	6744	6939	7135	7330	7525	7720	7915	8110	195
223	8305	8500	8694	8889	9083	9278	9472	9666	9860	35 0054	194
224	35 0248	35 0442	35 0636	35 0829	35 1023	35 1216	35 1410	35 1603	35 1796	1989	193
225	35 2183	35 2375	35 2568	35 2761	35 2954	35 3147	35 3339	35 3532	35 3724	35 3916	193
226	4108	4301	4493	4685	4876	5068	5260	5452	5643	5834	192
227	6026	6217	6408	6599	6790	6981	7172	7363	7554	7744	191
228	7935	8125	8316	8506	8696	8886	9076	9266	9456	9646	190
229	9835	36 0025	36 0215	36 0404	36 0593	36 0783	36 0972	36 1161	36 1350	36 1539	189
230	36 1728	36 1917	36 2105	36 2294	36 2482	36 2671	36 2859	36 3048	36 3236	36 3424	188
231	3612	3800	3988	4176	4363	4551	4739	4926	5113	5301	188
232	5488	5675	5862	6049	6236	6423	6610	6796	6983	7169	187
233	7356	7542	7729	7915	8101	8287	8473	8659	8845	9030	186
234	9216	9401	9587	9772	9958	37 0143	37 0328	37 0513	37 0698	37 0883	185
235	37 1068	37 1253	37 1437	37 1622	37 1806	37 1991	37 2175	37 2360	37 2544	37 2728	184
236	2912	3096	3280	3464	3647	3831	4015	4198	4382	4565	184
237	4748	4932	5115	5298	5481	5664	5846	6029	6212	6394	183
238	6577	6759	6942	7124	7306	7488	7670	7852	8034	8216	182
239	8398	8580	8761	8943	9124	9306	9487	9668	9849	38 0030	181
240	38 0211	38 0392	38 0573	38 0754	38 0934	38 1115	38 1296	38 1476	38 1656	38 1837	181
241	2017	2197	2377	2557	2737	2917	3097	3277	3456	3636	180
242	3815	3995	4174	4353	4533	4712	4891	5070	5249	5428	179
243	5606	5785	5964	6142	6321	6499	6677	6856	7034	7212	178
244	7390	7568	7746	7923	8101	8279	8456	8634	8811	8989	178
245	38 9166	38 9343	38 9520	38 9698	38 9875	39 0051	39 0228	39 0405	39 0582	39 0759	177
246	39 0935	39 1112	39 1288	39 1464	39 1641	1817	1993	2169	2345	2521	176
247	2697	2873	3048	3224	3400	3575	3751	3926	4101	4277	176
248	4452	4627	4802	4977	5152	5326	5501	5676	5850	6025	175
249	6199	6374	6548	6722	6896	7071	7245	7419	7592	7766	174
250	39 7940	39 8114	39 8287	39 8461	39 8634	39 8808	39 8981	39 9154	39 9328	39 9501	173
251	9674	9847	40 0020	40 0192	40 0365	40 0538	40 0711	40 0883	40 1056	40 1228	173
252	40 1401	40 1573	1745	1917	2089	2261	2433	2605	2777	2949	172
253	3121	3292	3464	3635	3807	3978	4149	4320	4492	4663	171
254	4834	5005	5176	5346	5517	5688	5858	6029	6199	6370	171
255	40 6540	40 6710	40 6881	40 7051	40 7221	40 7391	40 7561	40 7731	40 7901	40 8070	170
256	8240	8410	8579	8749	8918	9087	9257	9426	9595	9764	169
257	9933	41 0102	41 0271	41 0440	41 0609	41 0777	41 0946	41 1114	41 1283	41 1451	169
258	41 1620	1788	1956	2124	2293	2461	2629	2796	2964	3132	168
259	3300	3467	3635	3803	3970	4137	4305	4472	4639	4806	167
260	41 4973	41 5140	41 5307	41 5474	41 5641	41 5808	41 5974	41 6141	41 6308	41 6474	167
261	6641	6807	6973	7139	7306	7472	7638	7804	7970	8135	166
262	8301	8467	8633	8798	8964	9129	9295	9460	9625	9791	165
263	9956	42 0121	42 0286	42 0451	42 0616	42 0781	42 0945	42 1110	42 1275	42 1439	165
264	42 1604	1768	1933	2097	2261	2426	2590	2754	2918	3082	164
265	42 3246	42 3410	42 3574	42 3737	42 3901	42 4065	42 4228	42 4392	42 4555	42 4718	164
266	4882	5045	5208	5371	5534	5697	5860	6023	6186	6349	163
267	6511	6674	6836	6999	7161	7324	7486	7648	7811	7973	162
268	8135	8297	8459	8621	8783	8944	9106	9268	9429	9591	162
269	9752	9914	43 0075	43 0236	43 0398	43 0559	43 0720	43 0881	43 1042	43 1203	161
270	43 1364	43 1525	43 1685	43 1846	43 2007	43 2167	43 2328	43 2488	43 2649	43 2809	161
271	2969	3130	3290	3450	3610	3770	3930	4090	4249	4409	160
272	4569	4729	4888	5048	5207	5367	5526	5685	5844	6004	159
273	6163	6322	6481	6640	6799	6957	7116	7275	7433	7592	159
274	7751	7909	8067	8226	8384	8542	8701	8859	9017	9175	158
275	43 9333	43 9491	43 9648	43 9806	43 9964	44 0122	44 0279	44 0437	44 0594	44 0752	158
276	44 0909	44 1066	44 1224	44 1381	44 1538	1695	1852	2009	2166	2323	157
277	2480	2637	2793	2950	3106	3263	3419	3576	3732	3889	157
278	4045	4201	4357	4513	4669	4825	4981	5137	5293	5449	156
279	5604	5760	5915	6071	6226	6382	6537	6692	6848	7003	155
N.	0	1	2	3	4	5	6	7	8	9	D.

Digitized by Google

N.	0	1	2	3	4	5	6	7	8	9	D.
280	44 7158	44 7313	44 7468	44 7623	44 7778	44 7933	44 8088	44 8242	44 8397	44 8552	155
281	8706	8861	9015	9170	9324	9478	9633	9787	9941	45 0095	154
282	45 0249	45 0403	45 0557	45 0711	45 0865	45 1018	45 1172	45 1326	45 1479	1633	154
283	1786	1940	2093	2247	2400	2553	2706	2859	3012	3165	153
284	3318	3471	3624	3777	3930	4082	4235	4387	4540	4692	153
285	45 4845	45 4997	45 5150	45 5302	45 5454	45 5606	45 5758	45 5910	45 6062	45 6214	152
286	6366	6518	6670	6821	6973	7125	7276	7428	7579	7731	152
287	7882	8033	8184	8336	8487	8638	8789	8940	9091	9242	151
288	9392	9543	9694	9845	9995	4601	46 0296	46 0447	46 0597	46 0748	151
289	46 0898	46 1048	46 1198	46 1348	46 1499	1649	1799	1948	2098	2248	150
290	46 2398	46 2548	46 2697	46 2847	46 2997	46 3146	46 3296	46 3445	46 3594	46 3744	150
291	3893	4042	4191	4340	4490	4639	4788	4936	5085	5234	149
292	5383	5532	5680	5829	5977	6126	6274	6423	6571	6719	149
293	6868	7016	7164	7312	7460	7608	7756	7904	8052	8200	148
294	8347	8495	8643	8790	8938	9085	9233	9380	9527	9675	148
295	46 9822	46 9969	47 0116	47 0263	47 0410	47 0557	47 0704	47 0851	47 0998	47 1145	147
296	47 1292	47 1438	1585	1732	1878	2025	2171	2318	2464	2610	146
297	2756	2903	3049	3195	3341	3487	3633	3779	3925	4071	146
298	4216	4362	4508	4653	4799	4944	5090	5235	5381	5526	146
299	5671	5816	5962	6107	6252	6397	6542	6687	6832	6976	145
300	47 7121	47 7266	47 7411	47 7555	47 7700	47 7844	47 7989	47 8133	47 8278	47 8422	145
301	8566	8711	8855	8999	9143	9287	9431	9575	9719	9863	144
302	48 0007	48 0151	48 0294	48 0438	48 0582	48 0725	48 0869	48 1012	48 1156	48 1299	144
303	1443	1586	1729	1872	2016	2159	2302	2445	2588	2731	143
304	2874	3016	3159	3302	3445	3587	3730	3872	4015	4157	143
305	48 4300	48 4442	48 4585	48 4727	48 4869	48 5011	48 5153	48 5295	48 5437	48 5579	142
306	5721	5863	6005	6147	6289	6430	6572	6714	6855	6997	142
307	7138	7280	7421	7563	7704	7845	7986	8127	8269	8410	141
308	8551	8692	8833	8974	9114	9255	9396	9537	9677	9818	141
309	9958	49 0099	49 0239	49 0380	49 0520	49 0661	49 0801	49 0941	49 1081	49 1222	140
310	49 1362	49 1502	49 1642	49 1782	49 1922	49 2062	49 2201	49 2341	49 2481	49 2621	140
311	2760	2900	3040	3179	3319	3458	3597	3737	3876	4015	139
312	4155	4294	4433	4572	4711	4850	4989	5128	5267	5406	139
313	5544	5683	5822	5960	6099	6238	6376	6515	6653	6791	139
314	6930	7068	7206	7344	7483	7621	7759	7897	8035	8173	138
315	49 8311	49 8448	49 8586	49 8724	49 8862	49 8999	49 9137	49 9275	49 9412	49 9550	138
316	9687	9824	9962	50 0099	50 0236	50 0374	50 0511	50 0648	50 0785	50 0922	137
317	50 1059	50 1196	50 1333	1470	1607	1744	1880	2017	2154	2291	137
318	2427	2564	2700	2837	2973	3109	3246	3382	3518	3655	136
319	3791	3927	4063	4199	4335	4471	4607	4743	4878	5014	136
320	50 5150	50 5286	50 5421	50 5557	50 5693	50 5828	50 5964	50 6099	50 6234	50 6370	136
321	6505	6640	6776	6911	7046	7181	7316	7451	7586	7721	135
322	7856	7991	8126	8260	8395	8530	8664	8799	8934	9068	135
323	9203	9337	9471	9606	9740	9874	51 0009	51 0143	51 0277	51 0411	134
324	51 0545	51 0679	51 0813	51 0947	51 1081	51 1215	1349	1482	1616	1750	134
325	51 1883	51 2017	51 2151	51 2284	51 2418	51 2551	51 2684	51 2818	51 2951	51 3084	133
326	3218	3351	3484	3617	3750	3883	4016	4149	4282	4415	133
327	4548	4681	4813	4946	5079	5211	5344	5476	5609	5741	133
328	5874	6006	6139	6271	6403	6535	6668	6800	6932	7064	132
329	7196	7328	7460	7592	7724	7855	7987	8119	8251	8382	132
330	51 8514	51 8646	51 8777	51 8909	51 9040	51 9171	51 9303	51 9434	51 9566	51 9697	131
331	9828	9959	52 0090	52 0221	52 0353	52 0484	52 0615	52 0745	52 0876	52 1007	131
332	52 1138	52 1269	1400	1530	1661	1792	1922	2053	2183	2314	131
333	2444	2575	2705	2835	2966	3096	3226	3356	3486	3616	130
334	3746	3876	4006	4136	4266	4396	4526	4656	4785	4915	130
335	52 5045	52 5174	52 5304	52 5434	52 5563	52 5693	52 5822	52 5951	52 6081	52 6210	129
336	6339	6469	6598	6727	6856	6985	7114	7243	7372	7501	129
337	7630	7759	7888	8016	8145	8274	8402	8531	8660	8788	129
338	8917	9045	9174	9302	9430	9559	9687	9815	9943	53 0072	128
339	53 0200	53 0328	53 0456	53 0584	53 0712	53 0840	53 0968	53 1096	53 1223	1351	128
N.	0	1	2	3	4	5	6	7	8	9	D.

Digitized by Google

N.	0	1	2	3	4	5	6	7	8	9	D.
340	53 1479	53 1607	53 1734	53 1862	53 1990	53 2117	53 2245	53 2372	53 2500	53 2627	128
341	2754	2882	3009	3136	3264	3391	3518	3645	3772	3899	127
342	4026	4153	4280	4407	4534	4661	4787	4914	5041	5167	127
343	5294	5421	5547	5674	5800	5927	6053	6180	6306	6432	126
344	6558	6685	6811	6937	7063	7189	7315	7441	7567	7693	126
345	53 7819	53 7945	53 8071	53 8197	53 8322	53 8448	53 8574	53 8699	53 8825	53 8951	126
346	9076	9202	9327	9452	9578	9703	9829	9954	54 0079	54 0204	125
347	54 0329	54 0455	54 0580	54 0705	54 0830	54 0955	54 1080	54 1205	1330	1454	125
348	1579	1704	1829	1953	2078	2203	2327	2452	2576	2701	125
349	2825	2950	3074	3199	3323	3447	3571	3696	3820	3944	124
350	54 4068	54 4192	54 4316	54 4440	54 4564	54 4688	54 4812	54 4936	54 5060	54 5183	124
351	5307	5431	5555	5678	5802	5925	6049	6172	6296	6419	124
352	6543	6666	6789	6913	7036	7159	7282	7405	7529	7652	123
353	7775	7898	8021	8144	8267	8389	8512	8635	8758	8881	123
354	9003	9126	9249	9371	9494	9616	9739	9861	9984	55 0106	123
355	55 0228	55 0351	55 0473	55 0595	55 0717	55 0840	55 0962	55 1084	55 1206	55 1328	122
356	1450	1572	1694	1816	1938	2060	2181	2303	2425	2547	122
357	2668	2790	2911	3033	3155	3276	3398	3519	3640	3762	121
358	3883	4004	4126	4247	4368	4489	4610	4731	4852	4973	121
359	5094	5215	5336	5457	5578	5699	5820	5940	6061	6182	121
360	55 6303	55 6423	55 6544	55 6664	55 6785	55 6905	55 7026	55 7146	55 7267	55 7387	120
361	7507	7627	7748	7868	7988	8108	8228	8349	8469	8589	120
362	8709	8829	8948	9068	9188	9308	9428	9548	9667	9787	120
363	9907	56 0026	56 0146	56 0265	56 0385	56 0504	56 0624	56 0743	56 0863	56 0982	119
364	56 1101	1221	1340	1459	1578	1698	1817	1936	2055	2174	119
365	56 2293	56 2412	56 2531	56 2650	56 2769	56 2887	56 3006	56 3125	56 3244	56 3362	119
366	3481	3600	3718	3837	3955	4074	4192	4311	4429	4548	119
367	4666	4784	4903	5021	5139	5257	5376	5494	5612	5730	118
368	5848	5966	6084	6202	6320	6437	6555	6673	6791	6909	118
369	7026	7144	7262	7379	7497	7614	7732	7849	7967	8084	118
370	56 8202	56 8319	56 8436	56 8554	56 8671	56 8788	56 8905	56 9023	56 9140	56 9257	117
371	9374	9491	9608	9725	9842	9959	57 0076	57 0193	57 0309	57 0426	117
372	57 0543	57 0660	57 0776	57 0893	57 1010	57 1126	1243	1359	1476	1592	117
373	1709	1825	1942	2058	2174	2291	2407	2523	2639	2755	116
374	2872	2988	3104	3220	3336	3452	3568	3684	3800	3915	116
375	57 4031	57 4147	57 4263	57 4379	57 4494	57 4610	57 4726	57 4841	57 4957	57 5072	116
376	5188	5303	5419	5534	5650	5765	5880	5996	6111	6226	115
377	6341	6457	6572	6687	6802	6917	7032	7147	7262	7377	115
378	7492	7607	7722	7836	7951	8066	8181	8295	8410	8525	115
379	8639	8754	8868	8983	9097	9212	9326	9441	9555	9669	114
380	57 9784	57 9898	58 0012	58 0126	58 0241	58 0355	58 0469	58 0583	58 0697	58 0811	114
381	58 0925	58 1039	1153	1267	1381	1495	1608	1722	1836	1950	114
382	2063	2177	2291	2404	2518	2631	2745	2858	2972	3085	114
383	3199	3312	3426	3539	3652	3765	3879	3992	4105	4218	113
384	4331	4444	4557	4670	4783	4896	5009	5122	5235	5348	113
385	58 5461	58 5574	58 5686	58 5799	58 5912	58 6024	58 6137	58 6250	58 6362	58 6475	113
386	6587	6700	6812	6925	7037	7149	7262	7374	7486	7599	112
387	7711	7823	7935	8047	8160	8272	8384	8496	8608	8720	112
388	8832	8944	9056	9167	9279	9391	9503	9615	9726	9838	112
389	9950	59 0061	59 0173	59 0284	59 0396	59 0507	59 0619	59 0730	59 0842	59 0953	112
390	59 1065	59 1176	59 1287	59 1399	59 1510	59 1621	59 1732	59 1843	59 1955	59 2066	111
391	2177	2288	2399	2510	2621	2732	2843	2954	3064	3175	111
392	3286	3397	3508	3618	3729	3840	3950	4061	4171	4282	111
393	4393	4503	4614	4724	4834	4945	5055	5165	5276	5386	110
394	5496	5606	5717	5827	5937	6047	6157	6267	6377	6487	110
395	59 6597	59 6707	59 6817	59 6927	59 7037	59 7146	59 7256	59 7366	59 7476	59 7586	110
396	7695	7805	7914	8024	8134	8243	8353	8462	8572	8681	110
397	8791	8900	9009	9119	9228	9337	9446	9556	9665	9774	109
398	9883	9992	60 0101	60 0210	60 0319	60 0428	60 0537	60 0646	60 0755	60 0864	109
399	60 0973	60 1082	1191	1299	1408	1517	1625	1734	1843	1951	109
N.	0	1	2	3	4	5	6	7	8	9	D.

Digitized by Google

N.	0	1	2	3	4	5	6	7	8	9	D.
400	60 2060	60 2169	60 2277	60 2386	60 2494	60 2603	60 2711	60 2819	60 2928	60 3036	108
401	3144	3253	3361	3469	3577	3686	3794	3902	4010	4118	108
402	4226	4334	4442	4550	4658	4766	4874	4982	5089	5197	108
403	5305	5413	5521	5628	5736	5844	5951	6059	6166	6274	108
404	6381	6489	6596	6704	6811	6919	7026	7133	7241	7348	107
405	60 7455	60 7562	60 7669	60 7777	60 7884	60 7991	60 8098	60 8205	60 8312	60 8419	107
406	8526	8633	8740	8847	8954	9061	9167	9274	9381	9488	107
407	9594	9701	9808	9914	61 0021	61 0128	61 0234	61 0341	61 0447	61 0554	107
408	61 0660	61 0767	61 0873	61 0979	1086	1192	1298	1405	1511	1617	106
409	1723	1829	1936	2042	2148	2254	2360	2466	2572	2678	106
410	61 2784	61 2890	61 2996	61 3102	61 3207	61 3313	61 3419	61 3525	61 3630	61 3736	106
411	3842	3947	4053	4159	4264	4370	4475	4581	4686	4792	106
412	4897	5003	5108	5213	5319	5424	5529	5634	5740	5845	105
413	5950	6055	6160	6265	6370	6476	6581	6686	6790	6895	105
414	7000	7105	7210	7315	7420	7525	7629	7734	7839	7943	105
415	61 8048	61 8153	61 8257	61 8362	61 8466	61 8571	61 8676	61 8780	61 8884	61 8989	105
416	9093	9198	9302	9406	9511	9615	9719	9824	9928	62 0032	104
417	62 0136	62 0240	62 0344	62 0448	62 0552	62 0656	62 0760	62 0864	62 0968	1072	104
418	1176	1280	1384	1488	1592	1695	1799	1903	2007	2110	104
419	2214	2318	2421	2525	2628	2732	2835	2939	3042	3146	104
420	62 3249	62 3353	62 3456	62 3559	62 3663	62 3766	62 3869	62 3973	62 4076	62 4179	103
421	4282	4385	4488	4591	4695	4798	4901	5004	5107	5210	103
422	5312	5415	5518	5621	5724	5827	5929	6032	6135	6238	103
423	6340	6443	6546	6648	6751	6853	6956	7058	7161	7263	103
424	7366	7468	7571	7673	7775	7878	7980	8082	8185	8287	102
425	62 8389	62 8491	62 8593	62 8695	62 8797	62 8900	62 9002	62 9104	62 9206	62 9308	102
426	9410	9512	9613	9715	9817	9919	63 0021	63 0123	63 0224	63 0326	102
427	63 0428	63 0530	63 0631	63 0733	63 0835	63 0936	1038	1139	1241	1342	102
428	1444	1545	1647	1748	1849	1951	2052	2153	2255	2356	101
429	2457	2559	2660	2761	2862	2963	3064	3165	3266	3367	101
430	63 3468	63 3569	63 3670	63 3771	63 3872	63 3973	63 4074	63 4175	63 4276	63 4376	101
431	4477	4578	4679	4779	4880	4981	5081	5182	5283	5383	101
432	5484	5584	5685	5785	5886	5986	6087	6187	6287	6388	100
433	6488	6588	6688	6789	6889	6989	7089	7189	7290	7390	100
434	7490	7590	7690	7790	7890	7990	8090	8190	8290	8389	100
435	63 8489	63 8589	63 8689	63 8789	63 8888	63 8988	63 9088	63 9188	63 9287	63 9387	100
436	9486	9586	9686	9785	9885	9984	64 0084	64 0183	64 0283	64 0382	99
437	64 0481	64 0581	64 0680	64 0779	64 0879	64 0978	1077	1177	1276	1375	99
438	1474	1573	1672	1771	1871	1970	2069	2168	2267	2366	99
439	2465	2563	2662	2761	2860	2959	3058	3156	3255	3354	99
440	64 3453	64 3551	64 3650	64 3749	64 3847	64 3946	64 4044	64 4143	64 4242	64 4340	98
441	4439	4537	4636	4734	4832	4931	5029	5127	5226	5324	98
442	5422	5521	5619	5717	5815	5913	6011	6110	6208	6306	98
443	6404	6502	6600	6698	6796	6894	6992	7089	7187	7285	98
444	7383	7481	7579	7676	7774	7872	7969	8067	8165	8262	98
445	64 8360	64 8458	64 8555	64 8653	64 8750	64 8848	64 8945	64 9043	64 9140	64 9237	97
446	9335	9432	9530	9627	9724	9821	9919	65 0016	65 0113	65 0210	97
447	65 0308	65 0405	65 0502	65 0599	65 0696	65 0793	65 0890	0987	1084	1181	97
448	1278	1375	1472	1569	1666	1762	1859	1956	2053	2150	97
449	2246	2343	2440	2536	2633	2730	2826	2923	3019	3116	97
450	65 3213	65 3309	65 3405	65 3502	65 3598	65 3695	65 3791	65 3888	65 3984	65 4080	96
451	4177	4273	4369	4465	4562	4658	4754	4850	4946	5042	96
452	5138	5235	5331	5427	5523	5619	5715	5810	5906	6002	96
453	6098	6194	6290	6386	6482	6577	6673	6769	6864	6960	96
454	7056	7152	7247	7343	7438	7534	7629	7725	7820	7916	96
455	65 8011	65 8107	65 8202	65 8298	65 8393	65 8488	65 8584	65 8679	65 8774	65 8870	95
456	8965	9060	9155	9250	9346	9441	9536	9631	9726	9821	95
457	9916	66 0011	66 0106	66 0201	66 0296	66 0391	66 0486	66 0581	66 0676	66 0771	95
458	66 0865	0960	1055	1150	1245	1339	1434	1529	1623	1718	95
459	1813	1907	2002	2096	2191	2286	2380	2475	2569	2663	95
N.	0	1	2	3	4	5	6	7	8	9	D.

Digitized by Google

N.	0	1	2	3	4	5	6	7	8	9	D.
460	66 2758	66 2852	66 2947	66 3041	66 3135	66 3230	66 3324	66 3418	66 3512	66 3607	94
461	3701	3795	3889	3983	4078	4172	4266	4360	4454	4548	94
462	4642	4736	4830	4924	5018	5112	5206	5299	5393	5487	94
463	5581	5675	5769	5862	5956	6050	6143	6237	6331	6424	94
464	6518	6612	6705	6799	6892	6986	7079	7173	7266	7360	94
465	66 7453	66 7546	66 7640	66 7733	66 7826	66 7920	66 8013	66 8106	66 8199	66 8293	93
466	8386	8479	8572	8665	8759	8852	8945	9038	9131	9224	93
467	9317	9410	9503	9596	9689	9782	9875	9967	67 0060	67 0153	93
468	67 0246	67 0339	67 0431	67 0524	67 0617	67 0710	67 0802	67 0895	0988	1080	93
469	1173	1265	1358	1451	1543	1636	1728	1821	1913	2005	93
470	67 2098	67 2190	67 2283	67 2375	67 2467	67 2560	67 2652	67 2744	67 2836	67 2929	92
471	3021	3113	3205	3297	3390	3482	3574	3666	3758	3850	92
472	3942	4034	4126	4218	4310	4402	4494	4586	4677	4769	92
473	4861	4953	5045	5137	5228	5320	5412	5503	5595	5687	92
474	5778	5870	5962	6053	6145	6236	6328	6419	6511	6602	92
475	67 6694	67 6785	67 6876	67 6968	67 7059	67 7151	67 7242	67 7333	67 7424	67 7516	91
476	7607	7698	7789	7881	7972	8063	8154	8245	8336	8427	91
477	8518	8609	8700	8791	8882	8973	9064	9155	9246	9337	91
478	9428	9519	9610	9700	9791	9882	9973	68 0063	68 0154	68 0245	91
479	68 0336	68 0426	68 0517	68 0607	68 0698	68 0789	68 0879	0970	1060	1151	91
480	68 1241	68 1332	68 1422	68 1513	68 1603	68 1693	68 1784	68 1874	68 1964	68 2055	90
481	2145	2235	2326	2416	2506	2596	2686	2777	2867	2957	90
482	3047	3137	3227	3317	3407	3497	3587	3677	3767	3857	90
483	3947	4037	4127	4217	4307	4396	4486	4576	4666	4756	90
484	4845	4935	5025	5114	5204	5294	5383	5473	5563	5652	90
485	68 5742	68 5831	68 5921	68 6010	68 6100	68 6189	68 6279	68 6368	68 6458	68 6547	89
486	6636	6726	6815	6904	6994	7083	7172	7261	7351	7440	89
487	7529	7618	7707	7796	7886	7975	8064	8153	8242	8331	89
488	8420	8509	8598	8687	8776	8865	8953	9042	9131	9220	89
489	9309	9398	9486	9575	9664	9753	9841	9930	69 0019	69 0107	89
490	69 0196	69 0285	69 0373	69 0462	69 0550	69 0639	69 0728	69 0816	69 0905	69 0993	89
491	1081	1170	1258	1347	1435	1524	1612	1700	1789	1877	88
492	1965	2053	2142	2230	2318	2406	2494	2583	2671	2759	88
493	2847	2935	3023	3111	3199	3287	3375	3463	3551	3639	88
494	3727	3815	3903	3991	4078	4166	4254	4342	4430	4517	88
495	69 4605	69 4693	69 4781	69 4868	69 4956	69 5044	69 5131	69 5219	69 5307	69 5394	88
496	5482	5569	5657	5744	5832	5919	6007	6094	6182	6269	87
497	6356	6444	6531	6618	6706	6793	6880	6968	7055	7142	87
498	7229	7317	7404	7491	7578	7665	7752	7839	7926	8014	87
499	8101	8188	8275	8362	8449	8535	8622	8709	8796	8883	87
500	69 8970	69 9057	69 9144	69 9231	69 9317	69 9404	69 9491	69 9578	69 9664	69 9751	87
501	9838	9924	70 0011	70 0098	70 0184	70 0271	70 0358	70 0444	70 0531	70 0617	87
502	70 0704	70 0790	0877	0963	1050	1136	1222	1309	1395	1482	86
503	1568	1654	1741	1827	1913	1999	2086	2172	2258	2344	86
504	2431	2517	2603	2689	2775	2861	2947	3033	3119	3205	86
505	70 3291	70 3377	70 3463	70 3549	70 3635	70 3721	70 3807	70 3893	70 3979	70 4065	86
506	4151	4236	4322	4408	4494	4579	4665	4751	4837	4922	86
507	5008	5094	5179	5265	5350	5436	5522	5607	5693	5778	86
508	5864	5949	6035	6120	6206	6291	6376	6462	6547	6632	85
509	6718	6803	6888	6974	7059	7144	7229	7315	7400	7485	85
510	70 7570	70 7655	70 7740	70 7826	70 7911	70 7996	70 8081	70 8166	70 8251	70 8336	85
511	8421	8506	8591	8676	8761	8846	8931	9015	9100	9185	85
512	9270	9355	9440	9524	9609	9694	9779	9863	9948	71 0033	85
513	71 0117	71 0202	71 0287	71 0371	71 0456	71 0540	71 0625	71 0710	71 0794	0879	85
514	0763	1048	1323	1217	1301	1385	1470	1554	1639	1723	84
515	71 1807	71 1892	71 1976	71 2060	71 2144	71 2229	71 2313	71 2397	71 2481	71 2566	84
516	2650	2734	2818	2902	2986	3070	3154	3238	3323	3407	84
517	3491	3575	3659	3742	3826	3910	3994	4078	4162	4246	84
518	4330	4414	4497	4581	4665	4749	4833	4916	5000	5084	84
519	5167	5251	5335	5418	5502	5586	5669	5753	5836	5920	84
N.	0	1	2	3	4	5	6	7	8	9	D.

Digitized by Google

N.	0	1	2	3	4	5	6	7	8	9	D.
520	71 6003	71 6087	71 6170	71 6254	71 6337	71 6421	71 6504	71 6588	71 6671	71 6754	83
521	6838	6921	7004	7088	7171	7254	7338	7421	7504	7587	83
522	7671	7754	7837	7920	8003	8086	8169	8253	8336	8419	83
523	8502	8585	8668	8751	8834	8917	9000	9083	9165	9248	83
524	9331	9414	9497	9580	9663	9745	9828	9911	9994	72 0077	83
525	72 0159	72 0242	72 0325	72 0407	72 0490	72 0573	72 0655	72 0738	72 0821	72 0903	83
526	0986	1068	1151	1233	1316	1398	1481	1563	1646	1728	82
527	1811	1893	1975	2058	2140	2222	2305	2387	2469	2552	82
528	2634	2716	2798	2881	2963	3045	3127	3209	3291	3374	82
529	3456	3538	3620	3702	3784	3866	3948	4030	4112	4194	82
530	72 4276	72 4358	72 4440	72 4522	72 4604	72 4685	72 4767	72 4849	72 4931	72 5013	82
531	5095	5176	5258	5340	5422	5503	5585	5667	5748	5830	82
532	5912	5993	6075	6156	6238	6320	6401	6483	6564	6646	82
533	6727	6809	6890	6972	7053	7134	7216	7297	7379	7460	81
534	7541	7623	7704	7785	7866	7948	8029	8110	8191	8273	81
535	72 8354	72 8435	72 8516	72 8597	72 8678	72 8759	72 8841	72 8922	72 9003	72 9084	81
536	9165	9246	9327	9408	9489	9570	9651	9732	9813	9893	81
537	9974	73 0055	73 0136	73 0217	73 0298	73 0378	73 0459	73 0540	73 0621	73 0702	81
538	73 0782	0863	0944	1024	1105	1186	1266	1347	1428	1508	81
539	1589	1669	1750	1830	1911	1991	2072	2152	2233	2313	81
540	73 2394	73 2474	73 2555	73 2635	73 2715	73 2796	73 2876	73 2956	73 3037	73 3117	80
541	3197	3278	3358	3438	3518	3598	3679	3759	3839	3919	80
542	3999	4079	4160	4240	4320	4400	4480	4560	4640	4720	80
543	4800	4880	4960	5040	5120	5200	5279	5359	5439	5519	80
544	5599	5679	5759	5838	5918	5998	6078	6157	6237	6317	80
545	73 6397	73 6476	73 6556	73 6635	73 6715	73 6795	73 6874	73 6954	73 7034	73 7113	80
546	7193	7272	7352	7431	7511	7590	7670	7749	7829	7908	79
547	7987	8067	8146	8225	8305	8384	8463	8543	8622	8701	79
548	8781	8860	8939	9018	9097	9177	9256	9335	9414	9493	79
549	9572	9651	9731	9810	9889	9968	74 0047	74 0126	74 0205	74 0284	79
550	74 0363	74 0442	74 0521	74 0600	74 0678	74 0757	74 0836	74 0915	74 0994	74 1073	79
551	1152	1230	1309	1388	1467	1546	1624	1703	1782	1860	79
552	1939	2018	2096	2175	2254	2332	2411	2489	2568	2647	79
553	2725	2804	2882	2961	3039	3118	3196	3275	3353	3431	78
554	3510	3588	3667	3745	3823	3902	3980	4058	4136	4215	78
555	74 4293	74 4371	74 4449	74 4528	74 4606	74 4684	74 4762	74 4840	74 4919	74 4997	78
556	5075	5153	5231	5309	5387	5465	5543	5621	5699	5777	78
557	5855	5933	6011	6089	6167	6245	6323	6401	6479	6556	78
558	6634	6712	6790	6868	6945	7023	7101	7179	7256	7334	78
559	7412	7489	7567	7645	7722	7800	7878	7955	8033	8110	78
560	74 8188	74 8266	74 8343	74 8421	74 8498	74 8576	74 8653	74 8731	74 8808	74 8885	77
561	8963	9040	9118	9195	9272	9350	9427	9504	9582	9659	77
562	9736	9814	9891	9968	75 0045	75 0123	75 0200	75 0277	75 0354	75 0431	77
563	75 0508	75 0586	75 0663	75 0740	0817	0894	0971	1048	1125	1202	77
564	1279	1356	1433	1510	1587	1664	1741	1818	1895	1972	77
565	75 2048	75 2125	75 2202	75 2279	75 2356	75 2433	75 2509	75 2586	75 2663	75 2740	77
566	2816	2893	2970	3047	3123	3200	3277	3353	3430	3506	77
567	3583	3660	3736	3813	3889	3966	4042	4119	4195	4272	77
568	4348	4425	4501	4578	4654	4730	4807	4883	4960	5036	76
569	5112	5189	5265	5341	5417	5494	5570	5646	5722	5799	76
570	75 5875	75 5951	75 6027	75 6103	75 6180	75 6256	75 6332	75 6408	75 6484	75 6560	76
571	6636	6712	6788	6864	6940	7016	7092	7168	7244	7320	76
572	7396	7472	7548	7624	7700	7775	7851	7927	8003	8079	76
573	8155	8230	8306	8382	8458	8533	8609	8685	8761	8836	76
574	8912	8988	9063	9139	9214	9290	9366	9441	9517	9592	76
575	75 9668	75 9743	75 9819	75 9894	75 9970	76 0045	76 0121	76 0196	76 0272	76 0347	75
576	76 0422	76 0498	76 0573	76 0649	76 0724	0799	0875	0950	1025	1101	75
577	1176	1251	1326	1402	1477	1552	1627	1702	1778	1853	75
578	1928	2003	2078	2153	2228	2303	2378	2453	2529	2604	75
579	2679	2754	2829	2904	2978	3053	3128	3203	3278	3353	75
N.	0	1	2	3	4	5	6	7	8	9	D.

Digitized by Google

N.	0	1	2	3	4	5	6	7	8	9	D.
580	76 3428	76 3503	76 3578	76 3653	76 3727	76 3802	76 3877	76 3952	76 4027	76 4101	75
581	4176	4251	4326	4400	4475	4550	4624	4699	4774	4848	75
582	4923	4998	5072	5147	5221	5296	5370	5445	5520	5594	75
583	5669	5743	5818	5892	5966	6041	6115	6190	6264	6338	74
584	6413	6487	6562	6636	6710	6785	6859	6933	7007	7082	74
585	76 7156	76 7230	76 7304	76 7379	76 7453	76 7527	76 7601	76 7675	76 7749	76 7823	74
586	7898	7972	8046	8120	8194	8268	8342	8416	8490	8564	74
587	8638	8712	8786	8860	8934	9008	9082	9156	9230	9303	74
588	9377	9451	9525	9599	9673	9746	9820	9894	9968	77 0042	74
589	77 0115	77 0189	77 0263	77 0336	77 0410	77 0484	77 0557	77 0631	77 0705	0778	74
590	77 0852	77 0926	77 0999	77 1073	77 1146	77 1220	77 1293	77 1367	77 1440	77 1514	74
591	1587	1661	1734	1808	1881	1955	2028	2102	2175	2248	73
592	2322	2395	2468	2542	2615	2688	2762	2835	2908	2981	73
593	3055	3128	3201	3274	3348	3421	3494	3567	3640	3713	73
594	3786	3860	3933	4006	4079	4152	4225	4298	4371	4444	73
595	77 4517	77 4590	77 4663	77 4736	77 4809	77 4882	77 4955	77 5028	77 5100	77 5173	73
596	5246	5319	5392	5465	5538	5610	5683	5756	5829	5902	73
597	5974	6047	6120	6193	6265	6338	6411	6483	6556	6629	73
598	6701	6774	6846	6919	6992	7064	7137	7209	7282	7354	73
599	7427	7499	7572	7644	7717	7789	7862	7934	8006	8079	72
600	77 8151	77 8224	77 8296	77 8368	77 8441	77 8513	77 8585	77 8658	77 8730	77 8802	72
601	8874	8947	9019	9091	9163	9236	9308	9380	9452	9524	72
602	9596	9669	9741	9813	9885	9957	78 0029	78 0101	78 0173	78 0245	72
603	78 0317	78 0389	78 0461	78 0533	78 0605	78 0677	0749	0821	0893	0965	72
604	1037	1109	1181	1253	1324	1396	1468	1540	1612	1684	72
605	78 1755	78 1827	78 1899	78 1971	78 2042	78 2114	78 2186	78 2258	78 2329	78 2401	72
606	2473	2544	2616	2688	2759	2831	2902	2974	3046	3117	72
607	3189	3260	3332	3403	3475	3546	3618	3689	3761	3832	71
608	3904	3975	4046	4118	4189	4261	4332	4403	4475	4546	71
609	4617	4689	4760	4831	4902	4974	5045	5116	5187	5259	71
610	78 5330	78 5401	78 5472	78 5543	78 5615	78 5686	78 5757	78 5828	78 5899	78 5970	71
611	6041	6112	6183	6254	6325	6396	6467	6538	6609	6680	71
612	6751	6822	6893	6964	7035	7106	7177	7248	7319	7390	71
613	7460	7531	7602	7673	7744	7815	7885	7956	8027	8098	71
614	8168	8239	8310	8381	8451	8522	8593	8663	8734	8804	71
615	78 8875	78 8946	78 9016	78 9087	78 9157	78 9228	78 9299	78 9369	78 9440	78 9510	71
616	9581	9651	9722	9792	9863	9933	79 0004	79 0074	79 0144	79 0215	70
617	79 0285	79 0356	79 0426	79 0496	79 0567	79 0637	0707	0778	0848	0918	70
618	0988	1059	1129	1199	1269	1340	1410	1480	1550	1620	70
619	1691	1761	1831	1901	1971	2041	2111	2181	2252	2322	70
620	79 2392	79 2462	79 2532	79 2602	79 2672	79 2742	79 2812	79 2882	79 2952	79 3022	70
621	3092	3162	3231	3301	3371	3441	3511	3581	3651	3721	70
622	3790	3860	3930	4000	4070	4139	4209	4279	4349	4418	70
623	4488	4558	4627	4697	4767	4836	4906	4976	5045	5115	70
624	5185	5254	5324	5393	5463	5532	5602	5672	5741	5811	70
625	79 5880	79 5949	79 6019	79 6088	79 6158	79 6227	79 6297	79 6366	79 6436	79 6505	69
626	6574	6644	6713	6782	6852	6921	6990	7060	7129	7198	69
627	7268	7337	7406	7475	7545	7614	7683	7752	7821	7890	69
628	7960	8029	8098	8167	8236	8305	8374	8443	8513	8582	69
629	8651	8720	8789	8858	8927	8996	9065	9134	9203	9272	69
630	79 9341	79 9409	79 9478	79 9547	79 9616	79 9685	79 9754	79 9823	79 9892	79 9961	69
631	80 0029	80 0098	80 0167	80 0236	80 0305	80 0373	80 0442	80 0511	80 0580	80 0648	69
632	0717	0786	0854	0923	0992	1061	1129	1198	1266	1335	69
633	1404	1472	1541	1609	1678	1747	1815	1884	1952	2021	69
634	2089	2158	2226	2295	2363	2432	2500	2568	2637	2705	68
635	80 2774	80 2842	80 2910	80 2979	80 3047	80 3116	80 3184	80 3252	80 3321	80 3389	68
636	3457	3525	3594	3662	3730	3798	3867	3935	4003	4071	68
637	4139	4208	4276	4344	4412	4480	4548	4616	4685	4753	68
638	4821	4889	4957	5025	5093	5161	5229	5297	5365	5433	68
639	5501	5569	5637	5705	5773	5841	5908	5976	6044	6112	68
N.	0	1	2	3	4	5	6	7	8	9	D.

Digitized by Google

N.	0	1	2	3	4	5	6	7	8	9	D.
640	80 6180	80 6248	80 6316	80 6384	80 6451	80 6519	80 6587	80 6655	80 6723	80 6790	68
641	6858	6926	6994	7061	7129	7197	7264	7332	7400	7467	68
642	7535	7603	7670	7738	7806	7873	7941	8008	8076	8143	68
643	8211	8279	8346	8414	8481	8549	8616	8684	8751	8818	67
644	8886	8953	9021	9088	9156	9223	9290	9358	9425	9492	67
645	80 9560	80 9627	80 9694	80 9762	80 9829	80 9896	80 9964	81 0031	81 0098	81 0165	67
646	81 0233	81 0300	81 0367	81 0434	81 0501	81 0569	81 0636	0703	0770	0837	67
647	0904	0971	1039	1106	1173	1240	1307	1374	1441	1508	67
648	1575	1642	1709	1776	1843	1910	1977	2044	2111	2178	67
649	2245	2312	2379	2445	2512	2579	2646	2713	2780	2847	67
650	81 2913	81 2980	81 3047	81 3114	81 3181	81 3247	81 3314	81 3381	81 3448	81 3514	67
651	3581	3648	3714	3781	3848	3914	3981	4048	4114	4181	67
652	4248	4314	4381	4447	4514	4581	4647	4714	4780	4847	67
653	4913	4980	5046	5113	5179	5246	5312	5378	5445	5511	66
654	5578	5644	5711	5777	5843	5910	5976	6042	6109	6175	66
655	81 6241	81 6308	81 6374	81 6440	81 6506	81 6573	81 6639	81 6705	81 6771	81 6838	66
656	6904	6970	7036	7102	7169	7235	7301	7367	7433	7499	66
657	7565	7631	7698	7764	7830	7896	7962	8028	8094	8160	66
658	8226	8292	8358	8424	8490	8556	8622	8688	8754	8820	66
659	8885	8951	9017	9083	9149	9215	9281	9346	9412	9478	66
660	81 9544	81 9610	81 9676	81 9741	81 9807	81 9873	81 9939	82 0004	82 0070	82 0136	66
661	82 0201	82 0267	82 0333	82 0399	82 0464	82 0530	82 0595	0661	0727	0792	66
662	0858	0924	0989	1055	1120	1186	1251	1317	1382	1448	66
663	1514	1579	1645	1710	1775	1841	1906	1972	2037	2103	65
664	2168	2233	2299	2364	2430	2495	2560	2626	2691	2756	65
665	82 2822	82 2887	82 2952	82 3018	82 3083	82 3148	82 3213	82 3279	82 3344	82 3409	65
666	3474	3539	3605	3670	3735	3800	3865	3930	3996	4061	65
667	4126	4191	4256	4321	4386	4451	4516	4581	4646	4711	65
668	4776	4841	4906	4971	5036	5101	5166	5231	5296	5361	65
669	5426	5491	5556	5621	5686	5751	5815	5880	5945	6010	65
670	82 6075	82 6140	82 6204	82 6269	82 6334	82 6399	82 6464	82 6528	82 6593	82 6658	65
671	6723	6787	6852	6917	6981	7046	7111	7175	7240	7305	65
672	7369	7434	7499	7563	7628	7692	7757	7821	7886	7951	65
673	8015	8080	8144	8209	8273	8338	8402	8467	8531	8595	64
674	8660	8724	8789	8853	8918	8982	9046	9111	9175	9239	64
675	82 9304	82 9368	82 9432	82 9497	82 9561	82 9625	82 9690	82 9754	82 9818	82 9882	64
676	9947	83 0011	83 0075	83 0139	83 0204	83 0268	83 0332	83 0396	83 0460	83 0525	64
677	83 0589	0653	0717	0781	0845	0909	0973	1037	1102	1166	64
678	1230	1294	1358	1422	1486	1550	1614	1678	1742	1806	64
679	1870	1934	1998	2062	2126	2189	2253	2317	2381	2445	64
680	83 2509	83 2573	83 2637	83 2700	83 2764	83 2828	83 2892	83 2956	83 3020	83 3083	64
681	3147	3211	3275	3338	3402	3466	3530	3593	3657	3721	64
682	3784	3848	3912	3975	4039	4103	4166	4230	4294	4357	64
683	4421	4484	4548	4611	4675	4739	4802	4866	4929	4993	64
684	5056	5120	5183	5247	5310	5373	5437	5500	5564	5627	63
685	83 5691	83 5754	83 5817	83 5881	83 5944	83 6007	83 6071	83 6134	83 6197	83 6261	63
686	6324	6387	6451	6514	6577	6641	6704	6767	6830	6894	63
687	6957	7020	7083	7146	7210	7273	7336	7399	7462	7525	63
688	7588	7652	7715	7778	7841	7904	7967	8030	8093	8156	63
689	8219	8282	8345	8408	8471	8534	8597	8660	8723	8786	63
690	83 8849	83 8912	83 8975	83 9038	83 9101	83 9164	83 9227	83 9289	83 9352	83 9415	63
691	9478	9541	9604	9667	9729	9792	9855	9918	9981	84 0043	63
692	84 0106	84 0169	84 0232	84 0294	84 0357	84 0420	84 0482	84 0545	84 0608	0671	63
693	0733	0796	0859	0921	0984	1046	1109	1172	1234	1297	63
694	1359	1422	1485	1547	1610	1672	1735	1797	1860	1922	63
695	84 1985	84 2047	84 2110	84 2172	84 2235	84 2297	84 2360	84 2422	84 2484	84 2547	62
696	2609	2672	2734	2796	2859	2921	2983	3046	3108	3170	62
697	3233	3295	3357	3420	3482	3544	3606	3669	3731	3793	62
698	3855	3918	3980	4042	4104	4166	4229	4291	4353	4415	62
699	4477	4539	4601	4664	4726	4788	4850	4912	4974	5036	62
N.	0	1	2	3	4	5	6	7	8	9	D.

Digitized by Google

N.	0	1	2	3	4	5	6	7	8	9	D.
700	84 5098	84 5160	84 5222	84 5284	84 5346	84 5408	84 5470	84 5532	84 5594	84 5656	62
701	5718	5780	5842	5904	5966	6028	6090	6151	6213	6275	62
702	6337	6399	6461	6523	6585	6646	6708	6770	6832	6894	62
703	6955	7017	7079	7141	7202	7264	7326	7388	7449	7511	62
704	7573	7634	7696	7758	7819	7881	7943	8004	8066	8128	62
705	84 8189	84 8251	84 8312	84 8374	84 8435	84 8497	84 8559	84 8620	84 8682	84 8743	62
706	8805	8866	8928	8989	9051	9112	9174	9235	9297	9358	61
707	9419	9481	9542	9604	9665	9726	9788	9849	9911	9972	61
708	85 0033	85 0095	85 0156	85 0217	85 0279	85 0340	85 0401	85 0462	85 0524	85 0585	61
709	0646	0707	0769	0830	0891	0952	1014	1075	1136	1197	61
710	85 1258	85 1320	85 1381	85 1442	85 1503	85 1564	85 1625	85 1686	85 1747	85 1809	61
711	1870	1931	1992	2053	2114	2175	2236	2297	2358	2419	61
712	2480	2541	2602	2663	2724	2785	2846	2907	2968	3029	61
713	3090	3150	3211	3272	3333	3394	3455	3516	3577	3637	61
714	3698	3759	3820	3881	3941	4002	4063	4124	4185	4245	61
715	85 4306	85 4367	85 4428	85 4488	85 4549	85 4610	85 4670	85 4731	85 4792	85 4852	61
716	4913	4974	5034	5095	5156	5216	5277	5337	5398	5459	61
717	5519	5580	5640	5701	5761	5822	5882	5943	6003	6064	61
718	6124	6185	6245	6306	6366	6427	6487	6548	6608	6668	60
719	6729	6789	6850	6910	6970	7031	7091	7152	7212	7272	60
720	85 7332	85 7393	85 7453	85 7513	85 7574	85 7634	85 7694	85 7755	85 7815	85 7875	60
721	7935	7995	8056	8116	8176	8236	8297	8357	8417	8477	60
722	8537	8597	8657	8718	8778	8838	8898	8958	9018	9078	60
723	9138	9198	9258	9318	9379	9439	9499	9559	9619	9679	60
724	9739	9799	9859	9918	9978	86 0038	86 0098	86 0158	86 0218	86 0278	60
725	86 0338	86 0398	86 0458	86 0518	86 0578	86 0637	86 0697	86 0757	86 0817	86 0877	60
726	0937	0996	1056	1116	1176	1236	1295	1355	1415	1475	60
727	1534	1594	1654	1714	1773	1833	1893	1952	2012	2072	60
728	2131	2191	2251	2310	2370	2430	2489	2549	2608	2668	60
729	2728	2787	2847	2906	2966	3025	3085	3144	3204	3263	60
730	86 3323	86 3382	86 3442	86 3501	68 3561	86 3620	86 3680	86 3739	86 3799	86 3858	59
731	3917	3977	4036	4096	4155	4214	4274	4333	4392	4452	59
732	4511	4570	4630	4689	4748	4808	4867	4926	4985	5045	59
733	5104	5163	5222	5282	5341	5400	5459	5519	5578	5637	59
734	5696	5755	5814	5874	5933	5992	6051	6110	6169	6228	59
735	86 6287	86 6346	86 6405	86 6465	86 6524	86 6583	86 6642	86 6701	86 6760	86 6819	59
736	6878	6937	6996	7055	7114	7173	7232	7291	7350	7409	59
737	7467	7526	7585	7644	7703	7762	7821	7880	7939	7998	59
738	8056	8115	8174	8233	8292	8350	8409	8468	8527	8586	59
739	8644	8703	8762	8821	8879	8938	8997	9056	9114	9173	59
740	86 9232	86 9290	86 9349	86 9408	86 9466	86 9525	86 9584	86 9642	86 9701	86 9760	59
741	9818	9877	9935	9994	87 0053	87 0111	87 0170	87 0228	87 0287	87 0345	59
742	87 0404	87 0462	87 0521	87 0579	0638	0696	0755	0813	0872	0930	58
743	0989	1047	1106	1164	1223	1281	1339	1398	1456	1515	58
744	1573	1631	1690	1748	1806	1865	1923	1981	2040	2098	58
745	87 2156	87 2215	87 2273	87 2331	87 2389	87 2448	87 2506	87 2564	87 2622	87 2681	58
746	2739	2797	2855	2913	2972	3030	3088	3146	3204	3262	58
747	3321	3379	3437	3495	3553	3611	3669	3727	3785	3844	58
748	3902	3960	4018	4076	4134	4192	4250	4308	4366	4424	58
749	4482	4540	4598	4656	4714	4772	4830	4888	4945	5003	58
750	87 5061	87 5119	87 5177	87 5235	87 5293	87 5351	87 5409	87 5466	87 5524	87 5582	58
751	5640	5698	5756	5813	5871	5929	5987	6045	6102	6160	58
752	6218	6276	6333	6391	6449	6507	6564	6622	6680	6737	58
753	6795	6853	6910	6968	7026	7083	7141	7199	7256	7314	58
754	7371	7429	7487	7544	7602	7659	7717	7774	7832	7889	58
755	87 7947	87 8004	87 8062	87 8119	87 8177	87 8234	87 8292	87 8349	87 8407	87 8464	57
756	8522	8579	8637	8694	8752	8809	8866	8924	8981	9039	57
757	9096	9153	9211	9268	9325	9383	9440	9497	9555	9612	57
758	9669	9726	9784	9841	9898	9956	88 0013	88 0070	88 0127	88 0185	57
759	88 0242	88 0299	88 0356	88 0413	88 0471	88 0528	0585	0642	0699	0756	57
N.	0	1	2	3	4	5	6	7	8	9	D.

Digitized by Google

N.	0	1	2	3	4	5	6	7	8	9	D.
760	88 0814	88 0871	88 0928	88 0985	88 1042	88 1099	88 1156	88 1213	88 1271	88 1328	57
761	1385	1442	1499	1556	1613	1670	1727	1784	1841	1898	57
762	1955	2012	2069	2126	2183	2240	2297	2354	2411	2468	57
763	2525	2581	2638	2695	2752	2809	2866	2923	2980	3037	57
764	3093	3150	3207	3264	3321	3377	3434	3491	3548	3605	57
765	88 3661	88 3718	88 3775	88 3832	88 3888	88 3945	88 4002	88 4059	88 4115	88 4172	57
766	4229	4285	4342	4399	4455	4512	4569	4625	4682	4739	57
767	4795	4852	4909	4965	5022	5078	5135	5192	5248	5305	57
768	5361	5418	5474	5531	5587	5644	5700	5757	5813	5870	57
769	5926	5983	6039	6096	6152	6209	6265	6321	6378	6434	56
770	88 6491	88 6547	88 6604	88 6660	88 6716	88 6773	88 6829	88 6885	88 6942	88 6998	56
771	7054	7111	7167	7223	7280	7336	7392	7449	7505	7561	56
772	7617	7674	7730	7786	7842	7898	7955	8011	8067	8123	56
773	8179	8236	8292	8348	8404	8460	8516	8573	8629	8685	56
774	8741	8797	8853	8909	8965	9021	9077	9134	9190	9246	56
775	88 9302	88 9358	88 9414	88 9470	88 9526	88 9582	88 9638	88 9694	88 9750	88 9806	56
776	9862	9918	9974	89 0030	89 0086	89 0141	89 0197	89 0253	89 0309	89 0365	56
777	89 0421	89 0477	89 0533	0589	0645	0700	0756	0812	0868	0924	56
778	0980	1035	1091	1147	1203	1259	1314	1370	1426	1482	56
779	1537	1593	1649	1705	1760	1816	1872	1928	1983	2039	56
780	89 2095	89 2150	89 2206	89 2262	89 2317	89 2373	89 2429	89 2484	89 2540	89 2595	56
781	2651	2707	2762	2818	2873	2929	2985	3040	3096	3151	56
782	3207	3262	3318	3373	3429	3484	3540	3595	3651	3706	56
783	3762	3817	3873	3928	3984	4039	4094	4150	4205	4261	55
784	4316	4371	4427	4482	4538	4593	4648	4704	4759	4814	55
785	89 4870	89 4925	89 4980	89 5036	89 5091	89 5146	89 5201	89 5257	89 5312	89 5367	55
786	5423	5478	5533	5588	5644	5699	5754	5809	5864	5920	55
787	5975	6030	6085	6140	6195	6251	6306	6361	6416	6471	55
788	6526	6581	6636	6692	6747	6802	6857	6912	6967	7022	55
789	7077	7132	7187	7242	7297	7352	7407	7462	7517	7572	55
790	89 7627	89 7682	89 7737	89 7792	89 7847	89 7902	89 7957	89 8012	89 8067	89 8122	55
791	8176	8231	8286	8341	8396	8451	8506	8561	8615	8670	55
792	8725	8780	8835	8890	8944	8999	9054	9109	9164	9218	55
793	9273	9328	9383	9437	9492	9547	9602	9656	9711	9766	55
794	9821	9875	9930	9985	90 0039	90 0094	90 0149	90 0203	90 0258	90 0312	55
795	90 0367	90 0422	90 0476	90 0531	90 0586	90 0640	90 0695	90 0749	90 0804	90 0859	55
796	0913	0968	1022	1077	1131	1186	1240	1295	1349	1404	55
797	1458	1513	1567	1622	1676	1731	1785	1840	1894	1948	54
798	2003	2057	2112	2166	2221	2275	2329	2384	2438	2492	54
799	2547	2601	2655	2710	2764	2818	2873	2927	2981	3036	54
800	90 3090	90 3144	90 3199	90 3253	90 3307	90 3361	90 3416	90 3470	90 3524	90 3578	54
801	3633	3687	3741	3795	3849	3904	3958	4012	4066	4120	54
802	4174	4229	4283	4337	4391	4445	4499	4553	4607	4661	54
803	4716	4770	4824	4878	4932	4986	5040	5094	5148	5202	54
804	5256	5310	5364	5418	5472	5526	5580	5634	5688	5742	54
805	90 5796	90 5850	90 5904	90 5958	90 6012	90 6066	90 6119	90 6173	90 6227	90 6281	54
806	6335	6389	6443	6497	6551	6604	6658	6712	6766	6820	54
807	6874	6927	6981	7035	7089	7143	7196	7250	7304	7358	54
808	7411	7465	7519	7573	7626	7680	7734	7787	7841	7895	54
809	7949	8002	8056	8110	8163	8217	8270	8324	8378	8431	54
810	90 8485	90 8539	90 8592	90 8646	90 8699	90 8753	90 8807	90 8860	90 8914	90 8967	54
811	9021	9074	9128	9181	9235	9289	9342	9396	9449	9503	54
812	9556	9610	9663	9716	9770	9823	9877	9930	9984	91 0037	53
813	91 0091	91 0144	91 0197	91 0251	91 0304	91 0358	91 0411	91 0464	91 0518	0571	53
814	0624	0678	0731	0784	0838	0891	0944	0998	1051	1104	53
815	91 1158	91 1211	91 1264	91 1317	91 1371	91 1424	91 1477	91 1530	91 1584	91 1637	53
816	1690	1743	1797	1850	1903	1956	2009	0263	2116	2169	53
817	2222	2275	2328	2381	2435	2488	2541	2594	2647	2700	53
818	2753	2806	2859	2913	2966	3019	3072	3125	3178	3231	53
819	3284	3337	3390	3443	3496	3549	3602	3655	3708	3761	53
N.	0	1	2	3	4	5	6	7	8	9	D.

Digitized by Google

N.	0	1	2	3	4	5	6	7	8	9	D.
820	91 3814	91 3867	91 3920	91 3973	91 4026	91 4079	91 4132	91 4184	91 4237	91 4290	53
821	4343	4396	4449	4502	4555	4608	4660	4713	4766	4819	53
822	4872	4925	4977	5030	5083	5136	5189	5241	5294	5347	53
823	5400	5453	5505	5558	5611	5664	5716	5769	5822	5875	53
824	5927	5980	6033	6085	6138	6191	6243	6296	6349	6401	53
825	91 6454	91 6507	91 6559	91 6612	91 6664	91 6717	91 6770	91 6822	91 6875	91 6927	53
826	6980	7033	7085	7138	7190	7243	7295	7348	7400	7453	53
827	7506	7558	7611	7663	7716	7768	7820	7873	7925	7978	52
828	8030	8083	8135	8188	8240	8293	8345	8397	8450	8502	52
829	8555	8607	8659	8712	8764	8816	8869	8921	8973	9026	52
830	91 9078	91 9130	91 9183	91 9235	91 9287	91 9340	91 9392	91 9444	91 9496	91 9549	52
831	9601	9653	9706	9758	9810	9862	9914	9967	92 0019	92 0071	52
832	92 0123	92 0176	92 0228	92 0280	92 0332	92 0384	92 0436	92 0489	0541	0593	52
833	0645	0697	0749	0801	0853	0906	0958	1010	1062	1114	52
834	1166	1218	1270	1322	1374	1426	1478	1530	1582	1634	52
835	92 1686	92 1738	92 1790	92 1842	92 1894	92 1946	92 1998	92 2050	92 2102	92 2154	52
836	2206	2258	2310	2362	2414	2466	2518	2570	2622	2674	52
837	2725	2777	2829	2881	2933	2985	3037	3089	3140	3192	52
838	3244	3296	3348	3399	3451	3503	3555	3607	3658	3710	52
839	3762	3814	3865	3917	3969	4021	4072	4124	4176	4228	52
840	92 4279	92 4331	92 4383	92 4434	92 4486	92 4538	92 4589	92 4641	92 4693	92 4744	52
841	4796	4848	4899	4951	5003	5054	5106	5157	5209	5261	52
842	5312	5364	5415	5467	5518	5570	5621	5673	5725	5776	52
843	5828	5879	5931	5982	6034	6085	6137	6188	6240	6291	51
844	6342	6394	6445	6497	6548	6600	6651	6702	6754	6805	51
845	92 6857	92 6908	92 6959	92 7011	92 7062	92 7114	92 7165	92 7216	92 7268	92 7319	51
846	7370	7422	7473	7524	7576	7627	7678	7730	7781	7832	51
847	7883	7935	7986	8037	8088	8140	8191	8242	8293	8345	51
848	8396	8447	8498	8549	8601	8652	8703	8754	8805	8857	51
849	8908	8959	9010	9061	9112	9163	9215	9266	9317	9368	51
850	92 9419	92 9470	92 9521	92 9572	92 9623	92 9674	92 9725	92 9776	92 9827	92 9879	51
851	9930	9981	93 0032	93 0083	93 0134	93 0185	93 0236	93 0287	93 0338	93 0389	51
852	93 0440	93 0491	0542	0592	0643	0694	0745	0796	0847	0898	51
853	0949	1000	1051	1102	1153	1204	1254	1305	1356	1407	51
854	1458	1509	1560	1610	1661	1712	1763	1814	1865	1915	51
855	93 1966	93 2017	93 2068	93 2118	93 2169	93 2220	93 2271	93 2322	93 2372	93 2423	51
856	2474	2524	2575	2626	2677	2727	2778	2829	2879	2930	51
857	2981	3031	3082	3133	3183	3234	3285	3335	3386	3437	51
858	3487	3538	3589	3639	3690	3740	3791	3841	3892	3943	51
859	3993	4044	4094	4145	4195	4246	4296	4347	4397	4448	51
860	93 4498	93 4549	93 4599	93 4650	93 4700	93 4751	93 4801	93 4852	93 4902	93 4953	50
861	5003	5054	5104	5154	5205	5255	5306	5356	5406	5457	50
862	5507	5558	5608	5658	5709	5759	5809	5860	5910	5960	50
863	6011	6061	6111	6162	6212	6262	6313	6363	6413	6463	50
864	6514	6564	6614	6665	6715	6765	6815	6865	6916	6966	50
865	93 7016	93 7066	93 7117	93 7167	93 7217	93 7267	93 7317	93 7367	93 7418	93 7468	50
866	7518	7568	7618	7668	7718	7769	7819	7869	7919	7969	50
867	8019	8069	8119	8169	8219	8269	8320	8370	8420	8470	50
868	8520	8570	8620	8670	8720	8770	8820	8870	8920	8970	50
869	9020	9070	9120	9170	9220	9270	9320	9369	9419	9469	50
870	93 9519	93 9569	93 9619	93 9669	93 9719	93 9769	93 9819	93 9869	93 9918	93 9968	50
871	94 0018	94 0068	94 0118	94 0168	94 0218	94 0267	94 0317	94 0367	94 0417	94 0467	50
872	0516	0566	0616	0666	0716	0765	0815	0865	0915	0964	50
873	1014	1064	1114	1163	1213	1263	1313	1362	1412	1462	50
874	1511	1561	1611	1660	1710	1760	1809	1859	1909	1958	50
875	94 2008	94 2058	94 2107	94 2157	94 2207	94 2256	94 2306	94 2355	94 2405	94 2455	50
876	2504	2554	2603	2653	2702	2752	2801	2851	2901	2950	50
877	3000	3049	3099	3148	3198	3247	3297	3346	3396	3445	49
878	3495	3544	3593	3643	3692	3742	3791	3841	3890	3939	49
879	3989	4038	4088	4137	4186	4236	4285	4335	4384	4433	49
N.	0	1	2	3	4	5	6	7	8	9	D.

Digitized by Google

N.	0	1	2	3	4	5	6	7	8	9	D.
880	94 4483	94 4532	94 4581	94 4631	94 4680	94 4729	94 4779	94 4828	94 4877	94 4927	49
881	4976	5025	5074	5124	5173	5222	5272	5321	5370	5419	49
882	5469	5518	5567	5616	5665	5715	5764	5813	5862	5912	49
883	5961	6010	6059	6108	6157	6207	6256	6305	6354	6403	49
884	6452	6501	6551	6600	6649	6698	6747	6796	6845	6894	49
885	94 6943	94 6992	94 7041	94 7090	94 7140	94 7189	94 7238	94 7287	94 7336	94 7385	49
886	7434	7483	7532	7581	7630	7679	7728	7777	7826	7875	49
887	7924	7973	8022	8070	8119	8168	8217	8266	8315	8364	49
888	8413	8462	8511	8560	8609	8657	8706	8755	8804	8853	49
889	8902	8951	8999	9048	9097	9146	9195	9244	9292	9341	49
890	94 9390	94 9439	94 9488	94 9536	94 9585	94 9634	94 9683	94 9731	94 9780	94 9829	49
891	9878	9926	9975	95 0024	95 0073	95 0121	95 0170	95 0219	95 0267	95 0316	49
892	95 0365	95 0414	95 0462	0511	0560	0608	0657	0706	0754	0803	49
893	0851	0900	0949	0997	1046	1095	1143	1192	1240	1289	49
894	1338	1386	1435	1483	1532	1580	1629	1677	1726	1775	49
895	95 1823	95 1872	95 1920	95 1969	95 2017	95 2066	95 2114	95 2163	95 2211	95 2260	48
896	2308	2356	2405	2453	2502	2550	2599	2647	2696	2744	48
897	2792	2841	2889	2938	2986	3034	3083	3131	3180	3228	48
898	3276	3325	3373	3421	3470	3518	3566	3615	3663	3711	48
899	3760	3808	3856	3905	3953	4001	4049	4098	4146	4194	48
900	95 4243	95 4291	95 4339	95 4387	95 4435	95 4484	95 4532	95 4580	95 4628	95 4677	48
901	4725	4773	4821	4869	4918	4966	5014	5062	5110	5158	48
902	5207	5255	5303	5351	5399	5447	5495	5543	5592	5640	48
903	5688	5736	5784	5832	5880	5928	5976	6024	6072	6120	48
904	6168	6216	6265	6313	6361	6409	6457	6505	6553	6601	48
905	95 6649	95 6697	95 6745	95 6793	95 6840	95 6888	95 6936	95 6984	95 7032	95 7080	48
906	7128	7176	7224	7272	7320	7368	7416	7464	7512	7559	48
907	7607	7655	7703	7751	7799	7847	7894	7942	7990	8038	48
908	8086	8134	8181	8229	8277	8325	8373	8421	8468	8516	48
909	8564	8612	8659	8707	8755	8803	8850	8898	8946	8994	48
910	95 9041	95 9089	95 9137	95 9185	95 9232	95 9280	95 9328	95 9375	95 9423	95 9471	48
911	9518	9566	9614	9661	9709	9757	9804	9852	9900	9947	48
912	9995	96 0042	96 0090	96 0138	96 0185	96 0233	96 0280	96 0328	96 0376	96 0423	48
913	96 0471	0518	0566	0613	0661	0709	0756	0804	0851	0899	48
914	0946	0994	1041	1089	1136	1184	1231	1279	1326	1374	48
915	96 1421	96 1469	96 1516	96 1563	96 1611	96 1658	96 1706	96 1753	96 1801	96 1848	47
916	1895	1943	1990	2038	2085	2132	2180	2227	2275	2322	47
917	2369	2417	2464	2511	2559	2606	2653	2701	2748	2795	47
918	2843	2890	2937	2985	3032	3079	3126	3174	3221	3268	47
919	3316	3363	3410	3457	3504	3552	3599	3646	3693	3741	47
920	96 3788	96 3835	96 3882	96 3929	96 3977	96 4024	96 4071	96 4118	96 4165	96 4212	47
921	4260	4307	4354	4401	4448	4495	4542	4590	4637	4684	47
922	4731	4778	4825	4872	4919	4966	5013	5061	5108	5155	47
923	5202	5249	5296	5343	5390	5437	5484	5531	5578	5625	47
924	5672	5719	5766	5813	5860	5907	5954	6001	6048	6095	47
925	96 6142	96 6189	96 6236	96 6283	96 6329	96 6376	96 6423	96 6470	96 6517	96 6564	47
926	6611	6658	6705	6752	6799	6845	6892	6939	6986	7033	47
927	7080	7127	7173	7220	7267	7314	7361	7408	7454	7501	47
928	7548	7595	7642	7688	7735	7782	7829	7875	7922	7969	47
929	8016	8062	8109	8156	8203	8249	8296	8343	8390	8436	47
930	96 8483	96 8530	96 8576	96 8623	96 8670	96 8716	96 8763	96 8810	96 8856	96 8903	47
931	8950	8996	9043	9090	9136	9183	9229	9276	9323	9369	47
932	9416	9463	9509	9556	9602	9649	9695	9742	9789	9835	47
933	9882	9928	9975	97 0021	97 0068	97 0114	97 0161	97 0207	97 0254	97 0300	47
934	97 0347	97 0393	97 0440	0486	0533	0579	0626	0672	0719	0765	46
935	97 0812	97 0858	97 0904	97 0951	97 0997	97 1044	97 1090	97 1137	97 1183	97 1229	46
936	1276	1322	1369	1415	1461	1508	1554	1601	1647	1693	46
937	1740	1786	1832	1879	1925	1971	2018	2064	2110	2157	46
938	2203	2249	2295	2342	2388	2434	2481	2527	2573	2619	46
939	2666	2712	2758	2804	2851	2897	2943	2989	3035	3082	46
N.	0	1	2	3	4	5	6	7	8	9	D.

Digitized by Google

N.	0	1	2	3	4	5	6	7	8	9	D.
940	97 3128	97 3174	97 3220	97 3266	97 3313	97 3359	97 3405	97 3451	97 3497	97 3543	46
941	3590	3636	3682	3728	3774	3820	3866	3913	3959	4005	46
942	4051	4097	4143	4189	4235	4281	4327	4374	4420	4466	46
943	4512	4558	4604	4650	4696	4742	4788	4834	4880	4926	46
944	4972	5018	5064	5110	5156	5202	5248	5294	5340	5386	46
945	97 5432	97 5478	97 5524	97 5570	97 5616	97 5662	97 5707	97 5753	97 5799	97 5845	46
946	5891	5937	5983	6029	6075	6121	6167	6212	6258	6304	46
947	6350	6396	6442	6488	6533	6579	6625	6671	6717	6763	46
948	6808	6854	6900	6946	6992	7037	7083	7129	7175	7220	46
949	7266	7312	7358	7403	7449	7495	7541	7586	7632	7678	46
950	97 7724	97 7769	97 7815	97 7861	97 7906	97 7952	97 7998	97 8043	97 8089	97 8135	46
951	8181	8226	8272	8317	8363	8409	8454	8500	8546	8591	46
952	8637	8683	8728	8774	8819	8865	8911	8956	9002	9047	46
953	9093	9138	9184	9230	9275	9321	9366	9412	9457	9503	46
954	9548	9594	9639	9685	9730	9776	9821	9867	9912	9958	46
955	98 0003	98 0049	98 0094	98 0140	98 0185	98 0231	98 0276	98 0322	98 0367	98 0412	45
956	0458	0503	0549	0594	0640	0685	0730	0776	0821	0867	45
957	0912	0957	1003	1048	1093	1139	1184	1229	1275	1320	45
958	1366	1411	1456	1501	1547	1592	1637	1683	1728	1773	45
959	1819	1864	1909	1954	2000	2045	2090	2135	2181	2226	45
960	98 2271	98 2316	98 2362	98 2407	98 2452	98 2497	98 2543	98 2588	98 2633	98 2678	45
961	2723	2769	2814	2859	2904	2949	2994	3040	3085	3130	45
962	3175	3220	3265	3310	3356	3401	3446	3491	3536	3581	45
963	3626	3671	3716	3762	3807	3852	3897	3942	3987	4032	45
964	4077	4122	4167	4212	4257	4302	4347	4392	4437	4482	45
965	98 4527	98 4572	98 4617	98 4662	98 4707	98 4752	98 4797	98 4842	98 4887	98 4932	45
966	4977	5022	5067	5112	5157	5202	5247	5292	5337	5382	45
967	5426	5471	5516	5561	5606	5651	5696	5741	5786	5830	45
968	5875	5920	5965	6010	6055	6100	6144	6189	6234	6279	45
969	6324	6369	6413	6458	6503	6548	6593	6637	6682	6727	45
970	98 6772	98 6817	98 6861	98 6906	98 6951	98 6996	98 7040	98 7085	98 7130	98 7175	45
971	7219	7264	7309	7353	7398	7443	7488	7532	7577	7622	45
972	7666	7711	7756	7800	7845	7890	7934	7979	8024	8068	45
973	8113	8157	8202	8247	8291	8336	8381	8425	8470	8514	45
974	8559	8604	8648	8693	8737	8782	8826	8871	8916	8960	45
975	98 9005	98 9049	98 9094	98 9138	98 9183	98 9227	98 9272	98 9316	98 9361	98 9405	45
976	9450	9494	9539	9583	9628	9672	9717	9761	9806	9850	44
977	9895	9939	9983	99 0028	99 0072	99 0117	99 0161	99 0206	99 0250	99 0294	44
978	99 0339	99 0383	99 0428	0472	0516	0561	0605	0650	0694	0738	44
979	0783	0827	0871	0916	0960	1004	1049	1093	1137	1182	44
980	99 1226	99 1270	99 1315	99 1359	99 1403	99 1448	99 1492	99 1536	99 1580	99 1625	44
981	1669	1713	1758	1802	1846	1890	1935	1979	2023	2067	44
982	2111	2156	2200	2244	2288	2333	2377	2421	2465	2509	44
983	2554	2598	2642	2686	2730	2774	2819	2863	2907	2951	44
984	2995	3039	3083	3127	3172	3216	3260	3304	3348	3392	44
985	99 3436	99 3480	99 3524	99 3568	99 3613	99 3657	99 3701	99 3745	99 3789	99 3833	44
986	3877	3921	3965	4009	4053	4097	4141	4185	4229	4273	44
987	4317	4361	4405	4449	4493	4537	4581	4625	4669	4713	44
988	4757	4801	4845	4889	4933	4977	5021	5065	5108	5152	44
989	5196	5240	5284	5328	5372	5416	5460	5504	5547	5591	44
990	99 5635	99 5679	99 5723	99 5767	99 5811	99 5854	99 5898	99 5942	99 5986	99 6030	44
991	6074	6117	6161	6205	6249	6293	6337	6380	6424	6468	44
992	6512	6555	6599	6643	6687	6731	6774	6818	6862	6906	44
993	6949	6993	7037	7080	7124	7168	7212	7255	7299	7343	44
994	7386	7430	7474	7517	7561	7605	7648	7692	7736	7779	44
995	99 7823	99 7867	99 7910	99 7954	99 7998	99 8041	99 8085	99 8129	99 8172	99 8216	44
996	8259	8303	8347	8390	8434	8477	8521	8564	8608	8652	44
997	8695	8739	8782	8826	8869	8913	8956	9000	9043	9087	44
998	9131	9174	9218	9261	9305	9348	9392	9435	9479	9522	44
999	9565	9609	9652	9696	9739	9783	9826	9870	9913	9957	43
N.	0	1	2	3	4	5	6	7	8	9	D.

Digitized by Google

Digitized by Google

Digitized by Google

89089674949

B89089674949A

This book may be kept

FOURTEEN DAYS

A fine of TWO CENTS will be charged for each day the book is kept overtime.

19 Oc'49			
~~7Mr'52~~			

DENCO-221-B

Digitized by Google



Digitized by Google

8908967494 9

b89089674949a

Digitized by Google